

Dear Prof. Dr. Frank Hagedorn,

On behalf of my co-authors, we extend our sincere gratitude for your helpful reviews and in facilitating the review of our manuscript, bg-2018-221. We have now incorporated all the changes we stipulated in our answers to the reviewers' comments. Additionally, from your suggestion:

Please also incorporate 'tree species' more explicitly into the final version of the manuscript. You nicely clarified that 'nutrient demand of vegetation and vegetation structure of the reference land-use are not the dominant control on leaching fluxes', but the reviewer asked for 'tree species'. I am aware that tree species and 'vegetation' are interlinked but you should clearly address/write that you do not expect that the different tree species composition between the sites was of minor importance for the leaching fluxes.

we have also addressed this in L443-449 of the revised manuscript, as also mentioned in our answers to Reviewer 2's specific comment #2.

For ease in reference, our answers to the reviewers' comments are now provided with the line numbers where the changes in our revised manuscript are reflected. All the line numbers are based on the revised manuscript (not on the marked-up version where the line numbers change).

We hope that our revisions will satisfy your and the reviewers' questions and the standards of Biogeosciences. We look forward to hearing back from you. If there are any questions regarding our manuscript, I would be happy to clarify.

Sincerely yours,

Marife D. Corre

Point-by-point response to the reviews and a list of all relevant changes made in the manuscript

RC1 – Dr. Yit Arn Teh

Author's response:

First, we greatly appreciate the very detailed comments and suggestions of Dr. Teh. These help improve the clarity and broaden the perspective of our Discussion. All the comments of Dr. Teh are incorporated into our revisions. We describe below how we have addressed his comments. All the line numbers we referred to in our revision are based on the revised manuscript (not on the marked-up version where the line numbers change).

General remarks and suggestions:

1. First, I think it may be worthwhile re-organizing the information in the discussion around the major findings, listing the top-level or most important findings first. The current structure of the discussion generally follows the order in which the results are reported, but there could be some value in arranging information according to the most ground-breaking or high impact results, in order to maximise the impact of the most important findings on the reader. Structuring a discussion in this way can be especially effective for data-rich papers like this one, because the discussion sections for data-rich papers can sometimes become quite large and extensive, and it is possible for key messages to get lost due to the volume of information covered.

Author's response:

We agree to this suggestion.

Author's changes in the manuscript:

We restructured the Discussion in the following:
Section 4.2– focuses first on the reference land uses.

L430-434, 452-453 - We put topic sentence in the beginning of the paragraphs to put first the high-impact results (previous L428-432 is condensed into a topic sentence; previous L447-448 is revised into a topic sentence). We minimized referencing back to the tables or figures with specific parameters, unless necessary. We streamlined every sentence to limit to the most convincing Results (previous L443-446 is deleted).

L449-451 - At the end of the paragraph, we give a take-home message (previous L458-460 is moved up to this place).

Section 4.3 – now titled land-use change effects.

The first paragraph focuses on the unfertilized rubber plantations and the second paragraph on the fertilized oil palm plantations, instead of separating the latter in the previous section 4.4.

Although we emphasized in the previous manuscript version that the smallholder rubber plantations are not fertilized (the common practice of the smallholders in the area, at least during our study years of 2012-2013), we now highlighted this main difference in the soil management of the rubber and oil palm plantations (L469-471, L489-490).

L484-488, L512-514 - We also emphasized that the decreases in leaching losses in this rubber plantations and the increases in leaching losses in fertilized area of the oil palm plantations, as

compared to the reference land uses, were mainly due to their management practices (i.e. without and with soil amendments). Again in each paragraph, we put a topic sentence (previous L465-470 is condensed into a topic sentence) to highlight the most important Results, and at the end of the paragraph a condensed take-home message (L525-528).

2. Second, another topic that is theoretically interesting and also policy-relevant is whether or not the investigators believe that over-fertilization is occurring for the rubber and oil palm systems? To phrase this another way, are the higher nutrient losses for rubber and oil palm because fertilizer inputs exceed plant/ecosystem demand, or because of the transport-reaction properties of the different soil types (e.g. do the exchange properties and rate of physical transport through the soil mean that the soil exchange complex cannot retain some of the added nutrients)? If the answer is the former, then this suggests that growers could be reducing their inputs of some elements. If the answer is the latter, then mitigation options become more complex, because they may require new means of introducing fertilizers to the soil (e.g. slow release fertilizers, organic fertilizers, soil conditioners to enhance CEC, etc.). It would be interesting if the investigators could expand upon this topic further in the discussion.

Author's response:

These are very good suggestions. We take into considerations all these points. Our discussion was geared both on the regulation of soil texture and fertilization rates. We focused on the absence of fertilization (rubber) and low (clay Acrisol, oil palm plantations) versus relatively high fertilization rates (loam Acrisol, oil palm plantations). We did not hone our discussion on exceedance of the nutrient retention capacity of the soils. The reason is because we had 2-5 times lower fertilization rates at our studied smallholder oil palm plantations than the nearby large-scale oil palm plantations, such that it will be very speculative to say that the soil exchange complex are saturated or increasingly unable to retain the added nutrients.

Author's changes in the manuscript:

L469-471 - We emphasized in the revised section 4.3 that the smallholder rubber plantations were not fertilized (at least during our study period of 2012-2013), and this was in part because the price of rubber had gone down at that time (as shown in the Supplementary Fig. 9 of Clough et al. 2016).

L494-497 - In the second paragraph of section 4.3, we also emphasized that the fertilizer application in oil palm plantations, despite at very low rates, resulted in increased nutrient leaching losses compared to the reference land uses, particularly in the loam Acrisol soil.

L529-535 - We stressed in the 4th paragraph of section 4.3 that the higher rates of fertilizer application in large-scale plantations than in smallholders imply for a need to optimize fertilization rate in order to minimize environmental effect while maintaining production level.

We also revised the previous L554-556 in Conclusion to this:

Management practices to regulate leaching losses are possibly more pressing for large-scale oil palm plantations, which have 2-5 times higher fertilization rates and may have a larger impact on ground water quality than the smallholders (L550-555). Process-based models, used to predict yield and associated environmental footprint of these tree cash crop plantations, should reflect the

differences in soil management (e.g., absence or low vs. high fertilization rates, weed control) between smallholder and large-scale plantations (L555-558).

3. Third, two aqueous fluxes not included in this study are throughfall and stemflow. This observation is not meant as a criticism per se, as I fully recognize that this was very comprehensive and in-depth study, and resources are always limited for large-scale field experiments like this one. However, it would be useful if the investigators could comment on whether they think that differences in throughfall and stemflow among the different land-uses could have resulted in differences in nutrient dynamics and loss? Throughfall and stemflow are potentially influenced by factors such as vegetation structure (e.g. plant density), leaf area and tissue chemistry, so it is possible that the different cover types (with different vegetation structure and properties) could have different patterns in throughfall and stemflow, with knock-on effects for soil nutrient dynamics.

Author's response:

This is a very important point. We incorporated our views on this aspect in section 4.1 last paragraph. In terms of magnitude, the highest throughfall nutrient depositions (from peat soils, influenced by land-clearing fires in Kalimantan; Ponette-Gonzales et al., 2016) are still much lower (<1-3%) than the extant soil-N cycling rates and nutrient stocks in the top 0.1-m soil at our sites. The effects of atmospheric nutrient deposition may not be on how much this has added to the soil nutrient levels but on whether or not the receiving ecosystem can serve as a sink and is able to buffer its other cascading effects (e.g. acidification).

Author's changes in the manuscript:

To keep the manuscript in the same length, previous L411-417 was shortened into one sentence. To incorporate these points raised by Dr. Teh above, we replaced the previous L418-425 with this:

L419-427 - From a peatland site in Kalimantan, influenced by land-clearing fires, throughfall nutrient depositions (19-22 kg N, 6-11 kg P, 25-44 kg S ha⁻¹ yr⁻¹) are larger than those from bulk precipitation, indicating large contribution from dry deposition (Ponette-Gonzales et al., 2016). Total (dry + wet) nutrient depositions in our study region could be larger than the values from bulk precipitation. Such high atmospheric nutrient deposition may have fertilizing or polluting effect, depending on whether or not the receiving ecosystem is a sink and is able to buffer its other cascading effects (e.g., acidification). Additionally, atmospheric redistribution of nutrients in areas with widespread land-use conversion and intensification may have unforeseen effects on down-wind and down-stream ecosystems (e.g., Bragazza et al., 2016; Sundarambal et al., 2010).

These new references are added in the reference list:

Bragazza, L., Freeman, C., Jones, T., Rydin, H., Limpens, J., Fenner, N., Ellis, T., Gerdol, R., Hájek, M., Hájek, T., Iacumin, P., Kutnar, L., Tahvanainen, T., and Toberman, H.: Atmospheric nitrogen deposition promotes carbon loss from peat bogs, *Proc. Natl. Acad. Sci. U.S.A.*, 103, 19386-19389, <https://doi.org/10.1073/pnas.0606629104>, 2006.
Ponette-González, A.G., LisaMcCurran, L.M., Pittman, A.M., Carlson, K.M., Steele, B.G., Ratnasari, D., Mujiman, and Weathers, K.C.: Biomass burning drives atmospheric nutrient

redistribution within forested peatlands in Borneo, *Environ. Res. Lett.*, 11, 085003, <https://doi.org/10.1088/1748-9326/11/8/085003>, 2016.

Sundarambal, P., Balasubramanian, R., Tkalich, P., and He, J.: Impact of biomass burning on ocean water quality in Southeast Asia through atmospheric deposition: field observations, *Atmos. Chem. Phys.*, 10, 11323–11336, <https://doi.org/10.5194/acp-10-11323-2010>, 2010.

SPECIFIC COMMENTS:

1. Lines 49-51: Provide information for wider context: It is worthwhile emphasizing here that smallholdings are very common through SE Asia, and account for approximately 40% of the land under production throughout the region. Therefore, while the smallholdings in Jambi may represent a larger proportion of land area than elsewhere in SE Asia, smallholdings are common and thus important to understand.

Author's response:

We incorporated this suggestion.

Author's changes in the manuscript:

L51-53 - The expansion of rubber and oil palm plantations has increased the income of Jambi, in particular the smallholder farmers (Clough et al., 2016; Rist et al., 2010), which account 99 % of rubber and 62 % of oil palm landholdings in the Jambi Province. In the whole of Indonesia, 85 % of rubber and 40 % of oil palm plantations are smallholders (DGEC, 2017).

DGEC (Directorate General of Estate Crops), Tree crop estate statistics of Indonesia 2015-2017: Palm oil and rubber, Indonesian Ministry of Agriculture, 2017, <http://ditjenbun.pertanian.go.id/tinymcpuk/gambar/file/statistik/2017/Kelapa-Sawit-2015-2017.pdf>, .../Karet-2015-2017.pdf.

2. Line 147-150: Consider re-phrasing the description of the fertilization rates, as the current wording makes it a bit more difficult to understand. One option may be to breakup this sentence into two shorter sentences; one referring to the clay Acrisol and the other to the loam Acrisol.

Author's response:

We take this in our revision.

Author's changes in the manuscript:

L150-152 - Fertilization rates were 48 kg N, 21 kg P and 40 kg K ha⁻¹ yr⁻¹ in the clay Acrisol soil, whereas these were 88 kg N, 38 kg P ha⁻¹ yr⁻¹ and 157 kg K ha⁻¹ yr⁻¹ (accompanied by Cl input of 143 kg Cl ha⁻¹ yr⁻¹) in the loam Acrisol soil.

3. Line 161: Minor question or point for clarification: Do the authors have any insight as to where nutrient-acquiring roots proliferate in this system? Is it possible that sampling 1.3-1.5 m from the palm could slightly overestimate the rate of leaching loss? Oil palms tend to show the highest

density of roots within 1 m of the plant stem; therefore, it is possible that by sampling outside of this region the investigators may underestimate plant uptake or overestimate leaching. Arguably, however, it is not clear if all the roots within 1 m of the palm stem are active or specialized for nutrient uptake, i.e. many of these roots may be dead or not directly involved in nutrient acquisition. Moreover, if the growers' practice is to apply fertilizer 1.3-1.5 m from the stem, then it is likely that this sampling scheme is likely to best represent actual trends in leaching. It is also possible that the roots produced 1.3-1.5 m from the stem are tracking nutrient availability and are specialized for nutrient uptake.

Author's response:

From another study (conducted by another group in this collaborative research center) that measured root distribution in the same smallholder oil palm plantations, there were no significant correlations between root mass distribution with distance to palms. This was attributed to the facts that these are mature plantations (12-16 yrs old, except one site that was 9 yrs old) and the weeding practices in smallholder plantations were not intensive (2 times per year only) and hence the ground was almost always covered with undergrowth. We think that we did not over-represent the leaching losses from the fertilized area as these values were averaged with the leaching losses from under the frond stacks to get a plot-scale estimate for an oil palm plantation.

4. Line 163: Did the growers plant any understory plants for erosion control? If so, did the authors sample from these areas too? Although the biomass and uptake capacity of these herbaceous plants is likely to be low relative to mature palms, leaching patterns are likely to be different from unvegetated areas.

Author's response:

In these smallholder oil palm plantations, the ground vegetation was that from natural regrowth after the 2-times weeding per year. The ground was mostly covered with understory plants for most part of the year.

5. Lines 268-279: Do the investigators have an estimate for the nutrient input from throughfall and stemflow? If these data do not exist, is it possible to constrain these values in the model from similar systems? While rain water provides a useful end-member with which to estimate the nutrient content of "external" moisture inputs, it is possible that dry deposition of nutrients and leaching from aboveground plant parts could contribute to the nutrient input to soil. Especially if this region is near local sources of N pollution, it is possible that throughflow/stemflow could make a contribution to the overall N load to the soil.

Author's response:

We did not measure stem flow and throughfall, and there are no data for stem flow and throughfall for these land uses for Jambi or Sumatra that we are aware of. It is likely that stem flow + throughfall is larger than from bulk precipitation in areas with large dry deposition from biomass burning. In terms of magnitude, those high throughfall nutrient depositions from heavily fire-impacted peatlands in Kalimantan (Ponette-González et al., 2016) are still much lower than extant N cycling rates and macronutrient stocks in the soil at our sites. As nutrients deposited into a system will eventually be incorporated into the soil-plant cycling, changes in leaching losses are

ultimately reflecting how efficient the system (soil, biota and vegetation) is in retaining the nutrients from both external sources and internal cycling.

Author's changes in the manuscript:

Please see our answers to reviewer's major comment 3 above.

6. Lines 317-320: What are the comparable values for ET, run-off and drainage for rubber and oil palm systems?

Author's response:

We provide this information.

Author's changes in the manuscript:

L320-322 - In rubber and oil palm, modelled annual ET was 30-32 %, runoff was 22-31 %, and drainage was 37-47 % of annual precipitation.

7. Lines 395-534: Given that the authors introduce testable hypotheses in the introduction, I think it's important to "close the circle" by referencing these hypotheses in the discussion, and confirming if the authors' findings supported or falsified their hypotheses.

Author's response:

We agree with the reviewer.

Author's changes in the manuscript:

We re-structured the Discussion according to the 1st and 2nd major suggestions above. In the Conclusion, we closed the circle by linking our findings to our hypotheses (L540-544).

8. Line 441: Further clarification required re: the phrase "higher rates of soil NH₄⁺ cycling." For those who have not yet read Allen et al. (2015), does this phrase mean that the rate of NH₄⁺ mineralization is greater, gross production and uptake of NH₄⁺ is greater, or that the overall turnover of NH₄⁺ is greater?

Author's response:

Gross production and immobilization of NH₄⁺ were positively correlated and both rates are large, meaning this internal cycling was large and closely-coupled, and was mirrored by low TDN leaching fluxes in the clay than loam Acrisol soils.

Author's changes in the manuscript:

We changed this sentence accordingly (L441-442).

9a. Lines 491-534: One question and one comment: first, given the finding that fertilization is enhancing leaching losses in these smallholder landscapes, do the authors believe that the growers are over-fertilizing? Is the high rate of leaching loss because the plant demand is lower than nutrient supply, or is it because transport factors mean that the nutrients are lost before plants are able to take-up the nutrients? The authors expert assessment directly influences policy and management decisions; if it is an over-fertilization situation (i.e. plant demand \ll nutrient input), then the mitigation option would be to reduce fertilizer inputs. If it is an issue of transport (e.g. ion exchange sites are saturated or movement of soil solution is too rapid for efficient plant uptake), the different mitigation options suggest themselves (e.g. use of slower release fertilizers, or other technologies to reduce nutrient transport through the soil column). The conclusion that soil texture was the dominant influence (lines 528-529) tends to imply that the authors believe the second option is more likely (i.e. rapid transport leads to loss, rather than plant demand \ll nutrient input); however, it would be useful to hear the authors thoughts on this topic given its wider importance for mitigation of nutrient pollution.

Author's response:

These smallholders are not over-fertilizing; please see also our answer to the 2nd major comment above. The high leaching losses from oil palm plantations occurred particularly on the fertilized area around the palm base and were higher in the loam Acrisol soil, which also happened to have a larger fertilization (e.g., 48 vs. 88 kg N/ha/yr, section 2.1), than the clay Acrisol soil. The plant demand, using simply the index of fruit harvest export (72-96 kg N/ha/yr; Kotowska et al. 2015), was certainly higher than the fertilization rates of the smallholders, whose low fertilization rates were largely determined by their resources of being able to afford the cost of fertilizers. Thus, our discussion was focused more on the regulation of soil texture and fertilization rate rather than on the exceedance of the ecosystem's capacity to retain the added nutrients from fertilizers. The leaching losses that we measured are possibly contributed by both soil texture (not only through adsorption/exchange capacity but also on solute transport) and fertilizer application. We think the role of transport occurred on pulses or time periods when high rainfall occurred following the 2 periods in a year when fertilizers were applied. Unlike, however, N₂O emissions from the soil surface of which temporal pattern following fertilization are clearly manifested (Hassler et al. 2017), this is not the case for leaching losses - probably because transport of solute down to 1.5-m depth (lysimeter sampling) can take days of intermittent rainfall events.

Author's changes in the manuscript:

As to the aspect of our findings' implications to management, we addressed this in the last paragraph of section 4.3.

L529-535 - The fertilization rates in our studied smallholder oil palm plantations were only 2-5 times lower than the nearby large-scale plantations, typically with 230-260 kg N ha⁻¹ yr⁻¹. Our findings, that leaching of TDN and base cations increased and their retention efficiency decreased particularly in the loam Acrisol despite the low fertilization rates (Tables 4 and 5), imply for a need to optimize fertilization rate in large-scale plantations, especially on coarse-texture soils which have low inherent nutrient retention, in order to minimize environmental effect while maintaining production.

9b. My second point is a comment rather than a question. One of the challenges in predicting the behaviour of smallholder systems is that there is potentially a wider diversity of practices and fertilization schemes compared to large-scale industrial plantations. For instance, depending on the relative wealth or resources of individual growers, they may have better access to fertilizers than less fortunate growers. While this does not necessarily take away from the message that the authors are trying to convey here (i.e. that certain types of more “intensive” or “invasive” land-use can show enhanced leaching losses), I think it is useful to discuss this source of potential variance and uncertainty, since it means that we have to develop better process-based models so that we can adequately predict flux from smallholder systems.

Author’s response:

We completely agree to this comment.

Author’s changes in the manuscript:

We added this in the Conclusion.

L555-558 - Process-based models, used to predict yield and associated environmental footprint of these tree cash crop plantations, should reflect the differences in soil management (e.g., absence or low vs. high fertilization rates, weed control) between smallholder and large-scale plantations.’

10. Table and figure legends: Minor pedantic point: throughout the table and figure legends, the authors refer to the loam Acrisol and clay Acrisol as two different “landscapes.” While I do not consider this as problematic as such, I wonder if the phrase “soil orders” or “soil types” may be more intuitive for the reader, given that the reference for these two types of environments are the names of the soil orders?

Author’s response:

Yes, we agree. In the revised version, we changed all these in the text from landscapes to soil types.

RC2 – Dr. K. Fujii

Author's response:

First, we extend our sincere thanks to Dr. Fujii for his insightful suggestions and comments that help improve our manuscript greatly. We describe how we have addressed his comments in our answers below. All the line numbers we referred to in our revision are based on the revised manuscript (not on the marked-up version where the line numbers change).

1. One of major issues is soil classification (Acrisols). Sumatra soils are more or less affected by volcanic ash deposition. Soils are relatively young among Indonesian soils. I am afraid whether the soils studied satisfy Acrisols' low clay activity. Please confirm the soil profile data especially in the Bt horizon. Low CEC/clay is required. In addition, both loam and clay Acrisols contain high contents of clays. Please clarify how two types were separated.

Author's response:

Soil particle size distribution was determined from the three sites (or replicate plots) of each land use within each landscape (which was subsequently classified according to the major soil texture group). In each site, soil samples for particle size analysis was taken from 6 depth intervals within 2-m depth. For the general soil texture classification, we took the values of depth-weighted average for each land-use site, and then the averaged for the 12 land-use sites (4 land uses x 3 sites) for each landscape. Similarly, cation exchange capacity (CEC) was determined from 2 to 5 samples per depth for each land-use site. We also did an oxalate-extraction for Fe and Al, and these characteristics did not satisfy for an Andic property.

Our soil texture classification is based on the averages of the plots in order to come up with a general category of soil texture. The clay area had an average across sites of 48% clay, 27% silt and 25% sand. The loam area had particle size fractions that bordered between loam and (sandy) clay loam, and for ease in writing the classification in the manuscript, we generally termed this as loam (22-32% clay, 25-30% silt and 45-50% sand).

In the clay soils (with more than 40% clay), >8% increase in clay was observed in the subsoil. In the loam soils, the ratio of subsoil % clay to the overlying layer was >1.2. Both of these metrics satisfied the criterion for an Argic horizon. These Argic horizons of our sites has CEC of < 24 cmol_c kg⁻¹ clay and base saturation of <10% (all reported in our earlier publication, Allen et al. 2016).

Author's changes in the manuscript:

As these characteristics were already reported in our earlier publication (Allen et al. 2016), we did not elaborate these in the present manuscript.

However, in order to address this concern of Dr. Fujii, we inserted in section 2.1, after a short description of the loam and clay Acrisol soils, the following:

L122 - Detailed soil characteristics of these classifications are reported by Allen et al. (2016).

2. L447 The authors link between N leaching and the acid-buffering capacity of the soils, but link between N leaching and clay contents will be precise. Exchangeable Al as well as pH is a record

of soil acidification, but quantitative link between N loss and soil ANC cannot be supported by calculating proton budgets in soil.

Author's response:

We agree with the reviewer's comments. As stated in the Results (previous L366-376 of the original manuscript), N leaching fluxes (and N and base cation retention efficiency) were significantly correlated with soil base saturation, ECEC and organic C which were, in turn, correlated with clay content. Thus, this L447 is a leap in our interpretation, and we changed this L447 (as a topic sentence for this Discussion on correlations of nutrient leaching fluxes with soil biochemical characteristics) to refer only to what were clearly reflected by the correlation tests.

Author's changes in the manuscript:

We changed L447 to:

L452-453 - The influenced of soil texture on soil biochemical characteristics also linked to the leaching losses or, conversely, nutrient retention efficiency.

3. There were some droughts or dry-wet cycles in Indonesia. This has strong impacts on solute concentration and leaching flux. I recommend to add correlation analyses between water flux (or soil water content) and solute concentration to check dilution or condensation effects by dry-wet cycles. This effect can affect annual nutrient loss as well. At least, adding discussion will improve manuscript.

Author's response:

From the start of our data analyses, we have explored all correlation tests, including correlations of element concentrations with the modelled soil moisture content at 1.5-m depth (lysimeter sampling) in order to check for dilution or condensation; the correlation tests with soil moisture contents were conducted in a similar manner as those reported in Appendix Tables 3 and 4. The only significant correlation coefficients with soil moisture contents were found for the fertilized area of the oil palm plantations in the loam Acrisol soil for K, Ca, Mg and total S concentrations ($r = -0.59 - -0.72$, $P \leq 0.05$, $n = 12$ monthly measurements for one year). However, the influence of soil water content on nutrient concentrations were anyway incorporated in the calculation of leaching fluxes (nutrient concentration x drainage flux), as stated in L247-250. Also, all the correlations that used the nutrient concentrations (Appendix Tables 3 and 4) were interpreted only to assess which cations were correlated with which anions (i.e., L340-342, L350-352, L363-366) in order to support the partial ionic charge balance of solutes, as depicted in Fig. 1.

Author's changes in the manuscript:

Considering that (1) these above correlation tests were only significant in four elements at one spatial category (fertilized area of oil palm in the loam soils) and (2) the influence of soil water content on element concentrations were incorporated in the calculation of leaching fluxes, we will not add this in the Discussion. This is so that the main highlights of our findings will not be buried, as suggested by Dr. Teh's (reviewer 1) first major suggestion.

4. Throughout the paper, the authors use the ambiguous term “soil fertility”. The definition of soil fertility is not same among the readers. Please define it in the beginning of the paper. Most of soil scientists avoid to use the term “soil fertility” in scientific paper.

Author’s response:

We agree and take this suggestion. When we used the word soil fertility, we specified in parenthesis the soil biochemical characteristics that we used as basis. These were already done in the original manuscript version of the Introduction and M&M.

Introduction L61-62 - Soil texture affects nutrient leaching through its control on soil fertility (e.g., cation exchange capacity, decomposition, and nutrient cycling) and soil water-holding capacity.

M & M L123-125 - In summary, the soil textural difference leads to inherent differences in soil fertility (e.g., higher effective cation exchange capacity, base saturation, Bray-extractable P and lower Al saturation) in the clay than the loam Acrisols under forest and jungle rubber (Appendix Table A1).

Author’s changes in the manuscript:

We specified the soil biochemical properties when we used the word *soil fertility*.

Namely:

Discussion, section 4.2, the last sentence of 1st paragraph:

L449-451 - Our findings showed that soil texture was the main factor regulating nutrient leaching losses and soil fertility (e.g., nutrient stocks and N-cycling rates) in these highly weathered Acrisol soils.

In the Abstract and Discussion, section 4.3 last sentence of 1st paragraph – we replaced ‘*soil fertility*’ with ‘*nutrient availability*’:

L484-488 - Our results showed that disruption of nutrient cycling between the soil and vegetation brought about by land-use conversion to rubber plantations, combined with the absence of soil amendments, had decreased nutrient leaching (Tables 3 and 4) as well soil nutrient availability (i.e., P stocks, microbial N, gross N mineralization rates; Allen et al., 2015; Allen et al., 2016).

In the Conclusion, we replaced *soil fertility* with *soil nutrients* or *nutrient levels*.

Specific comments:

1. The authors regarded jungle rubber as original vegetation, but it is introduced from Brazil some hundreds of years ago. It is not native vegetation.

Author’s response:

We replaced the word ‘*original*’ with ‘*previous*’ (in the Introduction) or ‘*reference land use*’ (in the Discussion), which was what we actually meant. We use ‘*previous*’ or ‘*reference land use*’ to denote the land use immediately before the conversion to rubber and oil palm.

2. The authors ascribed the greater nutrient losses from loam Acrisols than those from clay Acrisols. However, tree composition is not same between two sites. The authors need to add careful discussion on this topic.

Author's response:

This is a very good point and we take this into consideration. Our interpretation that soil texture was the main factor influencing leaching losses is based on the following:

- a) total net primary production (aboveground + belowground), as an indicator of plant usage of soil nutrients, of the forest and jungle rubber did not differ between the loam and clay Acrisol soils (Kotowska et al., 2015).
- b) despite higher tree stem density, basal area and root mass (all together maybe indicative of potential differences in nutrient demands of vegetation between these soils) in the loam than in the clay Acrisol soils (Appendix Table A2), the loam Acrisols still showed generally larger leaching fluxes than the clay Acrisols.
- c) based from the rubber plantations' (which all have the same low degree of management, e.g. unfertilized, in both soil types) Na leaching fluxes (the element more prone to leaching because of its monovalence and large hydration radius), the loam Acrisol soil was also higher ($P = 0.06$) than the clay Acrisols.

Previously we did not include these above points in the Discussion to keep the information more focused, especially that we have a data-rich paper. However, in the revised version we will include points (a) and (b) to address the reviewer's suggestion.

Author's changes in the manuscript:

In the Discussion section 4.2, we added this:

L443-449 - Nutrient demand of vegetation may not be the dominant control on leaching fluxes, as the vegetation structure of the reference land uses (tree density, basal area, root biomass; Appendix Table A2) even seemed larger in the loam than the clay Acrisols. Similarly, the differences in tree species compositions between the loam and clay Acrisol soils (Appendix Table A2) may not have influenced the nutrient leaching fluxes, as supported by the comparable net primary production of the reference land uses between soil types (Kotowska et al., 2015).

3. L525-527 erosion and enhanced microbial mineralization of the native SOM can also contribute to low SOC stocks in oil palm plantation.

Author's response:

Yes, and we did not include in our discussion the erosion effect. Soil respiration in our oil palm plantations has significantly decreased compared to the reference land uses (Hassler et al., 2015). Based on correlations analysis with other soil biochemical parameters (^{15}N signatures, SOC, P and base cation stocks), we attributed the reduced soil CO_2 fluxes from the oil palm plantations as the result of the strongly decomposed soil organic matter and reduced soil C stocks, which in turn are due to reduced litter input as well as to a possible reduction in C allocation to roots because of addition of nutrients from liming and P fertilization (Hassler et al., 2015).

Author's changes in the manuscript:

Considering that erosion is an important process contributing to a decrease in SOC, we replaced the word '*strong*' with '*additional*':

L519-525 - Moreover, the increased annual DOC fluxes in fertilized areas of oil palm plantations (Table 4) suggests a reduction in the retention of DOC in the soil. This, combined with the decreases in litterfall and root production, harvest export (Kotowska et al., 2015), and decreases in soil CO₂ emissions (Hassler et al., 2015) from the same oil palm plantations, provided *additional* support for the decreases in soil organic C stocks in smallholder oil palm plantations in the same study region (van Straaten et al., 2015).

4. L505-506 What data can support this statement?

Author's response:

This statement (i.e., increases in dissolved Al and acidity of soil solution; Table 3) was based on the Results section where dissolved Al and soil water pH were presented (L352-354, L360-362).

Author's changes in the manuscript:

In this sentence (L502-504), we now inserted Table 3 as the data source.

5. Table A2 sp. or spp. should not be written in italic. Dipterocarpaceae spp. include Shorea spp. The tree composition should be re-checked.

Author's response:

We agree with the reviewer. This Appendix Table A1 was based on information we had in 2015, when another group working on species diversity in our plots were yet continuing to identify the species, and we had by mistake doubly listed the families Dipterocarpaceae and Shorea. We now checked the 5 numerous tree families with the most current identified trees.

Author's changes in the manuscript:

We updated the 5 numerous tree families in Appendix Table A2 based from Rembold et al. (2017) and Rembold (pers. comm.).

Rembold, K., Mangopo, H., Tjitrosoedirdjo, S.S., and Kreft, H.: Plant diversity, forest dependency, and alien plant invasions in tropical agricultural landscapes, *Biodivers. Conserv.*, 213, 234-242, <https://doi.org/10.1016/j.biocon.2017.07.020>, 2017.

6. Throughout the paper, "l-1" and "L-1" are used inconsistently. Please use terms consistently.

Author's response:

We appreciate very much for this very thorough read, and we indeed overlooked l⁻¹.

Author's changes in the manuscript:

We corrected the entire text and Table 3 to have uniformed unit abbreviation, L⁻¹.

Marked-up manuscript version

1 **Conversion of tropical forests to smallholder rubber and oil palm**
2 **plantations impacts nutrient leaching losses and nutrient retention**
3 **efficiency in highly weathered soils**

4

5 Syahrul Kurniawan^{1,3}, Marife D. Corre^{1*}, Amanda L. Matson¹, Hubert Schulte-Bisping², Sri
6 Rahayu Utami³, Oliver van Straaten¹ and Edzo Veldkamp¹

7

8 ¹Soil Science of Tropical and Subtropical Ecosystems, Faculty of Forest Sciences and Forest
9 Ecology, University of Goettingen, Germany

10 ²Soil Science of Temperate Ecosystems, Faculty of Forest Sciences and Forest Ecology,
11 University of Goettingen, Germany

12 ³Department of Soil Science, Faculty of Agriculture, Brawijaya University, Indonesia

13

14 **Correspondence to:* Marife D. Corre (mcorre@gwdg.de)

15 **Abstract.** Conversion of forest to rubber and oil palm plantations is widespread in Sumatra,
16 Indonesia, and it is largely unknown how such land-use conversion affects nutrient leaching
17 losses. Our study aimed to quantify nutrient leaching and nutrient retention efficiency in the
18 soil after land-use conversion to smallholder rubber and oil palm plantations. In Jambi province,
19 Indonesia, we selected two landscapes on highly weathered Acrisol soils that mainly differed
20 in texture: loam and clay. Within each landscapesoil type, we compared two reference land
21 uses: lowland forest and jungle rubber (defined as rubber trees interspersed in secondary forest)
22 with two converted land uses, smallholder rubber and oil palm plantations. Within each
23 landscapesoil type, the first three land uses were represented by four replicate sites and the oil
24 palm by three sites, totaling to 30 sites. We measured leaching losses using suction cup
25 lysimeters, sampled biweekly to monthly from February to December 2013. Forests and jungle
26 rubber had low solute concentrations in drainage water, suggesting low internal inputs of rock-
27 derived nutrients and efficient internal cycling of nutrients. These reference land uses on the
28 clay Acrisol soils had lower leaching of dissolved N and base cations ($P = 0.01-0.06$) and higher
29 N and base cation retention efficiency ($P < 0.01-0.07$) than those on the loam Acrisols. In the
30 converted land uses, particularly on the loam Acrisol, the fertilized area of oil palm plantations
31 showed higher leaching of dissolved N, organic C and base cations ($P < 0.01-0.08$) and lower
32 N and base cation retention efficiency compared to all the other land uses ($P < 0.01-0.06$). The
33 unfertilized rubber plantations, particularly on the loam Acrisol, showed lower leaching of
34 dissolved P ($P = 0.08$) and organic C ($P < 0.01$) compared to forest or jungle rubber, reflecting
35 decreases in soil P stocks and C inputs to the soil. Our results suggest that land-use conversion
36 to rubber and oil palm causes disruption of initially efficient nutrient cycling, which decreases
37 soil fertilitynutrient availability. Over time, smallholders will likely be increasingly reliant on
38 fertilization, with the risk of diminishing water quality due to increased nutrient leaching. Thus,

39 there is a need to develop management practices to minimize leaching while sustaining
40 productivity.

41 **1 Introduction**

42 Rainforests play an important role in maintaining ground water quality in tropical regions;
43 however, in some regions their effectiveness may be decreasing as a consequence of forest
44 conversion to agriculture. From 1990 to 2010, the deforestation rate in South and Southeast
45 Asia was approximately 3 million ha yr⁻¹, of which 1.2 million ha yr⁻¹ occurred in Indonesia
46 (FAO, 2010). During these two decades, the forest loss in the whole of Sumatra was 7.5 million
47 ha, of which 1.1 million ha occurred in Jambi province (Margono et al., 2012). The two most
48 common land uses replacing forests in Jambi province are oil palm and rubber plantations. From
49 2000 to 2010, the area of rubber plantations in Jambi increased by about 19% while oil palm
50 plantations increased by 85% (Luskin et al., 2013). The expansion of rubber and oil palm
51 plantations has increased the income of Jambi, in particular the smallholder farmers (Clough et
52 al., 2016; Rist et al., 2010), ~~as which account approximately 99 % of rubber and 62 % of oil~~
53 ~~palm landholdings in the Jambi Province are owned by smallholders (BPS, 2014). In the whole~~
54 ~~of Indonesia, 85 % of rubber and 40 % of oil palm plantations are smallholders (DGEC, 2017).~~
55 However, forest conversion to rubber and oil palm plantations has shown high ecological costs:
56 losses in biodiversity (Clough et al., 2016), decreases in above- and below-ground organic
57 carbon (C) stocks (Kotowska et al., 2015; van Straaten et al., 2015), reduction in soil nitrogen
58 (N) availability (Allen et al., 2015), decrease in uptake of methane (CH₄) from the atmosphere
59 into the soil (Hassler et al., 2015), and increase in soil N₂O emission following N fertilization
60 (Hassler et al., 2017).

61 Under similar climatic conditions and soil types, the two major factors that influence
62 nutrient leaching losses from forest conversion are soil texture and management practices. Soil
63 texture affects nutrient leaching through its control on soil fertility (e.g., cation exchange

64 capacity, decomposition, and nutrient cycling) and soil water-holding capacity. Fine-textured
65 soils have higher cation exchange capacity, decomposition and soil-N cycling rates, which
66 result in higher soil fertility than coarse-textured soils (Allen et al., 2015; Silver et al., 2000;
67 Sotta et al., 2008). Soil texture also influences water-holding capacity and drainage through its
68 effects on porosity, pore size distribution, and hydraulic conductivity (Hillel, 1982). Clay soils
69 can hold a large amount of water and are dominated by small pores, which have low hydraulic
70 conductivity in high moisture conditions. In contrast, coarse-textured soils have low water-
71 holding capacity and are dominated by large pores, which conduct water rapidly in high
72 moisture conditions, and therefore have high potential for leaching of dissolved solutes (Fujii
73 et al., 2009; Lehman and Schroth, 2002). Thus, in heavily weathered soils, such as Acrisols,
74 which dominate the converted lowland landscapes in Jambi, Indonesia (FAO et al., 2012),
75 retention of their inherently low exchangeable base cations in the soil and maintenance of
76 efficient soil-N cycling are largely influenced by soil texture (Allen et al., 2015).

77 Soil management practices (e.g., fertilizer and lime applications) in converted land uses
78 also play an important role in influencing nutrient leaching, as the magnitude of dissolved
79 nutrients moving downward with water is predominantly driven by the levels of those nutrients
80 in the soil (Dechert et al., 2005, 2004). Without fertilization, nutrient leaching losses in
81 agricultural land usually decrease with years following forest conversion (Dechert et al., 2004).
82 This may be the case for the smallholder rubber plantations in our present study, as these have
83 not been fertilized since conversion from forest (Allen et al., 2015; Hassler et al., 2017, 2015).
84 However, soils in oil palm plantations are very often supplemented with chemical fertilizer and
85 lime applications (Allen et al., 2015; Goh et al., 2003; Hassler et al., 2017, 2015). In cases
86 where oil palm plantations are regularly fertilized, nutrient leaching losses in older plantations
87 may be higher than in younger ones, as the applied nutrients accumulate in the subsoil over
88 time (Goh et al., 2003; Omoti et al., 1983). Consequently, nutrient leaching in regularly

89 fertilized oil palm plantations will likely be higher than in the original forest. Moreover, in our
90 earlier study conducted in smallholder oil palm plantations, fertilization was shown to decrease
91 microbial N immobilization due to decreases in microbial biomass (Allen et al., 2015), which
92 could lead to decrease in retention of N in the soil.

93 Despite a growing body of information on the effects of deforestation on soil properties
94 and processes, there is a lack of information on how forest conversion to rubber and oil palm
95 influences nutrient leaching and the efficiency with which nutrients are retained in the soil. This
96 lack is especially notable for nutrients other than N, as previous leaching studies commonly
97 focus on this. Here, we present leaching losses of the full suite of major nutrients using a large-
98 scale replicated design in a region affected by widespread land-use conversion to rubber and
99 oil palm plantations. Our study aimed to assess: 1) how soil physical and biochemical
100 characteristics affect nutrient leaching in highly weathered soils, and 2) the impact of land-use
101 conversion to smallholder rubber and oil palm plantations on nutrient leaching and on N and
102 base cation retention efficiency in the soil. We hypothesized that: 1) lowland forest and jungle
103 rubber (rubber trees planted in secondary forest), which were the ~~original~~previous land uses
104 ~~prior to~~before conversion, will have lower leaching losses and higher nutrient retention in clay
105 Acrisol soil than in loam Acrisol soil, and 2) smallholder oil palm plantations with fertilizer and
106 lime applications will have the highest nutrient leaching losses (lowest nutrient retention)
107 whereas smallholder rubber plantations with no fertilizer input will have the lowest nutrient
108 leaching losses.

109

110 **2 Materials and methods**

111 **2.1 Study sites and experimental design**

112 Our study is part of the on-going multidisciplinary research project, EFForTS ([http://www.uni-](http://www.uni-goettingen.de/en/310995.html)
113 [goettingen.de/en/310995.html](http://www.uni-goettingen.de/en/310995.html)), investigating the ecological and socioeconomic impact of

114 conversion of lowland forest to rubber and oil palm plantations. The detailed experimental
115 design and locations of the study sites were reported earlier (e.g., Allen et al., 2015; Hassler et
116 al., 2017, 2015). In short, our study region is located in Jambi province, Indonesia (2° 0' 57" S,
117 103° 15' 33" E, 35 - 95 m elevation). The area has a mean annual air temperature of 26.7 ± 0.1
118 °C and a mean annual precipitation of 2235 ± 385 mm (1991–2011; data from a climate station
119 at the Jambi Sultan Thaha airport from the Indonesian Meteorological, Climatological and
120 Geophysical Agency). The dry season (<100 mm month⁻¹) is from May to September, and the
121 wet season is from October to April. We selected two landscapes within our study region; while
122 both were located on highly weathered Acrisol soils, one ~~was~~ has a clay-textured soils and the
123 other ~~was a~~ loam-textured soils (hereafter we refer to them as clay Acrisol and loam Acrisol
124 landscapesoils). Detailed soil characteristics of these classifications are reported by Allen et
125 al. (2016). In summary, tThe soil textural difference leads to inherent differences in soil fertility;
126 as shown by (e.g., the higher effective cation exchange capacity, base saturation, Bray-
127 extractable P and lower Al saturation) in the clay than the loam Acrisols under forest and jungle
128 rubber (Appendix Table A1; ~~Allen et al. 2015~~). Within each landscapesoil type, we selected
129 four land uses: lowland forest, jungle rubber, and smallholder plantations of rubber and oil palm
130 (Appendix Table A2). Within each landscapesoil type, we had 15 sites (see Allen et al. 2015
131 for the map of these sites in the study region): four forest, four jungle rubber, four rubber
132 plantations, and three oil palm plantations. We started with four oil palm sites at each
133 landscapesoil type, but one plantation was sold and the new owner did not continue the
134 collaboration with our research and in another site the instruments for leaching sampling were
135 damaged. In our experimental design, land-use types (including the soil management practices
136 typical for smallholders in the region) were the treatment and the sites were the replications. At
137 each site, we established a plot of 50 m x 50 m. All plots were on the well-drained position of
138 the landscape with slopes ranging from 3-10 % across all plots.

139 Based on our interviews with the smallholders, their plantations were established after
140 clearing and burning of either forest or jungle rubber and hence these latter land uses served as
141 the reference with which the converted plantations were compared. Additionally, the
142 comparability of the initial soil conditions between the reference and converted land uses was
143 tested using a land use-independent soil characteristic, i.e., clay content at 1–2 m depth (van
144 Straaten et al., 2015); this did not statistically differ among land uses within each landscape soil
145 type (Appendix Table A1; Allen et al., 2015; Hassler et al., 2015). Thus, changes in nutrient
146 leaching can be attributed to land-use conversion with its inherent soil management practices.
147 These first generation rubber and oil palm plantations were between 7 and 17 years of age. Tree
148 density, height, basal area, and tree species abundance were higher in the reference land uses
149 than the smallholder plantations (Appendix Table A2; Allen et al., 2015; Hassler et al., 2015;
150 Kotowska et al., 2015).

151 Soil management practices in smallholder oil palm plantations are inherently varied
152 (e.g., fertilization rate), as this depended on financial resources of the smallholders. Fertilization
153 rates were 48 ~~and 88~~ kg N⁻, 21 kg P and 40 kg K ha⁻¹ yr⁻¹, in the clay Acrisol soil, whereas these
154 were 88 kg N, 21 and 38 kg P ha⁻¹ yr⁻¹ and 40 and 157 kg K ha⁻¹ yr⁻¹ (accompanied by Cl input
155 of 143 kg Cl ha⁻¹ yr⁻¹) in the clay Acrisol and in the loam Acrisol soils, respectively. Lime (e.g.,
156 CaMg(CO₃)₂), kieserite (MgSO₄.H₂O) and borate (Na₂B₄O₇.5H₂O) were also occasionally
157 applied. These fertilization rates are typical of the smallholder farms in the region. Soil
158 amendments were applied by hand around each palm tree at 0.8–1.5 m from the stem base. A
159 combination of manual weeding and herbicides was practiced. Old oil palm fronds were
160 regularly cut and stacked at 4–4.5 m from the palm rows (row spacing was about 9 m). The
161 rubber plantations were not fertilized but were weeded both manually and with herbicides.

162

163 **2.2 Lysimeter installation and soil water sampling**

164 For measuring nutrient leaching, we sampled soil water using lysimeters, which were installed
165 at two randomly chosen locations per replicate plot of the forest, jungle rubber and rubber
166 plantations. In the oil palm plantations, the lysimeters were deployed according to the spatial
167 structure of the soil management practices: one lysimeter was installed between 1.3–1.5-m
168 distance from the tree stem where fertilizers were applied, and another lysimeter was installed
169 between 4–4.5-m distance from the tree stem where the cut fronds were stacked. These suction
170 cup lysimeters (P80 ceramic, maximum pore size 1 μm ; CeramTec AG, Marktrechwitz,
171 Germany) were inserted into the soil down to 1.5-m depth. This depth was based from our
172 previous work in a lowland forest on highly weathered Ferralsol soil, where leaching losses
173 were measured at various depth intervals down to 3 m and from which we found that leaching
174 fluxes did not change below 1 m (Schwendenmann and Veldkamp, 2005). Moreover, this 1.5-
175 m depth of lysimeter installation at our sites was well below the rooting depth, as determined
176 from the fine-root biomass distribution with depths (Appendix Fig. B1; Kurniawan, 2016).

177 Prior to installation, lysimeters, tubes and collection containers were acid-washed and
178 rinsed with deionized water. Lysimeters were installed in the field three months prior to the first
179 sampling. The collection containers (dark glass bottles) were placed in plastic buckets with lids
180 and buried in the ground approximately 2 m away from the lysimeters. Soil water was sampled
181 biweekly to monthly, depending on the frequency of rainfall, from February to December 2013.
182 Soil water was withdrawn by applying a 40 kPa vacuum on the sampling tube (Dechert et al.,
183 2005; Schwendenmann and Veldkamp, 2005). The collected soil water was then transferred
184 into clean 100-mL plastic bottles. Upon arrival at the field station, a subsample of 20 mL was
185 set aside for pH measurement while the remaining sample was frozen. All frozen water samples
186 were transported to the University of Goettingen, Germany and were kept frozen until analysis.

187 The total dissolved N (TDN), NH_4^+ , NO_3^- and Cl^- concentrations were measured using
188 continuous flow injection colorimetry (SEAL Analytical AA3, SEAL Analytical GmbH,
189 Norderstedt, Germany). TDN was determined by ultraviolet-persulfate digestion followed by
190 hydrazine sulfate reduction (Autoanalyzer Method G-157-96); NH_4^+ was analyzed by salicylate
191 and dichloroisocyanuric acid reaction (Autoanalyzer Method G-102-93); NO_3^- by cadmium
192 reduction method with NH_4Cl buffer (Autoanalyzer Method G-254-02); and Cl^- was determined
193 with an ion strength adjustor reagent that is pumped through an ion selective chloride electrode
194 with an integrated reference electrode (Auto analyzer Method G-329-05). Dissolved organic N
195 (DON) is the difference between TDN and mineral N ($\text{NH}_4^+ + \text{NO}_3^-$). Dissolved organic C
196 (DOC) was determined using a Total Organic Carbon Analyzer (TOC-Vwp, Shimadzu Europa
197 GmbH, Duisburg, Germany). DOC was analyzed by pre-treating the samples with H_3PO_4
198 solution (to remove inorganic C) followed by ultraviolet-persulfate oxidation of organic C to
199 CO_2 , which is determined by an infrared detector. Base cations (Na, K, Ca, Mg), total Al, total
200 Fe, total Mn, total S, total P, and total Si in soil water were analyzed using inductively coupled
201 plasma-atomic emission spectrometer (iCAP 6300 Duo View ICP Spectrometer, Thermo
202 Fischer Scientific GmbH, Dreieich, Germany). Instruments' detection limits were: $6 \mu\text{g NH}_4^+$ -
203 N L^{-1} , $5 \mu\text{g NO}_3^-$ - N L^{-1} , $2 \mu\text{g TDN L}^{-1}$, $4 \mu\text{g DOC L}^{-1}$, $30 \mu\text{g Na L}^{-1}$, $50 \mu\text{g K L}^{-1}$, $3 \mu\text{g Ca L}^{-1}$,
204 $3 \mu\text{g Mg L}^{-1}$, $2 \mu\text{g Al L}^{-1}$, $3 \mu\text{g Fe L}^{-1}$, $2 \mu\text{g Mn L}^{-1}$, $10 \mu\text{g P L}^{-1}$, $10 \mu\text{g S L}^{-1}$, $1 \mu\text{g Si L}^{-1}$ and 30
205 $\mu\text{g Cl L}^{-1}$.

206 Partial cation-anion charge balance of the major solutes (i.e., those with concentrations
207 $>0.03 \text{ mg L}^{-1}$) in soil water was done by expressing solute concentrations in $\mu\text{molc L}^{-1}$ (molar
208 concentration multiplied by the equivalent charge of each solute). Contributions of organic
209 acids (RCOO^-) and bicarbonate (HCO_3^-) were calculated, together with S (having very low
210 concentrations), from the difference between cations and anions. Charge contributions of total
211 Al were assumed to be 3^+ , whereas solutes that had very low concentrations (i.e., total Fe, Mn

212 and P), and thus had minimal charge contribution, as well as the total dissolved Si (commonly
213 in a form of monosilicic acid (H_4SiO_4^0) that has no net charge) were excluded (similar to the
214 method used by Hedin et al., 2003).

215

216 **2.3 Soil water modelling and calculation of nutrient leaching fluxes**

217 Drainage water fluxes were estimated using the soil water module of the Expert-N model
218 (Priesack, 2005), which has been used in our earlier work on nutrient leaching losses in
219 Sulawesi, Indonesia (Dechert et al., 2005). The model was parameterized with the
220 characteristics measured at our sites, namely climate data, leaf area index, rooting depth, and
221 soil characteristics. The climate variables included daily air temperature (minimum, maximum
222 and average), relative humidity, wind speed, solar radiation, and precipitation. For the loam
223 Acrisol landscapesoil, the climate data were taken from a climate station at the Harapan Forest
224 Reserve, which was located 10–20 km from our sites. For the clay Acrisol landscapesoil, the
225 climate data were taken from the climate stations at the villages of Lubuk Kepayang and
226 Sarolangun, which were respectively 10 km and 20 km from our sites. The leaf area indices
227 measured in our forest, jungle rubber, rubber and oil palm sites in the loam Acrisol landscape
228 soil were 5.8, 4.8, 3.5, and 3.9 $\text{m}^2 \text{m}^{-2}$, respectively, and in the clay Acrisol landscape-soil were
229 6.2, 4.5, 2.8 and 3.1 $\text{m}^2 \text{m}^{-2}$, respectively (Rembold et al., unpublished data). Our measured fine
230 root biomass distribution (Appendix Fig. B1; Kurniawan, 2016) was used to partition root water
231 uptake at various soil depths. Soil characteristics included soil bulk density, texture (Appendix
232 Table A1) and the water retention curve. The latter was determined using the pressure plate
233 method for which intact soil cores (250 cm^3), taken at five soil depths (0.05, 0.2, 0.4, 0.75 and
234 1.25 m) from each land use within each landscapesoil type, were measured for water contents
235 at pressure heads of 0, 100, 330 and 15000 hPa.

236 Calculation of drainage water fluxes followed the water balance equations:

$$237 \quad \Delta W + D = P - R - ET \text{ and } ET = I + E + T$$

238 in which ΔW = change in soil water storage, D = drainage water below rooting zone, P =
239 precipitation, R = runoff, ET = evapotranspiration, I = interception of water by plant foliage, E
240 = evaporation from soil, and T = transpiration by plants. The Expert-N model calculates actual
241 evapotranspiration using the Penman-Monteith method, runoff based on the sites' slopes, and
242 vertical water movement using the Richards equation, of which the parameterization of the
243 hydraulic functions were based on our measured soil texture and water retention curve
244 (Mualem, 1976; Van Genuchten, 1980). To validate the output of the water model, we
245 compared the modelled and measured soil matrix potential (Appendix Fig. B2). Soil matrix
246 potential was measured biweekly to monthly from February to December 2013, using
247 tensiometers (P80 ceramic, maximum pore size 1 μm ; CeramTec AG, Marktrechwitz,
248 Germany), which were installed at the depths of 0.3 m and 0.6 m in two replicate plots per land
249 use within each [landscapesoil type](#).

250 Modelled daily drainage water fluxes at a depth of 1.5 m were summed to get the
251 biweekly or monthly drainage fluxes. Nutrient leaching fluxes were calculated by multiplying
252 the element concentrations from each of the two lysimeters per replicate plot with the total
253 biweekly or monthly drainage drainage water flux. The annual leaching flux was the sum of
254 biweekly to monthly measured leaching fluxes from February to December 2013, added with
255 the interpolated value for the unmeasured month of January 2013.

256

257 **2.4 Nutrient retention efficiency**

258 To evaluate the efficiency with which nutrients are retained in soil, we calculated the N and
259 base cation retention efficiency as follows: $1 - (\text{nutrient leaching loss}/\text{soil available nutrient})$
260 (Hoeft et al., 2014). For the oil palm plantations, we took the average leaching fluxes in the
261 fertilized and frond-stacked areas of each plot for calculating the nutrient retention efficiency.
262 This is because these sampling locations may contribute equally in terms of area as both the

263 vertical and lateral flows in the soil profile could influence the sampled drainage water, and
264 thus a wider area may contribute to the sampled drainage water than just the categorized
265 sampling locations. For N retention efficiency calculation, TDN leaching flux was ratioed to
266 gross N mineralization rate as the index of soil available N, with both terms expressed in mg N
267 $\text{m}^{-2} \text{d}^{-1}$. For calculation of base cation retention efficiency, base cation leaching flux was the
268 sum of K, Na, Mg and Ca in units of $\text{mol}_{\text{charge}} \text{m}^{-2} \text{yr}^{-1}$ and soil available base cations was the
269 sum of these exchangeable cations in units of $\text{mol}_{\text{charge}} \text{m}^{-2}$. We used the measurements of gross
270 N mineralization rate in the top 0.05-m depth and the stocks of exchangeable bases in the top
271 0.1-m depth (Appendix Table A1, reported by Allen et al., 2015).

272

273 **2.5 Supporting parameter: nutrient inputs through bulk precipitation**

274 In each landscape, we installed two rain samplers in an open area at 1.5 m above the ground.
275 Rain samplers consisted of 1-liter high-density polyethylene bottles with lids attached to
276 funnels that were covered with a 0.5-mm sieve, and were placed inside polyvinyl chloride tubes
277 (to shield from sunlight and prevent algal growth). Rain samplers were washed with acid and
278 rinsed with deionized water after each collection. Rain was sampled during the same sampling
279 period as the soil water. Each rain sample was filtered through prewashed filter paper (4 μm
280 pore size) into a 100 mL plastic bottle and stored frozen for transport to the University of
281 Goettingen, Germany. The element analyses were the same as those described for soil water.
282 The element concentrations in rainwater were weighted with the rainfall volume during the two-
283 week or 1-month collection period to get volume-weighted concentrations. The annual element
284 inputs from bulk precipitation were calculated by multiplying the volume-weighted average
285 element concentrations in a year with the annual rainfall in each landscape.

286

287 2.6 Statistical analysis

288 Each replicate plot was represented by the average of two lysimeters, except for the oil palm
289 plantations where lysimeters in fertilized and frond-stacked areas were analyzed separately.
290 Tests for normality (Shapiro-Wilk's test) and homogeneity of variance (Levene's test) were
291 conducted for each variable. Logarithmic or square-root transformation was used for variables
292 that showed non-normal distribution and/or heterogeneous variance. We used linear mixed
293 effects (LME) models (Crawley, 2009) to (1) assess differences between the two landscapes
294 soil types for the reference land uses (to answer objective 1), and (2) assess differences among
295 land-use types within each landscape-soil type (to answer objective 2). The latter was analyzed
296 for each landscape because the fertilization rates applied to the smallholder oil palm plantations
297 inherently differed between the two landscapes. For element concentrations, the LME model
298 had landscape-soil type or land-use type as the fixed effect with spatial replication (plot) and
299 time (biweekly or monthly measurements) as random effects. For the annual leaching fluxes,
300 the LME model had landscape-soil type or land-use type as the fixed effect with spatial
301 replication (plot) as a random effect. If they improved the relative goodness of the model fit
302 (based on the Akaike information criterion), we extended the LME model to include (1) a
303 variance function that allows different variances of the fixed effect, and/or (2) a first-order
304 temporal autoregressive process that assumes that correlation between measurement periods
305 decreases with increasing time intervals. Fixed effects were considered significant based on
306 analysis of variance at $P \leq 0.05$, and differences between landscapes-soil types or land-uses
307 types were assessed using Fisher's least significant difference test at $P \leq 0.05$. Given the
308 inherent spatial variability in our experimental design, we also considered P values of $> 0.05 \leq$
309 0.09 as marginal significance, mentioned explicitly for some variables. To support the partial
310 charge balance of dissolved cations and anions, we used Pearson correlation analysis to assess
311 the relationships between solute cations and anions, using the monthly average ($n = 12$) of the

312 four replicate plots per land use within each landscapesoil type. We also used Pearson
313 correlation analysis to test the modelled and measured soil matrix potential, using the monthly
314 average ($n = 12$) of the measured two replicate plots per land use within each landscapesoil
315 type. To assess how the soil physical and biochemical characteristics (Table A1) influence the
316 annual nutrient leaching fluxes, we conducted Spearman's rank correlation test for these
317 variables, separately for the reference land uses and the converted land uses across landscapes
318 both soil types ($n = 16$). All statistical analyses were conducted using R 3.0.2 (R Development
319 Core Team, 2013).

320

321 **3 Results**

322 **3.1 Water balance and nutrient input from bulk precipitation**

323 The modelled and measured soil matrix potential were highly correlated ($R = 0.79$ to 0.98 , $n =$
324 12 , $P < 0.01$) (Appendix Fig. B2). In forest and jungle rubber, modelled annual ET was 36-47
325 %, runoff was 16-27 %, and drainage was 32-44 % of annual precipitation. In rubber and oil
326 palm, modelled annual ET was 30-32 %, runoff was 22-31 %, and drainage was 37-47 % of
327 annual precipitation (Table 1). In both landscapes, annual input from bulk precipitation was
328 dominated by DOC (58 % of total element deposition), followed by Na, Cl, TDN, Ca, K and
329 total S (Table 2). We compared the chlorinity ratios of elements in the bulk precipitation at our
330 sites to those of seawater to infer anthropogenic influence. The average chlorinity ratios from
331 both landscapes were 1.13 ± 0.05 for Na:Cl, 0.05 ± 0.01 for Mg:Cl, 0.20 ± 0.02 for Ca:Cl and
332 0.13 ± 0.04 for K:Cl, which were higher, except for Mg:Cl, than seawater chlorinity ratios (0.56
333 for Na:Cl, 0.07 for Mg:Cl, 0.02 for Ca:Cl and 0.02 for K:Cl; p. 349, Schlesinger and Bernhardt,
334 2013).

335

3.2 Element concentrations in soil water

336 For forest, the loam Acrisol had higher dissolved Na, Mg, total Al (all $P \leq 0.05$), $\text{NH}_4^+\text{-N}$, DON,
337 total Fe and Cl concentrations (all $P \leq 0.09$) than the clay Acrisol (Table 3). For jungle rubber,
338 the loam Acrisol had higher dissolved $\text{NO}_3^-\text{-N}$ ($P \leq 0.05$) and lower total Si concentrations (P
339 ≤ 0.09) than the clay Acrisol (Table 3). The ionic charge concentration ~~of~~ in soil solution ~~of~~ in
340 the forest sites was higher in the loam ($274 \pm 19 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$) than in the clay Acrisols (203
341 $\pm 20 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$) ($P = 0.01$; Fig. 1), whereas in the jungle rubber these were comparable
342 (loam Acrisols: $199 \pm 31 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$, clay Acrisols: $207 \pm 24 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$; Fig. 1).
343 Correlation analysis of dissolved cations and anions in forest and jungle rubber showed that
344 $\text{NH}_4^+\text{-N}$, Na, K, Ca, Mg and total Al were positively correlated with DON, DOC, Cl, $\text{NO}_3^-\text{-N}$
345 and total S (Appendix Tables A3 and A4).

347 The rubber plantations in the loam Acrisol had lower $\text{NO}_3^-\text{-N}$, DON, DOC, Na, Ca, Cl
348 (all $P \leq 0.05$), total P and total S concentrations (both $P \leq 0.08$) than either forest or jungle
349 rubber (Table 3). This resulted in lower ionic charge concentration ~~of~~ in soil solution ~~of~~ in rubber
350 plantation ($200 \pm 21 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$) than ~~that of~~ in forest ($P < 0.01$; Fig. 1). In the clay Acrisol,
351 only dissolved Na was lower in rubber plantations than in jungle rubber ($P \leq 0.01$; Table 3),
352 and hence the ionic charge concentration ~~in~~ of soil solution ~~of~~ in rubber plantation (189 ± 23
353 $\mu\text{mol}_{\text{charge}} \text{L}^{-1}$) were comparable to those ~~of~~ in the reference land uses (Fig. 1). In contrast to
354 the reference land uses, unfertilized rubber plantations showed strong positive correlations of
355 dissolved cations ($\text{NH}_4^+\text{-N}$, Na, K, Ca, Mg and total Al) with Cl and only weaker positive
356 correlations with DOC or total S (Appendix Tables A3 and A4).

357 The fertilized areas of oil palm plantations had higher $\text{NO}_3^-\text{-N}$, Na, Ca, Mg, total Al, Cl
358 (all $P \leq 0.05$) and lower soil solution pH ($P = 0.07$) than in the reference land uses within the
359 loam Acrisol ~~soil~~ landscape (Table 3). In the clay Acrisol ~~landscapes~~ soil, the fertilized areas of
360 oil palm plantations had higher soil solution pH and dissolved Na (both $P \leq 0.05$) whereas DON

361 was lower ($P = 0.08$) than the reference land uses (Table 3). Ionic charge concentrations ~~in~~of
362 soil solutions ~~of~~in the fertilized areas of oil palm plantations ($648 \pm 306 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$ for loam
363 Acrisol and $317 \pm 83 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$ for clay Acrisol) were higher than in frond-stacked areas
364 ($190 \pm 23 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$ for loam Acrisol and $173 \pm 37 \mu\text{mol}_{\text{charge}} \text{L}^{-1}$ for clay Acrisol) and in
365 other land uses ($P < 0.01$; Fig. 1). In the fertilized areas of the loam Acrisol, dissolved NO_3^- -N
366 was positively correlated with total Al (Table A3) and both were negatively correlated with soil
367 solution pH ($R = -0.57$ to -0.76 , $n = 12$, $P \leq 0.05$). The fertilized areas showed strong positive
368 correlations of dissolved cations (Na, K, Ca, Mg and total Al) with total S or Cl and only weaker
369 positive correlations with DOC (Appendix Tables A3 and A4). The frond-stacked areas showed
370 positive correlations of these dissolved cations largely with Cl (Appendix Tables A3 and A4).

371

372 **3.3 Annual leaching flux and nutrient retention efficiency**

373 For forest, annual leaching fluxes of Na, Ca, Mg, total Al, Cl (all $P \leq 0.05$), NH_4^+ -N, DON,
374 total Si ($P \leq 0.09$) were larger in the loam than in the clay Acrisols, whereas in jungle rubber
375 only annual NO_3^- -N leaching flux was larger ($P \leq 0.05$) (Table 4). Across all forest and jungle
376 rubber sites, annual leaching fluxes of anions (DON and NO_3^- -N) were negatively correlated
377 with indicators of soil exchangeable cations (base saturation, effective cation exchange capacity
378 (ECEC), exchangeable Al; *Spearman's* $\rho = -0.51$ to -0.61 , $n = 16$, $P \leq 0.05$), while annual NH_4^+ -
379 N leaching flux was negatively correlated (*Spearman's* $\rho = -0.53$, $n = 16$, $P = 0.04$) with soil
380 organic C (Table A1). For both reference land uses, the higher leaching in loam than in clay
381 Acrisols was mirrored by decreases in N and base cation retention efficiency in the soil (Table
382 5). Across all reference sites, N and base cation retention efficiency in the soil were positively
383 correlated with base saturation, ECEC and soil organic C (*Spearman's* $\rho = 0.52$ to 0.70 , $n = 16$,
384 $P \leq 0.04$) which, in turn, were positively correlated with clay content (*Spearman's* $\rho = 0.55$ to
385 0.59 , $n = 12$ sites analyzed for clay content, $P \leq 0.05$).

386 The rubber plantations had lower annual P leaching flux than forests ($P = 0.08$) and
387 lower annual DOC leaching flux than jungle rubber in the loam Acrisol ($P < 0.01$) (Table 4). N
388 and base cation retention efficiency in the soil of rubber plantations were comparable with the
389 reference land uses in both landscapes-soil types (Table 5). In oil palm plantations of the loam
390 Acrisol landscapesoil, the fertilized areas had higher annual leaching fluxes of NO_3^- , TDN,
391 DOC, Na, Ca, Mg, total Al, total S and Cl (all $P \leq 0.05$) than in the unfertilized rubber
392 plantations or the reference land uses, whereas the frond-stacked areas showed comparable
393 leaching fluxes with the other land uses (Table 4). In the loam Acrisol, oil palm plantations had
394 lower N and base cation retention efficiency in the soil than the other land uses ($P \leq 0.01 -$
395 0.06 ; Table 5). In the clay Acrisol soil-landscape, where leaching fluxes were small (Table 4),
396 there were no differences observed in soil N and base cation retention efficiency among land
397 uses (Table 5). Across all rubber and oil palm sites, annual $\text{NH}_4^+\text{-N}$ and DON leaching fluxes
398 were negatively correlated with ECEC and clay content (*Spearman's* $\rho = -0.50$ to -0.64 , $n \leq 16$,
399 $P = 0.03 - 0.07$). Moreover, base cation retention efficiency in the soil was positively correlated
400 with ECEC, soil organic C and clay content (*Spearman's* $\rho = 0.68$ to 0.91 , $n \leq 16$, $P \leq 0.01 -$
401 0.02) which, in turn, were correlated with each other (*Spearman's* $\rho = 0.87$ to 0.90 , $n = 12$ sites
402 analyzed for clay content, $P \leq 0.01$).

403

404 **4 Discussion**

405 **4.1 Water balance and nutrient input from bulk precipitation**

406 Our modelled water balance was generally comparable with the estimates from other studies in
407 Indonesia. When compared to a forest at 200-500 m elevation on a clay loam soil in Kalimantan
408 (with 28-47 % ET and 40-55 % runoff of 3451 mm yr^{-1} precipitation; Suryatmojo et al., 2013),
409 our estimated ET in the forest sites was comparable, although our modelled runoff was lower
410 (Table 1). However, our runoff estimates were similar to the modelled runoff in oil palm and

411 rubber plantations in Jambi province (10-20 % of rainfall; Tarigan et al., 2016). Our values for
412 runoff and drainage flux in oil palm plantations (Table 1) were similar to oil palm plantations
413 at 130 m elevation on Andisol soils in Papua New Guinea (with 37-57 % ET, 0-44 % runoff,
414 and 38-59 % drainage of 2398-3657 mm yr⁻¹ precipitation; Banabas et al., 2008). Additionally,
415 our estimated daily ET in oil palm (2.4 ± 0.1 and 2.2 ± 0.1 mm d⁻¹ in the loam and clay Acrisols,
416 respectively) was similar to the measurements of Niu et al. (2015) (2.6 ± 0.7 mm d⁻¹) in the
417 same oil palm plantations included in our study. Finally, the high correlations between modelled
418 and measured matric potential (0.3-m depth; Appendix Fig. B2) suggest that our modelled
419 drainage fluxes closely approximated those in the studied land uses.

420 The chemical composition of bulk precipitation in our study area was clearly influenced
421 by ~~anthropogenic activities, likely from~~ biomass burning and/or terrigenous dust from
422 agriculture. This is evident from the high DOC₂ ~~and~~ TDN, Na:Cl, K:Cl and Ca:Cl ratios in bulk
423 precipitation, which were comparable to values ~~from~~ of bulk precipitation impacted by such
424 biomass burning anthropogenic activities in Southeast Asia as well as in Latin America in
425 Brazil, Panama and Costa Rica (Balasubramanian et al., 1999; Coelho et al., 2008; Corre et al.,
426 2010; Eklund et al., 1997). ~~The high Na:Cl, K:Cl and Ca:Cl ratios in bulk precipitation at our~~
427 ~~sites were similar to values from bulk precipitation influenced by dusts in Singapore and Costa~~
428 ~~Rica~~ (Balasubramanian et al., 1999; Eklund et al., 1997). From a peatland in Kalimantan,
429 influenced by land-clearing fires, throughfall nutrient depositions (19-22 kg N, 6-11 kg P, 25-
430 44 kg S ha⁻¹ yr⁻¹) are larger than those from bulk precipitation, indicating large contribution
431 from dry deposition (Ponette-Gonzales et al., 2016). Total (wet + dry) nutrient depositions in
432 our study region could be larger than the values from bulk precipitation. High atmospheric
433 nutrient deposition may have fertilizing or polluting effect, depending on whether or not the
434 receiving ecosystem is a sink and able to buffer its other cascading effects (e.g., acidification).
435 Additionally ~~The N deposition from bulk precipitation~~ (Table 2) was only 0.7-1.4 % of the gross

436 rate of N mineralization in the top 0.05 m of soil at our forest sites (250–600 mg N m⁻² d⁻¹; Allen
437 et al., 2015). The amount of P and base cations from bulk precipitation (Table 2) were also only
438 1–3 % of the stocks of Bray-extractable P and exchangeable base cations in the top 0.1 m of soil
439 at our forest sites (1–4 g P m⁻², 22–65 g K m⁻², 57–109 g Ca m⁻², and 8–29 g Mg m⁻²; Allen et al.,
440 2016). atmospheric redistribution of nutrients in areas with widespread land-use conversion and
441 intensification may have unforeseen effects on down-wind and down-stream ecosystems (e.g.,
442 Bragazza et al., 2016; Sundarambal et al., 2010). Thus, in our study area, the much larger stocks
443 and cycling rates of nutrients in the soil (and how these are affected by land-use change) will
444 be a more significant influence on nutrient leaching losses (see below) than the low amounts of
445 nutrients from bulk precipitation.

446

447 **4.2 Forest and jungle rubber: Leaching fluxes and nutrient retention efficiency in the** 448 **reference land uses**

449 Highly weathered soils (e.g., Acrisols and Ferralsols) are characterized by Low solute
450 concentrations in drainage and stream waters in soil solution of highly weathered soils is due
451 to minimal internal input of rock-derived nutrients via weathering (Hedin et al., 2003;
452 Markewitz et al., 2001). The Our reference land uses on Acrisol soils in our study region
453 exhibited similarly comparably low ionic charge concentration and with high dissolved Al in
454 soil solutions of forest and jungle rubber (Fig. 1) as those reported by those reported these
455 authors for drainage and stream waters in highly weathered Ferralsol soils (Hedin et al., 2003;
456 Markewitz et al., 2001). Low solute concentration in soil solution of highly weathered soils is
457 due to minimal internal input of rock-derived nutrients via weathering (Hedin et al., 2003). Soil
458 nutrients fertility of such highly weathered soils is are conserved through efficient cycling of
459 nutrients between the soil and vegetation, for which soil texture is one important controlling
460 factor. Previous studies have shown that For example, fine-textured, highly weathered Acrisol

461 and Ferralsol soils ~~have~~ show higher nutrient- and water-holding capacity, higher soil N
462 availability, decomposition rate and plant productivity than ~~the coarse-textured~~ soils of the
463 same Acrisols and Ferralsol soil groups (e.g., Ohta et al., 1993; Silver et al., 2000; Sotta et al.,
464 2008). Our measured nutrient leaching losses ~~from the reference land uses supported~~ concur
465 to these findings. The lower ~~solute concentrations (Table 3) and lower~~ annual nutrient leaching
466 fluxes in clay as compared to loam Acrisols (i.e., TDN, Na, Ca, Mg; Table 4) were paralleled
467 by higher gross rates of ~~NH₄⁺ soil production and immobilization~~ NH₄⁺ cycling (Allen et al.,
468 2015), ~~higher~~ soil N stocks, ECEC, ~~and~~ base saturation; (Appendix Table A1) and, ~~higher~~
469 water-holding capacity (Hassler et al., 2015) ~~and lower drainage fluxes (Table 1)~~. Nutrient
470 demand of vegetation may not be the dominant control on leaching fluxes, as the vegetation
471 structure of the reference land uses (tree density, basal area, root biomass; Appendix Table A2)
472 even seemed larger in the loam than the clay Acrisols. Similarly, the differences in tree species
473 compositions between the loam and clay Acrisol soils (Appendix Table A2) may not have
474 influenced the nutrient leaching fluxes, as supported by the comparable net primary production
475 of the reference land uses between soil types (Kotowska et al., 2015). Our findings showed that
476 soil texture was the main factor regulating nutrient leaching losses and soil fertility (e.g.,
477 nutrient stocks and N-cycling rates) in these highly weathered Acrisol soils ~~Since leaching of~~
478 ~~DON and mineral N was associated with leaching of dissolved cations (Appendix Tables A3~~
479 ~~and A4), high rates of soil N cycling in the clay Acrisol (Allen et al., 2015) had contributed to~~
480 ~~lower leaching of N with base cations, and thus conserving soil fertility (Appendix Table A1).~~

481 The influence of soil texture on soil biochemical characteristics also ~~We also observed~~
482 ~~a~~ linked to the leaching losses or, conversely, nutrient retention efficiency. ~~between N leaching~~
483 ~~and the acid buffering capacity of the soils, as~~ This was shown by the negative correlations of
484 annual DON and NO₃⁻-N leaching losses with soil base saturation, ECEC and exchangeable Al
485 across all the reference sites. The higher the N and cation leaching (as in the loam Acrisol), the

486 lower were the cation stocks and ECEC in the soil (Appendix Table A1). Similarly, the negative
487 correlation of annual NH_4^+ -N leaching losses with soil organic C suggest high retention of NH_4^+
488 in the clay Acrisol that has higher soil organic C (Appendix Table A1), higher soil microbial
489 biomass and higher gross rates of NH_4^+ cycling than in the loam Acrisol (Allen et al., 2015).
490 These all led to the higher N and base cation retention efficiency in clay than in loam Acrisols
491 (Table 5), ~~reflecting the higher nutrient and water retention capacity of the clay Acrisols.~~ The
492 positive correlations of N and base cation retention efficiency with soil base saturation, ECEC,
493 organic C and clay content across all the reference sites suggest efficient cycling of nutrients
494 between the soil and vegetation in the clay Acrisol. ~~In summary, our findings showed that soil
495 texture was an important factor regulating nutrient leaching losses and soil fertility in these
496 highly weathered Acrisol landscapes.~~

497

498 **4.3. Land-use change effects on leaching fluxes in rubber and nutrient retention** 499 **efficiency**

500 ~~The low ionic charge concentration in soil solutions of unfertilized rubber plantations,~~
501 ~~particularly in the loam Acrisol (Fig. 1; Table 3), reflected decreased leaching losses after 14-~~
502 ~~17 yrs of land use conversion (Appendix Table A2). Land-use conversion by smallholders~~
503 ~~entails (i.e., slashing and burning of the original previous vegetation) causes as well as localized~~
504 ~~manual cultivation. A large portion of nutrients in biomass are to be lost during burning~~
505 ~~(Kaufmann et al., 1995; Mackensen et al., 1996) and, after the initial and the pulse release of~~
506 ~~nutrients from pulse of nutrient release from ashes and decomposition, results in high nutrient~~
507 ~~leaching losses immediately after burning followed by continuously decreases in leaching~~
508 ~~losses with time (Klinge et al., 2004). Our smallholder rubber plantations were not fertilized~~
509 ~~during our study years, in part because the price of rubber was low during those years (Clough~~
510 ~~et al., 2015). The low ionic charge concentration in soil solutions of unfertilized rubber~~

511 plantations, particularly in the loam Acrisol (Fig. 1; Table 3), reflected decreased leaching
512 losses after 14-17 yrs of land-use conversion (Appendix Table A2).

513 ~~Without soil amendments, Previous studies have shown that~~ soil nutrient levels can decrease
514 significantly ~~after~~ years after of agricultural production land-use conversion without soil
515 amendments (,e.g., decreases in exchangeable bases (Dechert et al. 2004), P availability (Ngoze
516 et al., 2008), ~~and soil-~~N cycling availability rate and microbial N (Allen et al., 2015; Corre et
517 al., 2006; Davidson et al., 2007)). This was ~~also~~ evident in our unfertilized rubber plantations
518 with low ionic charge concentrations of soil solutions in the loam Acrisol soil (Fig. 1; Table 3).
519 ~~where, in the loam Acrisol, we measured lower annual P and DOC leaching fluxes than either~~
520 ~~in forest or jungle rubber (Table 4). The d~~A decrease in annual P leaching flux in rubber decreased
521 (Table 4) and was reflected by a decrease in Bray-extractable P ~~in the entire 2-m soil depth of~~
522 ~~the same rubber plantations~~ compared to forest (Allen et al., 2016). Compared to
523 forest Similarly, the decrease in annual DOC leaching flux in rubber (Table 4) was mirrored by
524 ~~the~~ decreases in microbial C (Allen et al., 2015), litterfall and root production (Kotowska et al.,
525 2015) in the same rubber plantations, and the overall decrease in soil organic C stocks in
526 smallholder rubber plantations in the same study region (van Straaten et al., 2015) ~~compared to~~
527 ~~forest~~. Decreases in DOC concentrations of soil solutions were possibly the reason why cations
528 in the soil solutions of the rubber plantations were strongly correlated with Cl and only weakly
529 correlated with organic-associated anions (DOC or total S; Appendix Tables A3 and A4). Our
530 results showed that disruption of nutrient cycling between the soil and ~~original~~ vegetation
531 brought about by land-use conversion to rubber plantations, combined with the absence of soil
532 amendments, had decreased P and DOC leaching nutrient leaching (Tables 3 and 4) which
533 suggest a as well soil nutrient decrease in soil fertility availability (i.e., P stocks, microbial N,
534 gross N mineralization rates; Allen et al., 2015; Allen et al., 2016).

535

4.4 Leaching fluxes in oil palm and nutrient retention efficiency in converted land uses

The most important factor influencing nutrient leaching in the smallholder oil palm plantations was fertilizer application. This was evident by the higher solute concentrations of the fertilized area compared to the frond-stacked area and to the other land uses (Fig. 1; Table 3). In the fertilized area, the stronger correlations of dissolved cations with total S and Cl, rather than with DOC, were because S and Cl are components of the applied fertilizers (see 2.1). The larger increases in solute concentrations ~~in of the~~ fertilized areas ~~of in the~~ loam Acrisol ~~compared to fertilized area than of~~ the clay Acrisol soils were ~~due attributed~~ to the following: 1) higher fertilization rates of oil palm plantations in the loam Acrisol ~~landscape~~ (see 2.1), and 2) its lower clay contents that contributed to its lower ~~nutrient and~~ water-holding capacity and nutrient retention (~~Appendix Table A1;~~ Tables 1 and 5). In fertilized areas of the loam Acrisol, the correlations among dissolved NO_3^- , total Al and acidity were likely due to nitrification of added N fertilizer and the low acid-buffering capacity of this loam Acrisol soil (i.e., low base saturation; ~~in the top 0.1 m~~ (Appendix Table A1) ~~and in the entire 2 m depth~~; Allen et al. 2016). Soil extractable NO_3^- and NH_4^+ in these smallholder plantations are elevated up to six weeks following fertilization (Hassler et al., 2017), during which time NO_3^- is susceptible to leaching. Nitrification-induced acidity may have enhanced the Al acid-buffering reaction and led to the increases in dissolved Al and acidity of soil solution (Table 3). Other studies in Indonesia and Malaysia have also reported increases in soil acidity due to N fertilization in oil palm plantations (Anuar et al., 2008; Comte et al., 2013). Even though occasional liming is practiced by smallholders in these oil palm plantations, soil pH (Appendix Table A1) was still within the Al acid-buffering range (pH 3-5; Van Breemen et al., 1983). The acidic soil water and elevated dissolved Al concentration resulting from N fertilization in these oil palm plantations may also have triggered the decrease in mycorrhizal colonization of fine roots and the increase in distorted root tips found at the same sites (Sahner et al., 2015).

561 In the fertilized areas of oil palm plantations in the loam Acrisol, increased annual
562 leaching fluxes of Na, total S, Cl, NO_3^- , TDN, Ca and Mg (Table 4) were due to applications of
563 Na-, S- and N-containing fertilizers and lime (see 2.1). The leaching losses in our oil palm
564 plantations were lower than those reported for oil palm plantations on Acrisol soils in Nigeria
565 (2.6 g Ca m^{-2} and 0.6 g Mg m^{-2} during a six-month period; Omoti et al., 1983) and Malaysia
566 ($0.3\text{-}0.6 \text{ g N m}^{-2}$ during a five-month period; Tung et al., 2009), and on Andisol soils in Papua
567 New Guinea ($3.7\text{-}10.3 \text{ g N m}^{-2} \text{ yr}^{-1}$ during a fourteen-month period; Banabas et al., 2008), all
568 of which had larger fertilization rates than our smallholders. Moreover, the increased annual
569 DOC fluxes in fertilized areas of oil palm plantations (Table 4) suggests a reduction in the
570 retention of DOC in the soil. ~~When This,~~ combined with the decreases in litterfall and root
571 production, harvest export (Kotowska et al., 2015), and decreases in soil CO_2 emissions
572 (Hassler et al., 2015) from the same oil palm plantations, ~~this provides strong additional~~
573 support for the decreases in soil organic C stocks in smallholder oil palm plantations in the
574 same study region (van Straaten et al., 2015). Altogether, our results showed the overarching
575 influence of soil texture on nutrient retention or leaching in these converted land uses. This was
576 shown by the positive correlations of annual NH_4^+ -N leaching, annual DON leaching and base
577 cation retention efficiency with ECEC, soil organic C and clay content across all sites of the
578 converted land uses.

579 The fertilization rates in our studied smallholder oil palm plantations were only 2-5
580 times lower than the nearby large-scale plantations, which were typically $230\text{-}260 \text{ kg N ha}^{-1} \text{ yr}^{-1}$
581 . Our findings of increased ~~Altogether, our results showed the overarching influence of soil~~
582 ~~texture on nutrient and water holding capacity in these converted land uses. First, this was~~
583 ~~evident from the increased leaching of~~ TDN and base cations leaching or decreased, particularly
584 in the loam Acrisol, in fertilized oil palm plantations (Table 4) that led to decreased N and base
585 cation retention efficiency, in the particularly in the loam Acrisol, soil despite the low

586 fertilization rates (Tables 4 and 5), imply for a need to optimize fertilization rate in large-scale
587 plantations, especially on coarse-texture soils which have low inherent nutrient retention, in
588 order to minimize environmental effect while maintaining production. Second, this was shown
589 by the positive correlations of annual NH_4^+ -N leaching, annual DON leaching and base cation
590 retention efficiency with ECEC, soil organic C and clay content across all sites of the converted
591 land uses.

592

593 **5 Conclusions**

594 The low solute concentrations in drainage water of the reference land uses signified low internal
595 inputs of rock-derived nutrients in these highly-weathered soils, and suggest efficient internal
596 cycling of nutrients. Our findings of lower nutrient leaching losses and higher nutrient retention
597 efficiency in the reference land uses on the clay as compared to the loam Acrisol soils supported
598 our first hypothesis, and reflected the influence of soil texture on nutrient retention- and water-
599 holding capacity. The low nutrient leaching losses in the unfertilized rubber plantations and the
600 high leaching in the fertilized oil palm plantations supported our second hypothesis. Reduced
601 P and DOC leaching in rubber plantations signaled reduction in soil fertility nutrient levels,
602 which may influence how long these rubber plantations can remain before conversion to another
603 land use. Sustainability of oil palm plantations must take into account the long-term effect of
604 chronic N fertilization on soil water acidity and Al solubility; the inherently low acid-buffering
605 capacity of Acrisol soils implies that the smallholders will be increasingly dependent on lime
606 application, which entails additional capital input. Our results highlight the need to develop soil
607 management practices that conserve soil fertility nutrients in unfertilized rubber plantations and
608 increase nutrient retention efficiency in fertilized oil palm plantations. Management practices
609 to regulate leaching losses are possibly more pressing for large-scale oil palm plantations, in

610 ~~order to minimize the reductions of ecosystem provisioning services (e.g., soil fertility and~~
611 ~~water quality) and hinder further forest conversion.~~
612 ~~Further quantification of leaching losses should focus on large-scale oil palm plantations,~~ which
613 have 2-35 times higher fertilization rates ~~than the smallholder plantations, as they~~and may have
614 a larger impact on ground water quality than the smallholder ~~plantations.~~ Process-based models,
615 used to predict yield and associated environmental footprint of these tree cash crop plantations,
616 should reflect the differences in soil management (e.g., absence or low vs. high fertilization
617 rates, weed control) between smallholder and large-scale plantations. For valid large-scale
618 extrapolation, quantification of leaching losses in oil palm plantations should not only represent
619 the spatial structure of management practices but also surface landforms, which influence water
620 redistribution (e.g., inclusion of riparian areas), and an improved water budget (e.g., estimates
621 of evapotranspiration from inter-rows).

622 *Data availability*

623 Our data are deposited in the EFForTS-IS data repository (<https://efforts-is.uni-goettingen.de>),
624 an internal data-exchange platform, which is accessible to EFForTS members only. Based on
625 data sharing agreement within EFForTS, these data are currently not publicly accessible but
626 will be made available through a written request to the corresponding and senior authors.

627 *Author contribution*

628 SK, MDC, EV and SRU conceived and designed research. SK carried out field measurements.
629 MDC, EV and SRU supported the field research. SK and HSB modelled water budget with the
630 Expert N water module. SK, MDC and EV analyzed the data. SK, MDC, ALM, OvS and EV
631 wrote the manuscript.

632 *Competing interests*

633 All authors declare no conflict of interest.

634

635 *Acknowledgements.* This study was funded by the Deutsche Forschungsgemeinschaft (DFG)
636 as part of subproject A05 (SFB 990/2) in the Collaborative Research Center 990 (EFForTS).
637 Kurniawan received a postgraduate scholarship from the Indonesian Directorate General of
638 Higher Education. We thank the village leaders, smallholders, PT REKI and Bukit Duabelas
639 National Park for fruitful collaboration. We are especially grateful to our Indonesian
640 assistants and the rangers of the forest areas. We acknowledge the Indonesian Meteorological,
641 Climatological and Geophysical Agency and the subprojects A03 and B06 for data sharing.
642 We also thank Andrea Bauer, Dirk Böttger, Martina Knaust and Kerstin Langs for their
643 assistance. This study was conducted using the research permits 215/SIP/FRP/SM/VI/2012
644 and 44/EXT/SIP/FRP/SM/V/2013, and the collection permits 2703/IPH.1/KS.02/XI/2012 and
645 S.13/KKH-2/2013, recommended by RISTEK and LIPI and issued by PHKA, Indonesia.

646

647 **References**

648 Allen, K., Corre, M.D., Kurniawan, S., Utami, S.R., and Veldkamp, E.: Spatial variability
649 surpasses land-use change effects on soil biochemical properties of converted lowland
650 landscapes in Sumatra, Indonesia, *Geoderma*, 284, 42-50,
651 <https://dx.doi.org/10.1016/j.geoderma.2016.08.010>, 2016.

652 Allen, K., Corre, M. D., Tjoa, A., and Veldkamp, E.: Soil nitrogen-cycling responses to
653 conversion of lowland forests to oil palm and rubber plantations in Sumatra, Indonesia,
654 *PLoS ONE*, 10, e0133325, <https://doi.org/10.1371/journal.pone.0133325>, 2015.

655 Anuar, A.R., Goh, K.J., Heoh, T.B., and Ahmed, O.H.: Spatial variability of soil inorganic N
656 in a mature oil palm plantation in Sabah, Malaysia, *Am. J. Appl. Sci.*, 5, 1239-1246,
657 <http://thescipub.com/PDF/ajassp.2008.1239.1246.pdf>, 2008.

658 Balasubramanian, R., Victor, T., and Begum, R.: Impact of biomass burning on rainwater
659 acidity and composition in Singapore, *J. Geophys. Res. Biogeosci.*, 104, 26881-26890,
660 <https://onlinelibrary.wiley.com/doi/10.1029/1999JD900247/epdf>, 1999.

661 Banabas, M., Turner, M.A., Scotter, D.R., and Nelson, P.N.: Losses of nitrogen fertiliser under
662 oil palm in Papua New Guinea: 1. Water balance, and nitrogen in soil solution and
663 runoff, *Aust. J. Soil Res.*, 46, 332-339, <https://doi.org/10.1071/SR07171>, 2008.

664 ~~[Bragazza, L., Freeman, C., Jones, T., Rydin, H., Limpens, J., Fenner, N., Ellis, T., Gerdol, R.,](#)~~
665 ~~[Hájek, M., Hájek, T., Iacumin, P., Kutnar, L., Tahvanainen, T., and Toberman, H.:](#)~~
666 ~~[Atmospheric nitrogen deposition promotes carbon loss from peat bogs, *Proc. Natl.*](#)~~
667 ~~[Acad. Sci. U.S.A.](#), 103, 19386-19389, <https://doi.org/10.1073/pnas.0606629104>, 2006.~~

668 ~~[BPS \(Badan Pusat Statistik\): Indonesian oil palm statistics 2013. BPS, Jakarta, Indonesia, 2014.](#)~~

669 Clough, Y., Krishna, V.V., Corre, M.D., Darras, K., Denmead, L.H., Meijide, A., Moser, S.,
670 Musshoff, O., Steinebach, S., Veldkamp, E., Allen, K., Barnes, A., Breidenbach, N.,
671 Brose, U., Buchori, D., Daniel, R., Finkeldey, R., Harahap, I., Hertel, D., Holtkamp,
672 A.M., Hörandl, E., Irawan, B., Jaya, I.N.S., Jochum, M., Klarner, B., Knohl, A.,
673 Kotowska, M.M., Krashevskaya, V., Kreft, H., Kurniawan, S., Leuschner, C., Maraun,
674 M., Melati, D.N., Opfermann, N., Pérez-Cruzado, C., Prabowo, W.E., Rembold, K.,
675 Rizali, A., Rubiana, R., Schneider, D., Tjitrosoedirdjo, S.S., Tjoa, A., Tschardtke, T.,
676 and Scheu, S.: Land-use choices follow profitability at the expense of ecological
677 functions in Indonesian smallholder landscapes, *Nature Communications*, 7, 13137,
678 <https://doi.org/10.1038/ncomms13137>, 2016.

679 ~~[Coelho, C.H., Francisco, J.G., Nogueira, R.F.P., Campos, M.L.A.M.: Dissolved organic carbon](#)~~
680 ~~[in rainwater from areas heavily impacted by sugarcane burning. *Atmospheric*](#)~~
681 ~~[Environment](#), 42, 7115-7121, <https://doi.org/10.1016/j.atmosenv.2008.05.072>, 2008.~~

- 682 Comte, I., Colin, F., Grünberger, O., Follain, S., Whalen, J.K., and Caliman, J.P.: Landscape-
683 scale assessment of soil response to long-term organic and mineral fertilizer application
684 in an industrial oil palm plantation, Indonesia, *Agric. Ecosyst. Environ.*, 169, 58-68,
685 <https://doi.org/10.1016/j.agee.2013.02.010>, 2013.
- 686 Corre, M.D., Dechert, G., and Veldkamp, E.: Soil nitrogen cycling following montane forest
687 conversion in Central Sulawesi, Indonesia, *Soil Sci. Soc. Am. J.*, 70, 359-366,
688 <https://doi.org/10.2136/sssaj2005.0061>, 2006.
- 689 Corre, M.D., Veldkamp, E., Arnold, J., and Wright, S.J.: Impact of elevated N input on soil N
690 cycling and losses in lowland and montane forests in Panama, *Ecology*, 91, 1715-
691 1729, <https://doi.org/10.1890/09-0274.1>, 2010.
- 692 Crawley, M.J.: *The R book*. John Wiley and Sons Limited, Chichester, UK, 2009.
- 693 ~~Coelho, C.H., Francisco, J.G., Nogueira, R.F.P., and Campos, M.L.A.M.: Dissolved organic~~
694 ~~carbon in rainwater from areas heavily impacted by sugarcane burning. *Atmos.*~~
695 ~~*Environ.*, 42, 7115-7121, 2008.~~
- 696 Davidson, E.A., de Carvalho, C.J.R., Figueira, A.M., Ishida, F.Y., Ometto, J.P.H.B., Nardoto,
697 G.B., Saba, R.T., Hayashi, S.N., Leal, E.C., Vieira, I.C.G., and Martinelli, L.A.:
698 Recuperation of nitrogen cycling in Amazonian forests following agricultural
699 abandonment, *Nature*, 447, 995–998, <https://doi.org/10.1038/nature05900>, 2007.
- 700 Dechert, G., Veldkamp, E., and Anas, I.: Is soil degradation unrelated to deforestation?
701 Examining soil parameters of land use systems in upland Central Sulawesi, Indonesia,
702 *Plant Soil*, 265, 197-209, <https://doi.org/10.1007/s11104-005-0885-8>, 2004.
- 703 Dechert, G., Veldkamp, E., and Brumme, R.: Are partial nutrient balances suitable to evaluate
704 nutrient sustainability of landuse systems? Results from a case study in Central

705 Sulawesi, Indonesia, Nutri. Cycl. Agroecosyst, 72, 201-212,
706 <https://doi.org/10.1007/s10705-005-1546-2>, 2005.

707 DGEC (Directorate General of Estate Crops), Tree crop estate statistics of Indonesia 2015-
708 2017: Palm oil and rubber, Indonesian Ministry of Agriculture, 2017,
709 [http://ditjenbun.pertanian.go.id/tinymcpuk/gambar/file/statistik/2017/Kelapa-Sawit-](http://ditjenbun.pertanian.go.id/tinymcpuk/gambar/file/statistik/2017/Kelapa-Sawit-2015-2017.pdf)
710 [2015-2017.pdf](http://ditjenbun.pertanian.go.id/tinymcpuk/gambar/file/statistik/2017/Kelapa-Sawit-2015-2017.pdf), .../[Karet-2015-2017.pdf](http://ditjenbun.pertanian.go.id/tinymcpuk/gambar/file/statistik/2017/Karet-2015-2017.pdf).

711 Eklund, T.J., McDowell, W.H., and Pringle, C.M.: Seasonal variation of tropical precipitation
712 chemistry: La Selva, Costa Rica, Atmos. Environ., 31, 3903-3910,
713 [https://doi.org/10.1016/S1352-2310\(97\)00246-X](https://doi.org/10.1016/S1352-2310(97)00246-X), 1997.

714 FAO (Food and Agricultural Organization): Global Forest Resources Assessment 2010, Rome,
715 2010.

716 FAO, IIASA, ISRIC, ISS-CAS, and JRC: Harmonized World Soil Database (version 1.2), FAO,
717 Rome, Italy & IIASA, Laxenburg, Austria, [http://www.fao.org/soils-portal/soil-](http://www.fao.org/soils-portal/soil-survey/soil-maps-and-databases/harmonized-world-soil-database-v12/en/)
718 [survey/soil-maps-and-databases/harmonized-world-soil-database-v12/en/](http://www.fao.org/soils-portal/soil-survey/soil-maps-and-databases/harmonized-world-soil-database-v12/en/) (Last access:
719 09 November 2017), 2012.

720 Fujii, K., Funakawa, S., Hayakawa, C., Sukartiningsih, and Kosaki, T.: Quantification of proton
721 budgets in soils of cropland and adjacent forest in Thailand and Indonesia, Plant Soil,
722 316, 241-255, <https://doi.org/10.1007/s11104-008-9776-0>, 2009.

723 Goh, K.J., Härdter, R., and Fairhurst, T.: Fertilizing for maximum return, in: Fairhurst, T. and
724 Härdter, R. (Eds.): Oil Palm: Management for Large and Sustainable Yields, PPI/PPIC
725 and IPI, Singapore, pp. 279-306, 2003.

726 Hassler, E., Corre, M.D., Tjoa, A., Damris, M., Utami, S.R., and Veldkamp, E: Soil fertility
727 controls soil-atmosphere carbon dioxide and methane fluxes in a tropical landscape

728 converted from lowland forest to rubber and oil palm plantations, *Biogeosciences*, 12,
729 5831-5852, <https://doi.org/10.5194/bg-12-5831-2015>, 2015.

730 Hassler, E., Corre, M.D., Kurniawan, S., and Veldkamp, E.: Soil nitrogen oxide fluxes from
731 lowland forests converted to smallholder rubber and oil palm plantations in Sumatra,
732 Indonesia, *Biogeosciences*, 14, 2781-2798, <https://doi.org/10.5194/bg-14-2781-2017>,
733 2017.

734 Hedin, L.O., Vitousek, P.M., and Matson, P.A.: Nutrient losses over four million years of
735 tropical forest development, *Ecology*, 84, 2231-2255, <https://doi.org/10.1890/02-4066>,
736 2003.

737 Hillel, D: *Introduction to Soil Physics*, pp. 107-114, Academic Press, California, USA, 1982.

738 Hoeft, I., Keuter, A., Quiñones, C.M., Schmidt-Walter, P., Veldkamp, E., and Corre, M.D.:
739 Nitrogen retention efficiency and nitrogen losses of a managed and phyto-diverse
740 temperate grassland, *Basic Appl. Ecol.*, 15, 207-218,
741 <https://doi.org/10.1016/j.baae.2014.04.001>, 2014.

742 Klinge, R., Araujo Martins, A.R., Mackensen, J., and Fölster, H.: Element loss on rain forest
743 conversion in East Amazonia: comparison of balances of stores and fluxes,
744 *Biogeochemistry*, 69, 63-82, <https://doi.org/10.1023/B:BIOG.0000031040.38388.9b>,
745 2004.

746 Kaufmann, J.B., Cummings, D.L., Ward, D.E., and Babbitt, R.: Fire in the Brazilian Amazon:
747 1. Biomass, nutrient pools, and losses in slashed primary forests, *Oecologia*, 104 (4),
748 397-408, <https://doi.org/10.1007/BF00341336>, 1995.

749 Klinge, R., Martins, A.A.R., Mackensen, J., and Fölster, H.: Element loss on rain forest
750 conversion in East Amazonia: comparison of balances of stores and fluxes,

751 Biogeochemistry, 69, 63-82, <https://doi.org/10.1023/B:BIOG.0000031040.38388.9b>,
752 2004.

753 Kotowska, M.M., Leuschner, C., Triadiati, T., Meriem, S., and Hertel, D.: Quantifying above-
754 and belowground biomass carbon loss with forest conversion in tropical lowlands of
755 Sumatra (Indonesia), *Glob. Chang. Biol.*, 21, 3620-3634,
756 <https://doi.org/10.1111/gcb.12979>, 2015.

757 Kurniawan, S.: Conversion of lowland forests to rubber and oil palm plantations changes
758 nutrient leaching and nutrient retention efficiency in highly weathered soils of Sumatra,
759 Indonesia, University of Goettingen, Germany, Doctoral thesis,
760 <http://hdl.handle.net/11858/00-1735-0000-0028-8706-8> (Last access: 25 May 2016),
761 2016.

762 Lehman, J., and Schroth, G.: Nutrient leaching, in: Schroth, G., and Sinclair, F.L.(Eds.): *Trees,*
763 *Crops and Soil Fertility: Concepts and Research Methods*, CABI Publishing,
764 Wallingford, UK, pp. 151-166, 2002.

765 Luskin, M.S., Christina, E.D., Kelly, L.C., and Potts, M.D.: Modern hunting practices and wild
766 meat trade in the oil palm plantation-dominated landscapes of Sumatra, Indonesia, *Hum.*
767 *Ecol.*, 42, 35-45, <https://doi.org/10.1007/s10745-013-9606-8>, 2013.

768 Mackensen, J., Hölscher, D., Klinge, R., and Fölster, H.: Nutrient transfer to the atmosphere by
769 burning of debris in Eastern Amazonia, *For. Ecol. Manage.*, 86, 121-128,
770 [https://doi.org/10.1016/S0378-1127\(96\)03790-5](https://doi.org/10.1016/S0378-1127(96)03790-5), 1996.

771 Margono, B.A., Turubanova, S., Zhuravleva, I., Potapov, P., Tyukavina, A., and Baccini, A.:
772 Mapping and monitoring deforestation and forest degradation in Sumatra (Indonesia)
773 using Landsat time series data sets from 1990 to 2010, *Environ. Res. Lett.*, 7, 1-16,
774 <https://doi.org/10.1088/1748-9326/7/3/034010>, 2012.

775 Markewitz, D., Davidson, E., Figueiredo, R., Victoria, R., and Krusche, A.: Control of cation
776 concentrations in stream waters by surface soil processes in an Amazonian watershed,
777 Nature, 410, 802–805, <https://doi.org/10.1038/35071052>, 2001.

778 Mualem, Y.: New model for predicting hydraulic conductivity of unsaturated porous-media,
779 Water Resour. Res., 12, 513-522, <https://doi.org/10.1029/WR012i003p00513>, 1976.

780 Ngoze, S., Riha, S., Lehmann, J., Verchot, L., Kinyangi, J., Mbugua, D., and Pell A.: Nutrient
781 constraints to tropical agroecosystem productivity in long-term degrading soils, Glob.
782 Chang. Biol., 14, 2810–2822, <https://doi.org/10.1111/j.1365-2486.2008.01698.x>, 2008.

783 Niu, F., Röhl, A., Hardanto, A., Meijide, A., Köhler, M., Hendrayanto, Hölscher, D.: Oil palm
784 water use: calibration of a sap flux method and a field measurement scheme, Tree
785 Physiol., 35, 563-573, <https://doi.org/10.1093/treephys/tpv013>, 2015.

786 Ohta, S., Effendi, S., Tanaka, N., and Miura, S.: Ultisols of lowland dipterocarp forest in East
787 Kalimantan, Indonesia. III. Clay minerals, free oxides, and exchangeable cations, Soil
788 Sci. Plant Nutr., 39, 1-12, <https://dx.doi.org/10.1080/00380768.1993.10416969>, 1993.

789 Omoti, U., Ataga, D.O., and Isenmila, A.E.: Leaching losses of nutrients in oil palm plantations
790 determined by tension lysimeters, Plant Soil, 73, 365-376,
791 <https://doi.org/10.1007/BF02184313>, 1983.

792 [Ponette-González, A.G., LisaMCurran, L.M., Pittman, A.M., Carlson, K.M., Steele, B.G.,](#)
793 [Ratnasari, D., Mujiman, and Weathers, K.C.: Biomass burning drives atmospheric](#)
794 [nutrient redistribution within forested peatlands in Borneo, Environ. Res. Lett., 11,](#)
795 [085003, https://doi.org/10.1088/1748-9326/11/8/085003, 2016.](#)

796 Priesack, E.: Expert-N model library documentation. Institute of Soil Ecology, National
797 Research Center for Environment and Health, Neuherberg, Germany, 2005.

798 R Development Core Team: R: A language and environment for statistical computing, R
799 Foundation for Statistical Computing, Vienna, Austria. <http://www.R-project.org> (last
800 access: 18 November 2016), 2013.

801 Rembold, K., Mangopo, H., Tjitrosoedirdjo, S.S., and Kreft, H.: Plant diversity, forest
802 dependency, and alien plant invasions in tropical agricultural landscapes, *Biodivers.*
803 *Conserv.*, 213, 234-242, <https://doi.org/10.1016/j.biocon.2017.07.020>, 2017.

804 Rist, L., Feintrenie, L., and Levang, P.: The livelihood impacts of oil palm: smallholders in
805 Indonesia, *Biodivers. Conserv.*, 19, 1009-1024, [https://doi.org/10.1007/s10531-010-](https://doi.org/10.1007/s10531-010-9815-z)
806 9815-z, 2010.

807 Sahner, J., Budi, S.W., Barus, H., Edy, N., Meyer, M., Corre, M.D., and Polle, A.: Degradation
808 of root community traits as indicator for transformation of tropical lowland rain forests
809 into oil palm and rubber plantations, *PLoS ONE*, 10, e0138077,
810 <https://doi.org/10.1371/journal.pone.0138077>, 2015.

811 Schlesinger, W.H. and Bernhardt, E.: *Biogeochemistry - an analysis of global change*, third
812 edition, Academic Press, California, USA, 2013.

813 Schwendenmann, L. and Veldkamp, E.: The role of dissolved organic carbon, dissolved organic
814 nitrogen and dissolved inorganic nitrogen in a tropical wet forest ecosystem,
815 *Ecosystems*, 8, 339-351, <https://doi.org/10.1007/s10021-003-0088-1>, 2005.

816 Silver, W.L., Neff, J., McGroddy, M., Veldkamp, E., Keller, M., and Cosme, R.: Effects of soil
817 texture on belowground carbon and nutrient storage in a lowland Amazonian forest
818 ecosystem, *Ecosystems*, 3, 193-209, <https://doi.org/10.1007/s100210000019>, 2000.

819 Sotta, E.D., Corre, M.D., and Veldkamp, E.: Differing N status and N retention processes of
820 soils under old-growth lowland forest in Eastern Amazonia, Caxiuanã, Brazil, *Soil Biol.*
821 *Biochem.*, 40, 740-750, <https://doi.org/10.1016/j.soilbio.2007.10.009>, 2008.

- 822 Sundarambal, P., Balasubramanian, R., Tkalich, P., and He, J.: Impact of biomass burning on
823 ocean water quality in Southeast Asia through atmospheric deposition: field
824 observations, Atmos. Chem. Phys., 10, 11323–11336, [https://doi.org/10.5194/acp-10-](https://doi.org/10.5194/acp-10-11323-2010)
825 [11323-2010](https://doi.org/10.5194/acp-10-11323-2010), 2010.
- 826 Suryatmojo, H., Fujimoto, M., Yamakawa, Y., Kosugi, K., and Mizuyama, T.: Water balance
827 changes in the tropical rainforest with intensive forest management system, Int. J.
828 Sustain. Future Hum. Secur., 1, 56-62, <https://doi.org/10.1016/j.proenv.2015.07.039>,
829 2013.
- 830 Tarigan, S.D., Sunarti, Wiegand, K., Dislich, C., Slamet, B., Heinonen, J., and Meyer, K.:
831 Mitigation options for improving the ecosystem function of water flow regulation in a
832 watershed with rapid expansion of oil palm plantations, Sustainability of Water Quality
833 and Ecology, 8, 4-13, <http://dx.doi.org/10.1016/j.swaqe.2016.05.001>, 2016.
- 834 Tung, P.G., Yusoff, M.K., Majid, N.M., Joo, G.K., and Huang, G.H.: Effect of N and K
835 fertilizers on nutrient leaching and groundwater quality under mature oil palm in Sabah
836 during the monsoon period, Am. J. Appl. Sci., 6, 1788-1799,
837 <https://doi.org/10.3844/ajassp.2009.1788.1799>, 2009.
- 838 Van Breemen, N., Mulder, J., and Driscoll, C.T.: Acidification and alkalization of soils, Plant
839 Soil, 75, 283-308, <https://doi.org/10.1007/BF02369968>, 1983.
- 840 Van Genuchten, M.T.: A closed-form equation for predicting the hydraulic conductivity of
841 unsaturated soils, Soil Sci. Soc. Am. J., 44, 892-898,
842 <https://doi.org/10.2136/sssaj1980.03615995004400050002x>, 1980.
- 843 van Straaten, O., Corre, M.D., Wolf, K., Tchienkoua, M., Cuellar, E., Matthews, R.B., and
844 Veldkamp, E.: Conversion of lowland tropical forests to tree cash-crop plantations loses

845

up to half of stored soil organic carbon, Proc. Natl. Acad. Sci. U.S.A. 112, 9956-9960,

846

<https://doi.org/10.1073/pnas.1504628112>, 2015.

847 **Table 1.** Simulated water balance during 2013 in different land uses within ~~two landscapes the~~
 848 ~~(loam and clay Acrisol soils)~~ in Jambi, Sumatra, Indonesia.

Water balance components (mm yr ⁻¹)	Forest	Jungle rubber	Rubber plantations	Oil palm plantations
loam Acrisol soil (precipitation: 3418 mm yr ⁻¹)				
Evapotranspiration	1384	1224	1077	1027
Transpiration	1033	815	594	437
Evaporation	155	213	287	408
Interception	196	196	196	182
Water drainage	1483	1487	1544	1614
Runoff	545	704	800	761
clay Acrisol soil (precipitation: 3475 mm yr ⁻¹)				
Evapotranspiration	1622	1271	1114	1071
Transpiration	1284	861	402	446
Evaporation	157	242	548	459
Interception	181	168	164	166
Water drainage	1117	1268	1280	1311
Runoff	722	932	1070	1087

849

850 **Table 2.** Mean (\pm SE, $n = 2$) volume-weighted element concentrations and annual inputs in
 851 bulk precipitation, measured bi-weekly to monthly from February to December 2013 within the
 852 two landscapes with two landscapes (loam and clay Acrisol soils) in Jambi, Sumatra, Indonesia.

Elements	Volume-weighted		Annual input	
	concentration (mg L^{-1})		(g m^{-2} yr $^{-1}$)	
	loam Acrisol	clay Acrisol	loam Acrisol	clay Acrisol
Ammonium (NH $_4^+$ -N)	0.17 (0.02)	0.20 (0.02)	0.58 (0.06)	0.69 (0.07)
Nitrate (NO $_3^-$ -N)	0.04 (0.02)	0.07 (0.01)	0.13 (0.06)	0.26 (0.04)
Dissolved organic nitrogen (N)	0.17 (0.01)	0.20 (0.04)	0.58 (0.02)	0.70 (0.14)
Total dissolved nitrogen (N)	0.38 (0.00)	0.47 (0.07)	1.29 (0.01)	1.64 (0.26)
Dissolved organic carbon (C)	8.15 (0.19)	7.44 (0.07)	27.84 (0.66)	25.86 (0.25)
Sodium (Na)	1.84 (0.04)	1.90 (0.18)	6.30 (0.13)	6.61 (0.63)
Potassium (K)	0.16 (0.04)	0.28 (0.14)	0.55 (0.15)	0.96 (0.49)
Calcium (Ca)	0.32 (0.02)	0.36 (0.07)	1.09 (0.08)	1.24 (0.24)
Magnesium (Mg)	0.07 (0.01)	0.09 (0.01)	0.24 (0.05)	0.30 (0.04)
Total aluminum (Al)	0.02 (0.01)	0.01 (0.00)	0.05 (0.03)	0.04 (0.01)
Total iron (Fe)	0.01 (0.00)	0.01 (0.00)	0.04 (0.01)	0.03 (0.01)
Total manganese (Mn)	0.001 (0.00)	0.001 (0.00)	0.003 (0.00)	0.004 (0.00)
Total phosphorus (P)	0.01 (0.00)	0.02 (0.00)	0.04 (0.01)	0.08 (0.01)
Total sulfur (S)	0.26 (0.00)	0.30 (0.03)	0.90 (0.01)	1.04 (0.10)
Total silica (Si)	0.02 (0.01)	0.03 (0.01)	0.06 (0.02)	0.09 (0.03)
Chloride (Cl)	1.79 (0.25)	1.54 (0.30)	6.11 (0.84)	5.34 (1.06)

853

854 **Table 3.** Mean (\pm SE, $n = 4$, except for oil palm $n = 3$) nutrient concentrations in soil solutions
855 from a depth of 1.5 m in different land uses within ~~the two landscapes~~ (loam and clay Acrisol
856 soils) in Jambi, Sumatra, Indonesia. Means followed by different lowercase letters indicate
857 significant differences among land uses within each ~~landscape-soil type~~ and different uppercase
858 letters indicate significant differences between ~~landscapes-soil types~~ for each reference land use
859 (Linear mixed effects models with Fisher's LSD test at $P \leq 0.05$, and † at $P \leq 0.09$ for marginal
860 significance).

Elements	Forest	Jungle rubber	Rubber	Oil palm fertilized area	Oil palm frond- stacked area
	loam Acrisol soil				
pH	4.3 (0.0) _{a†}	4.3 (0.1) _{a†}	4.4 (0.0) _{a†}	4.1 (0.1) _{b†}	4.3 (0.0) _{a†}
Ammonium (mg NH ₄ ⁺ -N <u>L</u> ⁻¹)	0.2 (0.0) _{A†}	0.3 (0.1)	0.2 (0.0)	0.2 (0.0)	0.2 (0.0)
Nitrate (mg NO ₃ ⁻ -N <u>L</u> ⁻¹)	0.1 (0.1) _b	0.1 (0.0) _{bA}	0.0 (0.0) _c	0.3 (0.2) _a	0.1 (0.0) _b
Dissolved organic N (mg N <u>L</u> ⁻¹)	0.2 (0.0) _{aA†}	0.1 (0.0) _b	0.1 (0.0) _b	0.1 (0.0) _{ab}	0.1 (0.0) _b
Total dissolved N (mg N <u>L</u> ⁻¹)	0.5 (0.1) _{A†}	0.4 (0.1) _{A†}	0.2 (0.0)	0.6 (0.2)	0.3 (0.0)
Dissolved organic C (mg C <u>L</u> ⁻¹)	3.7 (0.3) _{ab}	4.0 (0.5) _{ab}	3.1 (0.2) _c	4.2 (0.1) _a	3.6 (0.1) _b
Sodium (mg Na <u>L</u> ⁻¹)	3.2 (0.1) _{bA}	2.4 (0.2) _c	2.2 (0.2) _c	7.2 (3.9) _a	2.3 (0.3) _c
Potassium (mg K <u>L</u> ⁻¹)	0.4 (0.0)	0.2 (0.1)	0.3 (0.1)	0.4 (0.1)	0.4 (0.1)
Calcium (mg Ca <u>L</u> ⁻¹)	0.8 (0.0) _b	0.7 (0.1) _c	0.7 (0.1) _c	2.7 (0.9) _a	0.7 (0.1) _c
Magnesium	0.3 (0.0) _{bA}	0.2 (0.0) _c	0.3 (0.1) _b	0.5 (0.1) _a	0.2 (0.0) _c

(mg Mg L^{-1})					
Total aluminum	0.4 (0.1) _{bA}	0.2 (0.0) _c	0.3 (0.0) _b	1.2 (0.7) _a	0.1 (0.0) _c
(mg Al L^{-1})					
Total iron (mg Fe L^{-1})	0.2 (0.1) _{A†}	0.0 (0.0)	0.0 (0.0)	0.0 (0.0)	0.1 (0.1)
Total manganese	0.02 (0.00)	0.01 (0.00)	0.01 (0.00)	0.01 (0.00)	0.01 (0.00) _B
(mg Mn L^{-1})					
Total phosphorus	0.008 (0.0) _{a†}	0.004 (0.0) _{b†}	0.003 (0.0) _{c†}	0.005 (0.0) _{ab†}	0.005 (0.0) _{ab†}
(mg P L^{-1})					
Total sulfur (mg S L^{-1})	0.16 (0.00) _{a†}	0.14 (0.00) _{bc†}	0.10 (0.00) _{c†}	0.14 (0.00) _{ab†}	0.12 (0.00) _{b†}
Total silica (mg Si L^{-1})	0.5 (0.1)	0.3 (0.1) _{B†}	0.2 (0.1)	0.3 (0.1)	0.2 (0.0)
Chloride (mg Cl L^{-1})	8.9 (0.8) _{bA†}	6.6 (0.8) _c	6.7 (0.6) _c	21.0 (2.7) _a	6.2 (0.8) _c
clay Acrisol soil					
pH	4.3 (0.1) _c	4.4 (0.1) _{bc}	4.4 (0.0) _c	4.6 (0.1) _{ab}	4.6 (0.1) _a
Ammonium	0.2 (0.0) _{B†}	0.1 (0.0)	0.1 (0.0)	0.2 (0.0)	0.1 (0.0)
(mg $\text{NH}_4^+\text{-N}$ L^{-1})					
Nitrate	0.1 (0.0)	0.0 (0.0) _B	0.2 (0.1)	0.9 (0.9)	0.0 (0.0)
(mg $\text{NO}_3^-\text{-N}$ L^{-1})					
Dissolved organic N	0.1 (0.0) _{a†B†}	0.1 (0.0) _{a†}	0.1 (0.0) _{ab†}	0.0 (0.0) _{b†}	0.0 (0.0) _{b†}
(mg N L^{-1})					
Total dissolved N	0.3 (0.0) _{B†}	0.2 (0.0) _{B†}	0.4 (0.1)	1.1 (0.9)	0.2 (0.0)
(mg N L^{-1})					
Dissolved organic C	3.3 (0.4)	4.0 (0.3)	2.9 (0.1)	4.8 (0.9)	4.4 (1.1)
(mg C L^{-1})					
Sodium (mg Na L^{-1})	2.4 (0.2) _{bc B}	2.5 (0.1) _b	2.0 (0.1) _c	4.6 (1.2) _a	2.5 (0.5) _{bc}
Potassium (mg K L^{-1})	0.3 (0.0)	0.3 (0.1)	0.3 (0.0)	0.4 (0.1)	0.2 (0.1)

Calcium (mg Ca \underline{L}^{-1})	0.7 (0.1)	0.7 (0.0)	0.7 (0.1)	0.8 (0.2)	0.5 (0.1)
Magnesium (mg Mg \underline{L}^{-1})	0.3 (0.0) _B	0.3 (0.0)	0.3 (0.0)	0.4 (0.1)	0.2 (0.1)
Total aluminum (mg Al \underline{L}^{-1})	0.2 (0.0) _B	0.2 (0.1)	0.3 (0.1)	0.2 (0.1)	0.1 (0.0)
Total iron (mg Fe \underline{L}^{-1})	0.0 (0.0) _{b† B†}	0.0 (0.0) _{b†}	0.0 (0.0) _{b†}	0.0 (0.0) _{b†}	0.1 (0.0) _{a†}
Total manganese (mg Mn \underline{L}^{-1})	0.01 (0.00)	0.01 (0.00)	0.01 (0.00)	0.08 (0.10)	0.02 (0.00)
Total phosphorus (mg P \underline{L}^{-1})	0.010 (0.0)	0.004 (0.0)	0.004 (0.0)	0.004 (0.0)	0.010 (0.0)
Total sulfur (mg S \underline{L}^{-1})	0.15 (0.00)	0.11 (0.00)	0.11 (0.00)	0.13 (0.00)	0.12 (0.00)
Total silica (mg Si \underline{L}^{-1})	0.4 (0.0)	0.6 (0.1) _{A†}	0.3 (0.0)	1.0 (0.4)	0.7 (0.2)
Chloride (mg Cl \underline{L}^{-1})	6.4 (0.6) _{B†}	6.8 (0.9)	5.7 (0.8)	7.2 (2.1)	4.6 (0.8)

862 **Table 4.** Mean (\pm SE, $n = 4$, except for oil palm $n = 3$) annual (2013) nutrient leaching fluxes
863 measured at a depth of 1.5 m in different land uses within ~~two landscapes (the~~ loam and clay
864 Acrisol soils) in Jambi, Sumatra, Indonesia. Means followed by different lowercase letters
865 indicate significant differences among land uses within each ~~landscape-soil type~~ and different
866 uppercase letters indicate significant differences between ~~landscapes-soil types~~ for each
867 reference land use (Linear mixed effects models with Fisher's LSD test at $P \leq 0.05$, and † at P
868 ≤ 0.09 for marginal significance).

Elements	Forest	Jungle rubber	Rubber	Oil palm fertilized area	Oil palm frond- stacked area
	loam Acrisol soil				
Ammonium (g NH ₄ ⁺ -N m ⁻² yr ⁻¹)	0.3 (0.0) _{ab A†}	0.5 (0.3) _a	0.2 (0.01) _{bc}	0.3 (0.0) _{ab}	0.2 (0.0) _c
Nitrate (g NO ₃ ⁻ -N m ⁻² yr ⁻¹)	0.1 (0.1) _{ab}	0.1 (0.1) _{ab A}	0.0 (0.0) _b	0.6 (0.3) _a	0.1 (0.0) _{ab}
Dissolved organic N (g N m ⁻² yr ⁻¹)	0.2 (0.0) _{A†}	0.1 (0.0)	0.1 (0.0)	0.2 (0.1)	0.1 (0.0)
Total dissolved N (g N m ⁻² yr ⁻¹)	0.6 (0.1) _{ab† A†}	0.8 (0.3) _{ab†}	0.4 (0.0) _{b†}	1.1 (0.3) _{a†}	0.4 (0.1) _{b†}
Dissolved organic C (g C m ⁻² yr ⁻¹)	4.2 (0.5) _{bc}	6.2 (1.5) _{ab}	3.9 (0.2) _c	7.3 (0.2) _a	4.2 (0.4) _{bc}
Sodium (g Na m ⁻² yr ⁻¹)	3.8 (0.4) _{bA}	3.7 (0.8) _b	3.1 (0.3) _b	13.1 (7.6) _a	3.1 (0.5) _b
Potassium (g K m ⁻² yr ⁻¹)	0.4 (0.1)	0.4 (0.2)	0.4 (0.1)	0.7 (0.2)	0.4 (0.1)
Calcium	1.0 (0.1) _{bA}	1.2 (0.3) _b	0.9 (0.1) _b	4.6 (1.3) _a	1.0 (0.2) _b

(g Ca m ⁻² yr ⁻¹)					
Magnesium	0.4 (0.0) _{bA}	0.4 (0.1) _b	0.4 (0.1) _b	0.9 (0.2) _a	0.3 (0.1) _b
(g Mg m ⁻² yr ⁻¹)					
Total aluminum	0.4 (0.1) _{bA}	0.3 (0.1) _b	0.4 (0.0) _b	2.3 (1.3) _a	0.2 (0.0) _b
(g Al m ⁻² yr ⁻¹)					
Total iron	0.20 (0.10)	0.02 (0.01)	0.03 (0.01)	0.04 (0.00)	0.10 (0.10)
(g Fe m ⁻² yr ⁻¹)					
Total manganese	0.02 (0.01)	0.03 (0.02)	0.01 (0.01)	0.03 (0.00)	0.01 (0.00)
(g Mn m ⁻² yr ⁻¹)					
Total phosphorus	0.01 (0.00) _{a†}	0.01 (0.00) _{abc†}	0.00 (0.00) _{c†}	0.01 (0.00) _{ab†}	0.01 (0.00) _{bc†}
(g P m ⁻² yr ⁻¹)					
Total sulfur	0.20 (0.00) _{ab}	0.20 (0.10) _{ab}	0.13 (0.01) _b	0.24 (0.00) _a	0.15 (0.00) _{ab}
(g S m ⁻² yr ⁻¹)					
Total silica	0.7 (0.2) _{A†}	0.6 (0.3)	0.4 (0.1)	0.4 (0.1)	0.3 (0.1)
(g Si m ⁻² yr ⁻¹)					
Chloride	10.5 (0.9) _{bA}	11.5 (2.4) _b	9.1 (0.6) _b	38.0 (6.7) _a	7.8 (1.2) _b
(g Cl m ⁻² yr ⁻¹)					

clay Acrisol soil


Ammonium	0.2 (0.0) _{B†}	0.2 (0.0)	0.2 (0.0)	0.2 (0.0)	0.2 (0.0)
(g NH ₄ ⁺ -N m ⁻² yr ⁻¹)					
Nitrate	0.1 (0.1)	0.0 (0.0) _B	0.3 (0.2)	1.1 (1.1)	0.0 (0.0)
(g NO ₃ ⁻ -N m ⁻² yr ⁻¹)					
Dissolved organic N	0.1 (0.0) _{B†}	0.1 (0.0)	0.1 (0.0)	0.1 (0.0)	0.1 (0.0)
(g N m ⁻² yr ⁻¹)					
Total dissolved N	0.3 (0.1) _{B†}	0.3 (0.0)	0.6 (0.2)	1.4 (1.1)	0.3 (0.0)

(g N m ⁻² yr ⁻¹)					
Dissolved organic C	3.4 (0.4) _c	5.4 (0.7) _{ab}	3.6 (0.2) _{bc}	6.2 (1.4) _a	5.6 (1.0) _{ab}
(g C m ⁻² yr ⁻¹)					
Sodium	2.5 (0.4) _{bB}	3.2 (0.3) _b	2.5 (0.1) _b	6.3 (1.8) _a	3.3 (0.6) _b
(g Na m ⁻² yr ⁻¹)					
Potassium	0.3 (0.0)	0.3 (0.1)	0.3 (0.1)	0.5 (0.1)	0.2 (0.1)
(g K m ⁻² yr ⁻¹)					
Calcium	0.7 (0.1) _B	0.9 (0.0)	0.8 (0.1)	1.0 (0.2)	0.7 (0.1)
(g Ca m ⁻² yr ⁻¹)					
Magnesium	0.2 (0.0) _{bB}	0.3 (0.0) _b	0.3 (0.0) _b	0.6 (0.1) _a	0.2 (0.1) _b
(g Mg m ⁻² yr ⁻¹)					
Total aluminum	0.2 (0.0) _B	0.2 (0.1)	0.3 (0.1)	0.3 (0.1)	0.1 (0.0)
(g Al m ⁻² yr ⁻¹)					
Total iron	0.02 (0.00)	0.03 (0.00)	0.02 (0.00)	0.01 (0.0)	0.06 (0.05)
(g Fe m ⁻² yr ⁻¹)					
Total manganese	0.01 (0.00)	0.01 (0.00)	0.01 (0.00)	0.09 (0.07)	0.02 (0.00)
(g Mn m ⁻² yr ⁻¹)					
Total phosphorus	0.01 (0.00)	0.01 (0.00)	0.01 (0.00)	0.01 (0.00)	0.02 (0.01)
(g P m ⁻² yr ⁻¹)					
Total sulfur	0.16 (0.0) _{ab}	0.15 (0.0) _{ab}	0.14 (0.0) _b	0.17 (0.0) _a	0.17 (0.0) _{ab}
(g S m ⁻² yr ⁻¹)					
Total silica	0.3 (0.1) _{bB†}	0.7 (0.1) _{ab}	0.3 (0.0) _b	1.3 (0.6) _a	0.8 (0.3) _{ab}
(g Si m ⁻² yr ⁻¹)					
Chloride	6.0 (0.3) _B	8.2 (1.3)	6.9 (1.0)	9.8 (3.0)	5.6 (0.6)
(g Cl m ⁻² yr ⁻¹)					

870 **Table 5.** Mean (\pm SE, $n = 4$, except for oil palm $n = 3$) nitrogen and base cation retention
871 efficiency in soils under different land uses within ~~two landscapes (the~~ loam and clay Acrisol
872 soils) in Jambi, Sumatra, Indonesia. Mean followed by different lower case letters indicate
873 significant differences among land uses within each landscape-soil type and different upper case
874 letters indicate significant differences between landscapes-soil types for each reference land use
875 (Linear mixed effects models with Fisher's LSD test at $P \leq 0.05$, and † at $P = 0.07$ for marginal
876 significance).

Characteristic	Forest	Jungle rubber	Rubber	Oil palm
loam Acrisol soil				
N retention efficiency (mg N m ⁻² d ⁻¹ /mg N m ⁻² d ⁻¹)	0.997 (0.000) _{a B}	0.996 (0.001) _{a B†}	0.998 (0.000) _a	0.995 (0.001) _b
Base cation retention efficiency (mol _{charge} m ⁻² yr ⁻¹ / mol _{charge} m ⁻²)	0.455 (0.094) _{a† B}	0.591 (0.088) _{a† B†}	0.699 (0.08259) _{a†}	0.280 (0.128) _{b†}
clay Acrisol soil				
N retention efficiency (mg N m ⁻² d ⁻¹ /mg N m ⁻² d ⁻¹)	0.999 (0.000) _A	0.999 (0.000) _{A†}	0.997 (0.001)	0.998 (0.001)
Base cation retention efficiency (mol _{charge} m ⁻² yr ⁻¹ / mol _{charge} m ⁻²)	0.812 (0.084) _A	0.852 (0.083) _{A†}	0.841 (0.025)	0.894 (0.028)

877



878

879 **Figure 1.** Partial cation-anion charge balance of the major solutes (with concentrations >0.03 mg

880 L^{-1}) in soil water at a depth of 1.5 m in different land uses on the loam (top panel) and clay (bottom

881 panel) Acrisol soils in Jambi, Sumatra, Indonesia. The y-axis scale of the oil palm fertilized area

882 in the loam Acrisol soil is twice than the other land uses.

883 **Appendix A. Soil and vegetation characteristics, and Pearson correlations among solute**
884 **concentrations in each land use within each landscapesoil type**
885 **Table A1.** Soil characteristics in the top 0.1 m of soil (except for clay content, which is for 1-2 m)
886 in different land uses within ~~two landscapes (the~~ loam and clay Acrisol soils) in Jambi, Sumatra,
887 Indonesia. Mean (\pm SE, n = 4, except for clay content n = 3) followed by different lower case
888 letters indicate significant differences among land uses within each landscape-soil type and
889 different upper case letters indicate significant differences between landscapes-soil types for each
890 reference land use (Linear mixed effects models with Fisher's LSD test at $P \leq 0.05$, and † at $P \leq$
891 0.09 for marginal significance). These soil characteristics were reported by Allen et al. (2015).

Characteristic / land use	Forest	Jungle rubber	Rubber plantation	Oil palm plantation
	loam Acrisol soil			
Bulk density (g cm ⁻³)	1.0 (0.04) ab	0.9 (0.03) b A	1.1 (0.1) a	1.1 (0.1) a
pH (1:4 H ₂ O)	4.3 (0.04) b†	4.3 (0.03) b† B	4.5 (0.1) ab†	4.5 (0.1) a†
Soil organic C (kg C m ⁻²)	2.6 (0.2)	2.7 (0.3) B	2.0 (0.3)	1.8 (0.2)
Total N (g N m ⁻²)	182.9 (10.8)	186.1 (11.0) B	172.6 (23.8)	145.0 (13.5)
C:N ratio	14.3 (0.2) a	13.7 (0.8) a	11.7 (0.7) b	12.5 (0.5) ab
Effective cation exchange capacity (mmolc kg ⁻¹)	44.8 (5.0)	40.6 (7.6) B	46.0 (5.4)	39.5 (7.9)
Base saturation (%)	10.6 (0.5) b† B	16.0 (2.2) ab†	21.1 (7.5) ab†	27.9 (5.4) a†
Potassium (g K m ⁻²)	3.3 (0.3)	2.6 (0.2) B	3.4 (0.8)	2.1 (0.8)
Sodium (g Na m ⁻²)	0.5 (0.1) c B	1.5 (0.2) b B	1.4 (0.1) b	3.9 (1.1) a
Calcium (g Ca m ⁻²)	5.5 (2.0)	6.9 (0.8) B†	14.5 (7.1)	18.5 (7.4)
Magnesium (g Mg m ⁻²)	1.8 (0.1)	2.0 (0.3) B	3.4 (1.4)	1.7 (0.9)
Aluminum (g Al m ⁻²)	33.1 (3.5)	29.6 (6.6) B	30.7 (4.3)	23.5 (2.7)

Iron (g Fe m ⁻²)	0.8 (0.1) _{aB}	0.3 (0.02) _{bc B}	0.3 (0.1) _c	0.5 (0.02) _{ab}
Manganese (g Mn m ⁻²)	0.3 (0.1)	0.4 (0.2) _B	0.8 (0.3)	0.5 (0.2)
Bray-extractable phosphorus (g P m ⁻²)	0.5 (0.1) _B	0.7 (0.1)	0.5 (0.1)	0.8 (0.1)
Clay at 1.0-1.5 m (%)	33.3 (7.6)	42.4 (9.9)	46.1 (9.9)	43.3 (2.8)
Clay at 1.5-2.0 m (%)	37.3 (8.7)	44.5 (10.0)	43.4 (6.5)	47.6 (4.5)

clay Acrisol soil

Bulk density (g cm ⁻³)	1.0 (0.1)	0.8 (0.1) _B	0.9 (0.1)	0.9 (0.1)
pH (1:4 H ₂ O)	4.2 (0.04) _b	4.5 (0.04) _{aA}	4.5 (0.1) _a	4.4 (0.04) _a
Soil organic C (kg C m ⁻²)	3.3 (0.5)	4.3 (0.4) _A	2.8 (0.4)	3.5 (0.2)
Total N (g N m ⁻²)	263.4 (67.1)	331.4 (34.1) _A	198.9 (32.5)	260.2 (22.6)
C:N ratio	13.1 (1.3)	13.0 (0.3)	14.3 (0.6)	13.5 (0.2)
Effective cation exchange capacity (mmolc kg ⁻¹)	94.3 (40.8)	124.5 (25.5) _A	71.3 (22.3)	78.1 (8.4)
Base saturation (%)	22.9 (5.6) _A	23.2 (5.8)	20.1 (2.6)	37.5 (7.1)
Potassium (g K m ⁻²)	9.4 (3.9)	9.6 (2.6) _A	4.2 (1.1)	4.8 (0.9)
Sodium (g Na m ⁻²)	3.6 (0.8) _A	4.2 (0.2) _A	3.7 (1.3)	1.9 (1.3)
Calcium (g Ca m ⁻²)	32.3(21.2)	33.3 (10.9) _{A†}	14.7 (2.8)	59.1 (19.5)
Magnesium (g Mg m ⁻²)	7.3 (3.9)	12.0 (4.1) _A	4.0 (0.9)	3.5 (0.8)
Aluminum (g Al m ⁻²)	50.9 (22.7)	76.6 (15.6) _A	47.2 (17.6)	34.4 (2.0)
Iron (g Fe m ⁻²)	3.7 (1.1) _{aA}	3.0 (0.4) _{aA}	2.3 (0.6) _a	0.7 (0.3) _b
Manganese (g Mn m ⁻²)	4.5 (3.1)	2.5 (0.7) _A	1.5 (0.4)	3.4 (1.3)
Bray-extractable phosphorus (g P m ⁻²)	1.4 (0.1) _{ab A}	0.8 (0.1) _{bc}	0.4 (0.04) _c	4.7 (1.5) _a
Clay at 1.0-1.5 m (%)	39.0 (13.0)	62.8 (12.6)	40.8 (10.3)	62.8 (3.7)
Clay at 1.5-2.0 m (%)	41.3 (11.2)	46.6 (16.2)	36.5 (10.8)	63.3 (6.1)

893 **Table A2.** Mean (\pm SE, $n = 4$) tree density, diameter at breast height (DBH), basal area, height,
894 cumulative fine root mass in the top 1-m depth and the most common tree species with DBH \geq
895 0.10 m in different land uses within ~~two landscapes (the loam and clay Acrisol soils)~~ in Jambi,
896 Sumatra, Indonesia. The vegetation characteristics (e.g. tree density, DBH, basal area, and height)
897 were reported by Kotowska et al. (2015); ~~while the five most common numerous tree species~~
898 ~~families~~ with DBH \geq 0.10 m were ~~recorded based based from on trees found in five subplots (5 m~~
899 ~~x 5 m) of each replicate plot (50 m x 50 m) which had \geq 20 individuals, except Fabaceae spp.,~~
900 ~~which had $<$ 20 individuals (reported by Rembold et al. (-unpublished data 2017)) and Rembold~~
901 ~~(pers. comm.)~~. The fine root mass in the top 1-m soil depth was measured in our present study.
902 Mean of fine root mass followed by different lower case letters indicate significant differences
903 among land uses within each ~~landscape soil type (Linear mixed effects model one-way ANOVA~~
904 with Fisher's LSD test at $P \leq 0.05$, and † at $P \leq 0.09$ for marginal significance).

Characteristics	Forest	Jungle rubber	Rubber	Oil palm
	loam Acrisol soil			
Plantation age (years)	not determined (ND)	ND	14 – 17	12 – 16
Tree density (trees ha ⁻¹)	658 (26)	525 (60)	440 (81)	140 (4)
DBH (cm)	21.0 (0.5)	16.8 (0.5)	17.8 (1.2)	not applicable (NA)
Basal area (m ² ha ⁻¹)	30.7 (1.0)	16.6 (0.4)	12.2 (1.6)	NA
Tree height (m)	20.0 (0.6)	14.0 (0.2)	13.4 (0.5)	4.9 (0.6)

Fine root mass in the top 1-m soil depth (g m ⁻²)	290.2 (82.6) ab†	143.9 (33.0) b	188.2 (37.6) b	356.8 (49.9) a
---	------------------	----------------	----------------	----------------

Common trees <u>Five most numerous tree families-species</u>	<i>Aporosa spp., Burseraceae,</i> <u><i>Dipterocarpaceae,</i></u> <u><i>Sapotaceae,</i></u> <u><i>Phyllanthaceae,</i></u> <u><i>Euphorbiaceae</i></u> <u><i>Burseraceae</i></u> <u><i>spp., Dipterocarpaceae</i></u> <u><i>spp., Fabaceae spp.,</i></u> <u><i>Girardinia spp., Myrtaceae</i></u> <u><i>spp., Plaquium spp.,</i></u> <u><i>Porterandia spp., Shorea</i></u> <u><i>spp.</i></u>	<i>Alstonia spp.,</i> <u><i>Artocarpus spp.,</i></u> <u><i>Fabaceae spp.,</i></u> <u><i>Hevea spp.,</i></u> <u><i>Macaranga spp.,</i></u> <u><i>Porterandia</i></u> <u><i>sp., Euphorbiaceae,</i></u> <u><i>Moraceae,</i></u> <u><i>Apocynaceae,</i></u> <u><i>Rubiaceae,</i></u> <u><i>Fabaceae, Sloetia</i></u> <u><i>sp.</i></u>	<i>Hevea brasiliensis</i>	<i>Elaeis guineensis</i>
--	---	---	---------------------------	--------------------------

clay Acrisol soil

Plantation age (years)	ND	ND	7 – 16	9 – 13
Tree density (trees ha ⁻¹)	471 (31)	685 (72)	497 (15)	134 (6)
DBH (cm)	23.0 (0.4)	17.3 (0.6)	15.2 (0.7)	NA
Basal area (m ² ha ⁻¹)	29.4 (1.7)	21.1 (1.4)	10.0 (1.4)	NA
Tree height (m)	17.0 (0.5)	15.2 (0.3)	13.4 (0.1)	4.0 (0.3)

Fine root mass in the top 1-m soil depth (g m ⁻²)	140.4 (33.0) c	402.2 (65.9) b	309.6 (16.0) bc	630.1 (86.2) a
---	----------------	----------------	-----------------	----------------

<u>Five most</u>	<u>Phyllanthaceae,</u>	<u>Euphorbiaceae,</u>	<i>Hevea</i>	<i>Elaeis</i>
<u>numerous tree</u>	<u>Olacaceae, Fabaceae,</u>	<u>Moraceae,</u>	<i>brasiliensis</i>	<i>guineensis</i>
<u>families</u>	<u>Meliaceae,</u>	<u>Fabaceae,</u>		
<u>Common</u>	<u>Dipterocarpaceae</u>	<u>Apocynaceae,</u>		
<u>tree species</u>	<u>Archidendron sp.,</u>	<u>Ixonanthaceae</u>		
	<u>Baccaurea spp.,</u>	<u>Artocarpus spp.,</u>		
	<u>Ochanostachys sp.</u>	<u>Endospermum sp.,</u>		
		<u>Hevea sp.,</u>		
		<u>Macaranga spp.</u>		

906 **Table A3.** Pearson correlations among element concentrations (mg L⁻¹) in soil solution (1.5-m
907 depth) of the different land uses within the loam Acrisol soil in Jambi, Sumatra, Indonesia.
908 Correlations were carried out using monthly averages of four replicate plots per land use (*n* = 12
909 monthly measurements in 2013). Elements that had concentrations < 0.03 mg L⁻¹ (total Fe, total
910 Mn, and total P) and total Si (that did not show correlation with other elements) are not reported
911 below.

Element	NH ₄ ⁺ -N	NO ₃ ⁻ -N	DOC	Na ⁺	K ⁺	Ca ²⁺	Mg ²⁺	Total Al	Total S	Cl ⁻
Forest										
DON	0.79 ^c	-0.24	0.77 ^c	0.36	0.43	0.80 ^c	0.77 ^c	0.84 ^c	-0.17	0.86 ^c
NH ₄ ⁺ -N		0.22	0.48	0.23	0.64 ^b	0.67 ^b	0.65 ^b	0.58 ^b	0.30	0.58 ^b
NO ₃ ⁻ -N			-0.12	-0.09	0.35	-0.26	-0.25	-0.45	0.63 ^b	-0.47
DOC				0.36	0.45	0.72 ^c	0.71 ^c	0.73 ^c	-0.02	0.68 ^b
Na ⁺					0.58 ^b	0.53 ^a	0.46	0.34	0.23	0.45
K ⁺						0.51 ^a	0.45	0.29	0.71 ^c	0.33
Ca ²⁺							0.99 ^c	0.94 ^c	0.00	0.92 ^c
Mg ²⁺								0.95 ^c	-0.03	0.92 ^c
Total Al									-0.28	0.95 ^c
Total S										-0.23
Jungle rubber										
DON	0.80 ^c	0.28	0.77 ^c	0.72 ^c	0.85 ^c	0.72 ^c	0.79 ^c	0.30	0.60 ^b	0.68 ^b
NH ₄ ⁺ -N		0.32	0.73 ^c	0.35	0.77 ^c	0.53 ^a	0.67 ^b	0.55 ^b	0.17	0.79 ^c
NO ₃ ⁻ -N			0.35	0.17	0.20	0.65 ^b	0.62 ^b	0.61 ^b	-0.11	0.65 ^b
DOC				0.63 ^b	0.76 ^c	0.51 ^a	0.53 ^a	0.13	0.57 ^b	0.49 ^a

Na ⁺				0.80 ^c	0.58 ^b	0.55 ^b	-0.18	0.93 ^c	0.29
K ⁺					0.65 ^b	0.70 ^c	0.12	0.65 ^b	0.60 ^b
Ca ²⁺						0.97 ^c	0.56 ^b	0.32	0.84 ^c
Mg ²⁺							0.65 ^b	0.27	0.93 ^c
Total Al								-0.47	0.85 ^c
Total S									-0.02

Rubber

DON	-0.12	-0.32	0.53 ^a	0.04	0.65 ^b	0.37	0.65	0.67 ^b	-0.28	0.39
NH ₄ ⁺ -N		0.10	0.31	0.61 ^b	-0.05	0.17	-0.07	-0.41	0.65 ^b	-0.18
NO ₃ ⁻ -N			-0.25	0.25	-0.48	0.42	0.15	-0.09	0.26	0.31
DOC				0.50 ^a	0.46	0.51 ^a	0.50 ^a	0.29	0.30	0.34
Na ⁺					0.17	0.46	0.08	-0.34	0.85 ^c	0.00
K ⁺						0.24	0.55 ^b	0.54 ^a	-0.15	0.38
Ca ²⁺							0.81 ^c	0.40	0.27	0.72 ^c
Mg ²⁺								0.84 ^c	-0.26	0.92 ^c
Total Al									-0.70 ^c	0.83 ^c
Total S										-0.35

Oil palm fertilized areas

DON	-0.28	0.08	-0.18	-0.57 ^b	-0.12	0.16	0.31	0.50	-0.06	0.08
NH ₄ ⁺ -N		0.54 ^a	-0.12	0.00	0.50	0.15	0.37	0.46	0.22	0.46
NO ₃ ⁻ -N			-0.12	0.14	-0.02	-0.49	0.00	0.63 ^b	-0.38	0.10
DOC				-0.22	0.08	0.02	0.29	-0.17	0.40	-0.47
Na ⁺					-0.12	-0.45	-0.45	-0.37	-0.38	0.22

K ⁺						0.58 ^b	0.43	-0.17	0.58 ^b	0.27
Ca ²⁺							0.48	-0.19	0.79 ^c	0.45
Mg ²⁺								0.40	0.72 ^c	0.41
Total Al									-0.16	0.27
Total S										0.30

Oil palm frond-stacked areas

DON	-0.38	0.38	0.22	-0.38	0.24	-0.47	-0.16	0.47	-0.59 ^b	0.04
NH ₄ ⁺ -N		0.07	0.23	0.40	0.25	0.04	0.08	-0.17	0.42	0.06
NO ₃ ⁻ -N			0.61 ^b	0.12	0.56 ^b	-0.26	-0.21	0.11	0.20	0.02
DOC				-0.10	0.57 ^b	-0.38	-0.55 ^b	-0.28	0.22	-0.42
Na ⁺					0.09	0.23	0.22	-0.35	0.61 ^b	0.09
K ⁺						-0.27	-0.21	-0.07	0.29	-0.06
Ca ²⁺							0.83 ^c	0.30	-0.15	0.72 ^c
Mg ²⁺								0.63 ^b	-0.41	0.95 ^c
Total Al									-0.81 ^c	0.79 ^c
Total S										-0.48

912 ^a $P \leq 0.09$, ^b $P \leq 0.05$, ^c $P \leq 0.01$.

913 **Table A4.** Pearson correlations among element concentrations (mg L⁻¹) in soil solution (1.5-m
914 depth) of the different land uses withien the clay Acrisol soil in Jambi, Sumatra, Indonesia.
915 Correlations were carried out using monthly averages of four replicate plots per land use (*n* = 12
916 monthly measurements in 2013). Element that had concentrations < 0.03 mg L⁻¹ (total Fe, total Mn,
917 and total P) and total Si (that did not show correlation with other elements) are not reported below.

Element	NH ₄ ⁺ -N	NO ₃ ⁻ -N	DOC	Na ⁺	K ⁺	Ca ²⁺	Mg ²⁺	Total Al	Total S	Cl ⁻
Forest										
DON	0.10	-0.39	0.57 ^b	0.32	0.53 ^a	0.17	0.20	-0.28	0.25	-0.20
NH ₄ ⁺ -N		-0.48	0.81 ^c	0.63 ^b	0.23	0.51 ^a	0.28	-0.11	-0.27	0.09
NO ₃ ⁻ -N			-0.48	-0.24	-0.18	-0.05	-0.03	0.36	0.12	0.37
DOC				0.66 ^b	0.41	0.48	0.31	-0.25	-0.15	-0.06
Na ⁺					0.69 ^b	0.52 ^a	0.54 ^a	-0.22	-0.24	-0.10
K ⁺						0.74 ^c	0.88 ^c	0.22	-0.17	0.26
Ca ²⁺							0.93 ^c	0.54 ^a	-0.29	0.70 ^c
Mg ²⁺								0.52 ^a	-0.34	0.59 ^b
Total Al									-0.15	0.94 ^c
Total S										-0.10
Jungle rubber										
DON	0.23	0.55 ^b	0.58 ^b	0.19	0.69 ^c	0.50 ^a	0.63 ^b	0.70 ^c	-0.22	0.49 ^a
NH ₄ ⁺ -N		0.01	0.36	0.35	0.35	0.29	0.29	0.16	0.31	0.18
NO ₃ ⁻ -N			0.32	0.30	0.49 ^a	0.51 ^a	0.50 ^a	0.35	0.13	0.42
DOC				-0.24	0.11	-0.14	-0.05	0.29	0.06	-0.20
Na ⁺					0.68 ^c	0.84 ^c	0.73 ^c	0.01	0.52 ^a	0.66 ^b

K ⁺						0.87 ^c	0.93 ^c	0.63 ^b	0.09	0.84 ^c
Ca ²⁺							0.97 ^c	0.50 ^a	0.09	0.95 ^c
Mg ²⁺								0.66 ^b	-0.04	0.97 ^c
Total Al									-0.62 ^b	0.68 ^b
Total S										-0.18

Rubber

DON	-0.20	-0.18	0.21	-0.29	0.41	0.40	0.55 ^b	0.65 ^b	-0.57 ^b	0.48
NH ₄ ⁺ -N		0.22	0.81 ^c	0.85 ^c	0.47	0.19	0.10	-0.20	0.52 ^a	-0.06
NO ₃ ⁻ -N			-0.07	-0.16	-0.44	-0.68 ^b	-0.60 ^b	-0.38	0.05	-0.63 ^b
DOC				0.79 ^c	0.71 ^c	0.54 ^a	0.45	0.20	0.43	0.30
Na ⁺					0.61 ^b	0.38	0.21	-0.15	0.65 ^b	0.07
K ⁺						0.67 ^b	0.66 ^b	0.46	0.08	0.64 ^b
Ca ²⁺							0.93 ^c	0.73 ^c	-0.16	0.83 ^c
Mg ²⁺								0.88 ^c	-0.39	0.93 ^c
Total Al									-0.58 ^b	0.89 ^c
Total S										-0.40

Oil palm fertilized areas

DON	0.02	-0.09	0.49	0.70 ^b	0.69 ^b	0.67 ^b	0.42	0.45	0.54 ^a	0.63 ^b
NH ₄ ⁺ -N		0.08	0.15	0.39	0.37	0.16	0.06	0.06	0.46	-0.01
NO ₃ ⁻ -N			-0.18	0.03	0.46	0.51 ^a	-0.01	0.19	0.33	-0.49
DOC				0.52 ^a	0.66 ^b	0.56 ^a	0.50	0.56 ^a	0.25	0.70 ^b
Na ⁺					0.61 ^b	0.61 ^b	0.29	0.21	0.75 ^c	0.55 ^a
K ⁺						0.85 ^c	0.74 ^c	0.78 ^c	0.52 ^a	0.59 ^b


Ca ²⁺							0.81 ^c	0.74 ^c	0.69 ^b	0.64 ^b
Mg ²⁺								0.95 ^c	0.26	0.74 ^c
Total Al									0.15	0.75 ^c
Total S										0.26

Oil palm frond-stacked areas

DON	0.19	0.34	0.15	0.49 ^a	0.47	0.51 ^a	0.23	0.29	0.28	0.36
NH ₄ ⁺ -N		-0.07	0.27	0.21	0.38	0.11	0.06	0.07	0.13	0.09
NO ₃ ⁻ -N			-0.28	0.24	0.32	0.13	-0.13	0.09	0.56 ^b	-0.05
DOC				0.09	0.23	0.25	0.45	0.02	-0.46	0.19
Na ⁺					0.91 ^c	0.94 ^c	0.76 ^c	0.91 ^c	0.33	0.89 ^c
K ⁺						0.88 ^c	0.74 ^c	0.80 ^c	0.21	0.79 ^c
Ca ²⁺							0.90 ^c	0.91 ^c	0.10	0.95 ^c
Mg ²⁺								0.81 ^c	-0.28	0.93 ^c
Total Al									0.16	0.92 ^c
Total S										-0.06


918 ^a $P \leq 0.09$, ^b $P \leq 0.05$, ^c $P \leq 0.01$.

919 **Appendix B. Fine root biomass and soil water model validation**




920
 921 **Figure B1.** Fine root biomass (g m^{-2}) and distribution (%) down to a depth of 1 m in different
 922 land uses within ~~two landscapes (the~~ loam and clay Acrisol soils) in Jambi, Sumatra, Indonesia.
 923 The root measurement was conducted in each replicate plot by digging a pit (1 m x 1.5 m x 2-
 924 m depth) at about 2.5-m distance from an oil palm or a tree with a diameter at breast height of
 925 ≥ 10 cm. Root mass were sampled using a metal block (20 cm x 20 cm x 10 cm) at 10-cm depth
 926 interval from the top down to 1 m. Roots were carefully separated from the soil by washing
 927 over a 2-mm mesh screen and the fine roots were collected in a basin placed underneath the
 928 mesh screen. The roots were categorized into fine roots (≤ 2 mm diameter) and coarse roots (>2
 929 mm diameter), dried in an oven at $70\text{ }^{\circ}\text{C}$ for 5 days and weighed.

loam Acrisol soil



clay Acrisol soil



930

931 **Figure B2.** Validation between Expert N-modelled and field-measured matric potential at a

932 depth of 0.3 m in different land uses within ~~two landscapes (the~~ loam and clay Acrisol soils)

933 in Jambi, Sumatra, Indonesia.