

Biological weathering and its consequences at different spatial levels – from nanoscale to global scale

Roger D. Finlay¹, Shahid Mahmood¹, Nicholas Rosenstock², Emile B. Bolou-Bi³, Stephan J. Köhler⁴, Zaenab Fahad^{1,5}, Anna Rosling⁵, Håkan Wallander², Salim Belyazid⁶, Kevin Bishop⁴ and Bin Lian⁷

¹Uppsala BioCenter, Department of Forest Mycology and Plant Pathology, Swedish University of Agricultural Sciences, SE-750 07 Uppsala, Sweden

²Department of Biology, Lund University, Box 117, SE-221 00 Lund, Sweden

³Université Félix Houphouët-Boigny, UFR des Sciences de la Terre et des Ressources Minières, Département des Sciences du sol, BP 582 Abidjan 22, Côte D'Ivoire

⁴Soil-Water-Environment Center, Department of Aquatic Sciences and Assessment, Swedish University of Agricultural Sciences, SE-750 07 Uppsala, Sweden

⁵Department of Ecology and Genetics, EBC, Uppsala University SE-752 36 Uppsala, Sweden

⁶Department of Physical Geography, Stockholm University, SE-106 91 Stockholm, Sweden

⁷College of Marine Sciences and Engineering, Nanjing Normal University, Nanjing 210023, China

Correspondence to: Roger D. Finlay (Roger.Finlay@slu.se)

Abstract. Plant nutrients can be recycled through microbial decomposition of organic matter but replacement of base cations and phosphorus, lost through harvesting of biomass/biofuels or leaching, requires *de novo* supply of fresh nutrients released through weathering of soil parent material (minerals and rocks). Weathering involves physical and chemical processes that are modified by biological activity of plants, microorganisms and animals. This article reviews recent progress made in understanding biological processes contributing to weathering. A perspective of increasing spatial scale is adopted, examining the consequences of biological activity for weathering from nanoscale interactions, through *in vitro* and *in planta* microcosm and mesocosm studies, to field experiments and finally, ecosystem and global level effects. The topics discussed include: the physical alteration of minerals and mineral surfaces, the composition, amounts, chemical properties and effects of plant and microbial secretions, and the role of carbon flow (including stabilization/sequestration of C in organic and inorganic forms). Although the predominant focus is on the effects of fungi in forest ecosystems, the properties of biofilms, including bacterial interactions, are also discussed. The implications of these biological processes for modelling are discussed and we attempt to identify some key questions and knowledge gaps, as well as experimental approaches and areas of research in which future studies are likely to yield useful results. A particular focus of this article is to improve the representation of the ways in which biological processes complement physical and chemical processes that mobilize mineral elements, making them available for plant uptake. This is necessary to produce better estimates of weathering that are required for sustainable management of forests in a post fossil-fuel economy. While there are abundant examples of nm- and μ m-scale physical interactions between microorganisms and different minerals,

opinion appears to be divided with respect to the quantitative significance of these observations to overall weathering. Numerous *in vitro* experiments and microcosm studies involving plants and their associated microorganisms suggest that the allocation of plant-derived carbon, mineral dissolution and plant nutrient status are tightly coupled but there is still disagreement about the extent to which these processes contribute to field-scale observations. Apart from providing dynamically responsive pathways for the allocation of plant-derived carbon to power dissolution of minerals, mycorrhizal mycelia provide conduits for the long-distance transportation of weathering products back to plants that are also quantitatively significant sinks for released nutrients. These mycelial pathways bridge heterogeneous substrates, reducing the influence of local variation in C:N ratios. The production of polysaccharide matrices by biofilms of interacting bacteria and/or fungi at interfaces with mineral surfaces and roots, influences patterns of production of antibiotics and quorum sensing molecules, with concomitant effects on microbial community structure, and the qualitative and quantitative composition of mineral solubilizing compounds and weathering products. Patterns of carbon allocation and nutrient mobilization from both organic and inorganic substrates have been studied at larger spatial and temporal scales, including both ecosystem and global levels and there is a generally wider degree of acceptance of the ‘systemic’ effects of microorganisms on patterns of nutrient mobilization. Theories about the evolutionary development of weathering processes have been advanced but there is still a lack of information connecting processes at different spatial scales. Detailed studies of the liquid chemistry of local weathering sites at the μm -scale, together with up-scaling to soil-scale dissolution rates, are advocated, as well as new approaches involving stable isotopes.

1 Introduction

Modelling of base cation supply using the PROFILE/FORSAFE modelling platform (Kronnäs et al., 2019) suggests that planned intensification of Swedish forestry, involving increased harvesting of organic residues for biofuel, will not be sustainable in a long-term perspective without compensatory measures such as wood ash recycling (Akselsson et al., 2007; Klaminder et al., 2011; Futter et al., 2012; Moldan et al., 2017). The base cations and phosphorus that are essential for forest growth can be re-cycled from organic residues through microbial decomposition but if they are lost through removal of organic material the only way they can be replaced is by weathering of rocks and minerals, or deposition from the atmosphere. There is a need to improve the available estimates of weathering and to improve our knowledge of the ways in which biological processes may complement physical and chemical processes that mobilize mineral elements, making them available for plant uptake.

The role of fungi in biological weathering in boreal forest soils was reviewed by Hoffland et al. in 2004 and by Finlay et al. in 2009. More recent reviews of the more specific roles of mycorrhizal symbiosis in mineral weathering and nutrient mining from soil parent material (Smits and Wallander, 2017), pedogenesis (Leake and Read, 2017) and immobilization of carbon in mycorrhizal mycelial biomass and secretions (Finlay and Clemmensen, 2017) have

also been published. Twelve testable hypotheses on the geobiology of weathering were outlined by Brantley et al. (2011). These authors concede that some of the outlined hypotheses have been implicit in scientific research conducted since the late 1800's but argue that there are now new analytical, modelling and field opportunities to test these hypotheses. The aim of the present article is to review recent advances in the understanding of biological weathering, particularly with respect to nutrient and carbon cycling within boreal forests, including findings made within the interdisciplinary project *Quantifying Weathering Rates for Sustainable Forestry* (QWARTS, 2012-2016). One major motivation for this study was the concern that the modelling tools used to determine the long-term supply of weathering products for sustainable forest growth may have been missing biological processes that allow a forest ecosystem to alter the rate of weathering in response to the biological demand for these weathering products (Klaminder et al., 2011).

Biological weathering involves the weakening and disintegration of rocks and dissolution of minerals, caused by the activity of plants, animals and microorganisms. Biological weathering takes place in conjunction with physical and chemical processes but there is still disagreement about the quantitative contribution of biogenic weathering to overall weathering (see Leake and Read, 2017; Smits and Wallander, 2017). The first of Brantley et al.'s (2011) 12 hypotheses is that "*Solar-to-chemical conversion of energy by plants regulates flows of carbon, water, and nutrients through plant-microbe soil networks, thereby controlling the location and extent of biological weathering*". The supply and transport of photosynthetically derived carbon through roots and mycorrhizal hyphae to organic and inorganic substrates is a fundamental biogeochemical process (Jones et al., 2009), influencing both decomposition and mineral weathering, and these two processes influence each other. This flow of carbon and the 15 role of plant-microbe-soil interactions in the rhizosphere have been reviewed in an evolutionary perspective (Lambers et al., 2009) and with respect to their potential applications in sustainable agriculture, nature conservation, the development of bio-energy crops and the mitigation of climate change (Philippot et al., 2013). Since there is disagreement about whether biological processes demonstrated at small spatial scales contribute 20 significantly to field scale processes, but a greater degree of consensus about the importance of systemic effects of biological weathering at larger spatial and temporal scales, we have adopted a spatial perspective. We start by 25 reviewing processes occurring at the nm- and μm -scale before discussing *in vitro* microcosm experiments, mesocosm studies with plants, field experiments and finally studies of effects at the ecosystem and global scale. Biological weathering is also discussed within an evolutionary perspective and some recent experiments using 30 stable isotopes are presented. Each section is followed by a short summary in which we attempt to list the main conclusions and some of the remaining questions and knowledge gaps. Finally, different modelling approaches are discussed in relation to how we can incorporate the biological features discussed earlier and improve the reliability of models.

2 Microscale/nanoscale observations of physical alteration of minerals

The idea that microorganisms may alter rocks and minerals is not new and biogenic etching of microfractures in borosilicate glass and crystalline silicates (olivine) by microfungi (*Penicillium notatum* and *Aspergillus amstelodami*), presumed to be producing both organic acids and siderophores, was demonstrated by Callot et al. in

5 1987. Early studies by Paris et al. (1995, 1996) demonstrated *in vitro* weathering of phlogopite involving displacement of non-exchangeable interlayer K⁺ and alteration of the crystal lattice structure, as well as stimulated accumulation of oxalate under simultaneous K⁺ and Mg²⁺ deficiency. The widespread occurrence of tubular pores, 3-10 µm in diameter, has been demonstrated in weatherable minerals in podzol surface soils and shallow granitic rock under European coniferous forests (van Breemen et al., 2000; Jongmans et al., 1997; Landeweert et al., 2001).

10 Some of these pores were found to be occupied by fungal hyphae and the authors speculated that they could be formed by the weathering action of hyphae (possibly in association with bacteria) releasing organic acids and siderophores. The aetiology of pore formation has been questioned however, with some authors claiming that (all) the observed pores are of abiotic origin (Sverdrup, 2009). Studies of feldspar tunnelling along chronosequences created by post-glacial rebound (Hoffland et al., 2002) revealed that the tunnels were more frequent in the uppermost

15 2 cm of the E horizon, that the frequency of tunnelling increased with soil age, and that there was a lag period of up to 2000 years when tunnels were absent or rare, postulated by the authors to coincide with the time taken for the disappearance of the more easily weatherable K and Ca containing biotite and hornblende. Parallel studies along productivity gradients (Hoffland et al., 2003) have also revealed a significant positive correlation between the density of ectomycorrhizal root tips and the density of tunnels in the E horizon. However similar tunnels in feldspars

20 across a sand dune chronosequence at Lake Michigan have been estimated to contribute less than 0.5% of total mineral weathering (Smits et al., 2005) suggesting either that fungal weathering is negligible, or that *tunnel formation reflects only a small proportion of the total weathering effect of the fungi*. The total mineral surface area available for mineral weathering in most mineral soils is clearly much larger than the internal surface area of the observed tunnels and small tunnel-like features were observed in mineral surfaces by Smits et al. (2005). Different

25 biomechanical mechanisms used by fungi to penetrate rock have received increasing attention. Ultramicroscopic and spectroscopic observations of fungus-biotite interfaces during weathering of biotite flakes have revealed biomechanical forcing, and altered interlayer spacing associated with depletion of K by an ectomycorrhizal fungus (*Paxillus involutus*) (Bonneville et al., 2009). It appears that physical distortion of the lattice structure takes place before chemical alteration through dissolution and oxidation. Fungal hyphae colonizing fractures and voids in

30 minerals can exert substantial mechanical force and have been demonstrated to build up turgor pressure in excess of 8 MPa that is sufficient to penetrate Mylar and Kevlar and widen existing cracks in rocks (Howard et al., 1991). Recent studies of biotite colonization by *P. involutus* (Bonneville et al., 2016) have revealed extensive oxidation of

Fe(II) up to 2 μm in depth and the increase in Fe(III) implies a volumetric change that is sufficient to strain the crystal lattice and induce the formation of microcracks, which are abundant below the hypha-biotite interface.

The observations of Jongmans et al. (1997) stimulated interest in biogenic weathering and led to a large number of subsequent studies. The endolithic biosignatures of rock-inhabiting microorganisms can be distinguished from 5 purely abiotic microtunnels (McLoughlin et al., 2010). Biological tubular microcavities can be distinguished by their shapes, distribution, and the absence of intersections which excludes an origin by chemical dissolution of pre-existing heterogeneities such as, radiation damage trails, gas-escape structures, or fluid inclusion trails. Atomic force microscopy (AFM) and scanning transmission electron microscopy-energy dispersive X-ray spectroscopy (STEM-EDX) have been used to demonstrate nanoscale alteration of surface topography and attachment and deposition of 10 organic biolayers by fungal hyphae (Bonneville et al., 2011; McMaster, 2012; Gazzè et al., 2013, 2014; Saccone et al., 2012). More recent studies of lizardite dissolution by fungal cells, using confocal laser scanning microscopy (CLSM) (Li et al., 2016), suggest that biomechanical forces of hyphal growth are indispensable for fungal weathering and strong enough to breach the mineral lattice. The data from these studies suggest that biomechanical 15 forcing takes place with μm -scale acidification mediated by surface-bound hyphae and subsequent removal of chemical elements due to fungal action. However, so far, the quantitative significance of these effects to total weathering rates is still unclear. Comparative studies of forests with either ectomycorrhizal or arbuscular 20 mycorrhizal host tree species (Koele et al., 2014) have revealed the presence of tunnel like structures in minerals in both types of forest, suggesting that mineral weathering can be caused by acidification of the rhizosphere by both types of mycorrhizal fungus and/or saprotrophic fungi. Investigations of silicate mineral surfaces, buried in proximity to roots of trees that would normally host arbuscular mycorrhizal fungi (AMF) and were growing in an arboretum (Quirk et al., 2012, 2014), suggest that AMF may also form weathering trenches, although the associated fungi were not identified in these particular studies. Nanoscale channels in chlorite flakes colonized by ectomycorrhizal fungi have also been demonstrated (Gazzè et al., 2012) using AFM, and suggested as evidence that fungal activity, fuelled by plant photosynthate, can enhance mineral dissolution.

25

Summary:

Many new studies, published during the past ten years, using AFM, CLSM, energy dispersive X-ray spectroscopy and vertical scanning interferometry, have revealed the structural alteration of mineral substrates by fungi. The 30 endolithic signatures of rock-inhabiting microorganisms can now be distinguished from structures of abiotic origin but the proportional contribution of tunnels and voids with respect to total biological weathering is probably low since their volume and internal surface area is small in comparison to the total mineral surface area exposed to microbial contact. The capacity of different vegetation systems, hosting different types of mycorrhizal symbionts, to cause structural alteration of different minerals should be investigated in further studies, combined with DNA-

based methods to identify the fungi (and bacteria) involved *in-situ*. The influence of environmental factors such as atmospheric CO₂ concentration, nitrogen deposition and mineral composition should be investigated.

3 Biofilms and small-scale microbial interactions with consequences at higher spatial scales

Most microorganisms do not live as pure cultures of dispersed single cells in soil solution. Instead they aggregate 5 at interfaces – on surfaces of roots, organic matter, rocks and minerals, forming biofilms or microbial mats (Flemming and Wingender, 2010; Flemming et al., 2016). Biofilms consist of a hydrated matrix of extracellular polymeric substances (EPS), mostly produced by the organisms they contain. This matrix can account for 90% of the dry mass of the biofilm and provides a structural scaffold responsible for adhesion to surfaces and cohesion of the biofilm, enabling interactions that are entirely different from those of planktonic bacteria. The EPS matrix 10 isolates microorganisms from the bulk soil solution, maintaining them in close proximity to each other and to substrate surfaces, concentrating weathering agents and allowing cell to cell communication and quorum sensing by containing and concentrating signal molecules. This permits the formation of synergistic microbial consortia, production, accumulation, retention and stabilization of extracellular enzymes through binding interactions with polysaccharides, sorption of organic compounds and inorganic ions, as well as permitting redox activity in the matrix 15 (Liu and Lian, 2019), and facilitating horizontal gene transfer (Savage et al., 2013; Borgeaud et al., 2015). The retention of water maintains a hydrated microenvironment, protecting against desiccation, and proteins and polysaccharides can provide a protective barrier against specific and non-specific host defences during infection, antimicrobial agents and some grazing protozoa (Fig. 1a) (Flemming and Wingender, 2010).

Biofilms and microbial mats have been studied from different perspectives that are relevant to interactions 20 between microorganisms and minerals in a biogeochemical context. Subaerial biofilms occur within solid mineral surfaces exposed to the atmosphere and are dominated by fungi, algae, cyanobacteria and heterotrophic bacteria (Gorbushina, 2007). These communities are known to penetrate the mineral substrates and induce chemical and physical changes contributing to weathering. Effects of biofilms containing the phototrophic cyanobacterium *Nostoc punctiforme* and the rock-inhabiting ascomycete *Knufia petricola* have been quantified using inductively coupled 25 plasma optical emission spectrometry/mass spectrometry as well as scanning electron microscopy/transmission electron microscopy-energy dispersive X-ray spectrometry (Seiffert et al., 2014), demonstrating clear effects of the biofilms on mineral dissolution and leaching. Mats of hypogeous ectomycorrhizal fungi have been studied by Griffiths et al. (1994) who found that colonization by *Gautieria monticola* notably increased the amount of oxalic acid in soil. Calcium oxalate (CaOx) can accumulate in forest soils and deposition of Ca from the weathering of 30 apatite as CaOx crystals on the hyphal surfaces of *Rhizopogon* sp. growing from *Pinus muricata* seedlings has been shown in microcosm studies (Wallander et al., 2002). More CaOx is formed under higher P levels (Tuason et al., 2009). Bulk soil solution concentrations of organic acids are considered to be too low to have a large effect on

mineral dissolution, and modelling (Smits, 2009) suggests that local concentrations of weathering agents such as oxalate will not have a major effect on feldspar weathering unless the weathering agents remain within a few microns of the mineral surface. However, several authors (Balogh-Brunstad et al., 2008; Finlay et al., 2009) have suggested that higher concentrations of organic acids may accumulate within EPS matrices that are in close proximity to 5 mineral surfaces, so that mineral dissolution is influenced, and have called for more experiments to confirm this possible effect. More recent studies by Gazzè et al. (2013) using atomic force microscopy have demonstrated the presence of EPS halos (Fig. 1b) surrounding *Paxillus involutus* hyphae colonizing phyllosilicate surfaces. In addition to increasing the surface area for hyphal interaction with mineral surfaces these hydrated EPS layers presumably 10 enhance mineral weathering by promoting accumulation of weathering agents such as organic acids and acidic polysaccharides, but further detailed studies of the local concentrations of these molecules are still necessary.

Fungi and bacteria live together in a wide range of environments (Deveau et al., 2018) and the exudation of carbon compounds from roots and fungal hyphae into biofilms undoubtedly influences bacterial growth and activity (Guennoc et al., 2018). Priming of bacterial activity may occur through supply of exudates from vital hyphae (Toljander et al., 2007) but may also include recycling of C from damaged or senescent hyphae. Carbon supply from 15 arbuscular mycorrhizal hyphae can provide energy for associated bacteria to solubilize phosphate (Zhang et al., 2014, 2016). Different ectomycorrhizal fungi colonizing lateral roots of tree seedlings have been shown to influence the community structure of associated bacteria (Marupakula et al., 2016, 2017) and differences in the richness and composition of bacterial communities have been demonstrated between the hyphosphere of ectomycorrhizal fungi and that of saprotrophic fungi (Liu et al., 2018). Although the role of bacteria in mineral weathering has been less 20 widely studied than that of fungi in recent years, progress has been made in understanding the identity and mechanisms of bacteria involved in weathering of minerals in acidic forest soils. Bacteria in the genera *Burkholderia* and *Collimonas* appear to have significant mineral weathering ability (Uroz et al., 2011) and incubation of different minerals in forest soils appears to result in selection of different bacterial communities, that are distinct from those of the bulk soil (Uroz et al., 2012), confirming the concept of mineralogical control of fungal and bacterial 25 community structure (Gleeson et al., 2005; Hutchens, 2010). Uroz et al. (2015) contrasted the rhizosphere with the “mineralosphere” in which bacteria are selected, not by organic nutrients originating from roots, but by the physiochemical properties of different minerals. Microorganisms can also drive weathering of bedrock in subglacial environments and the ubiquitous nature of pyrite in many common bedrock types and high SO_4^{2-} concentrations in most glacial meltwaters has been interpreted to suggest (Mitchell et al. 2013) that pyrite may be a dominant 30 lithogenic control on subglacial microbial communities and that mineral-based energy may therefore serve a fundamental role in sustaining these microbial populations over glacial-interglacial time scales. Studies by Montross et al. (2013) demonstrated an up to eight-fold increase in dissolved cations in biotic systems containing glacial sediments and meltwater compared with abiotic systems, suggesting that microbial processes can maintain terrestrial chemical weathering rates in cooling climates during glacial advance. Recent experiments attempting to investigate

in-situ mineral dissolution rates and structure/diversity of bacterial communities colonizing silicate minerals (Wild et al., 2018, 2019) have revealed development of mineral-specific bacterial communities and large discrepancies between predicted and measured dissolution rates, which were attributed to “heterogeneity of fluid circulation and local variation of reaction conditions”.

5

Summary:

Consequences of the ecophysiological heterogeneity and spatial organization of plant-microbe-soil interactions in natural environments need to be incorporated into new models and experimental systems. The effects of biofilms at microbial-mineral interfaces include EPS haloes that increase the surface area of contact, increased concentrations 10 of weathering agents through protection by antibiotic compounds secreted into the EPS matrix, rapid removal of feedback-inhibiting weathering products by mycorrhizal hyphae attached to plants that act as strong sinks for mobilised products, and changed patterns of microbial activity due to the facilitation of quorum sensing and other types of signalling. Retention of water within the biofilm matrix may allow weathering to be maintained at higher 15 rates than would otherwise be possible during periods of soil drying. The extremely fine spatial scale of biofilms necessitates further development of sampling at a μm -scale to capture the steep chemical gradients and micro-scale variation in chemical and biological diversity and composition. These measurements are essential in order to gain an accurate picture of the chemical and biological conditions existing at weathering interfaces.

4 Microbial and plant secretions – evidence from microcosms and mesocosms

20 Plants play a fundamental role in soil formation since root activity and decomposing plant material enhance weathering rates by producing acidifying substances (H^+ , organic acids), and ligands that complex with metals in the minerals. In addition, uptake of ions released from weathering reduces the likelihood of saturating conditions that retard weathering rates. Many of these effects are mediated by mycorrhizal fungi and in temperate and boreal forests the vast majority of fine tree roots are colonized by symbiotic ectomycorrhizal fungi.

25 In ancient, highly weathered soils, P is the primary nutrient limiting plant growth, whereas N is the main growth-limiting nutrient in young soils. Plant nutrient acquisition in nutrient-impoverished soils often involves specialized root structures such as cluster roots or symbiotic structures such as mycorrhizas or root nodules (Lambers et al., 2008). In ancient soils with very low P availability ‘dauciform’ (carrot-shaped) roots are produced by monocots in the Cyperaceae and ‘proteoid’ roots are produced by numerous dicot families, including the Proteaceae. Both types 30 of roots are hairy and produce large amounts of carboxylates that desorb P from mineral surfaces. Phosphatases are also produced to release P from organic sources. Protons are quantitatively important weathering agents and many biotic processes, including uptake of positively charged nutrients such as NH_4^+ and K^+ , result in exudation of protons.

Organic acids such as oxalic acid and citric acid are produced by plant roots as well as fungi and bacteria and contribute to proton-driven weathering, but their deprotonated forms also act as strong weathering agents complexing with metals, including Fe^{3+} and Al^{3+} (Ma et al., 2001). Soil P and N change as a function of soil age and in younger- and intermediate-aged soils with adequate amounts of nutrients, mycorrhizal mycelia provide an effective strategy for nutrient acquisition (Lambers et al., 2008). Experiments using dual isotopic tracers of (^{14}C and ^{33}P) suggest that evolution of land plants from rootless gametophytes to rooted sporophytes with larger arbuscular mycorrhizal hyphal networks enabled enhanced efficiency of P capture as atmospheric CO_2 concentrations fell during the mid-Palaeozoic (480-360 Ma ago), (Field et al., 2012).

Strategies of mycorrhizal symbiosis differ depending upon the plant host. The majority of plant species form arbuscular mycorrhizas with Glomeromycotan fungi that are efficient at scavenging nutrients such as P, and transporting it to their plant hosts across the depletion zones around roots formed by the slow diffusion of P through soil. However, these fungi are less efficient than proteoid roots at ‘mining’ P and releasing it from sorbed forms. Ericoid mycorrhizas are formed by plants in the Ericaceae, Empetraceae and Epacridaceae, and ectomycorrhizas are formed by many woody plants and trees (Smith and Read, 2008). The fungi forming these two types of symbiosis vary in their enzymatic competence but in general they have a more highly developed capacity to both scavenge and ‘mine’ N and P than arbuscular mycorrhiza, releasing N and P from organic forms (in the case of ectomycorrhizal fungi) by different combinations of hydrolytic and oxidative enzymes and non-enzymatic Fenton chemistry (Lindahl and Tunlid, 2015; Nicolás et al., 2019), and P and other mineral elements from inorganic forms via proton, organic acid, and siderophore exudation. In boreal forests with stratified podzol soils, many ectomycorrhizal fungal species produce extensive fungal mycelia that colonize both organic soil horizons and mineral horizons to an equal extent on a land area basis (Söderström, 1979), although data expressed on a soil dry weight basis often suggest that colonization of the mineral soil is lower since the mineral soil has a dry weight approximately 10 times higher than the organic soil. Studies of vertical distribution of different functional guilds of fungi (Lindahl et al., 2007; Sterkenburg et al., 2018) suggest that ectomycorrhizal fungi are more abundant than saprotrophs in deeper organic and mineral horizons, presumably because they receive supplies of carbon from their plant hosts and are less reliant on local sources of carbon that are less abundant in the deeper horizons.

Mycorrhizal fungal mycelia secrete a wide range of molecules and the secretome has been shown to include low molecular weight (LMW) organic acids, amino acids, polyols, peptides, siderophores, glycoproteins and a diverse range of enzymes such as proteases, phosphatases, lignin peroxidases and laccases. The production of these substances is highly variable both within and between different types of mycorrhizal fungi and influenced by different environmental conditions. **Figure 2** illustrates the flow of plant-derived carbon compounds through the fungal mycelium, the secretion of compounds into extracellular polysaccharide matrices and the soil solution and the longer-term immobilization processes that result in storage of stable C in organic and mineral pools. Although many of the molecules produced by the mycelium and its associated bacteria are labile and subject to rapid turnover,

they play a collective role in mobilization of nutrients that can lead to a longer-term sequestration of C in recalcitrant substrates that are both organic (Clemmensen et al., 2013) and inorganic (Sun et al., 2019a).

LMW organic acids are frequently identified as important components of the exudates produced by ectomycorrhizal fungi. Simple carboxylic acids are often present in soil solution and implicated in pedogenic processes. Their sorption characteristics were studied by van Hees et al. (2003) who found adsorbed to solution ratios as high as 3100. Organic acids are readily adsorbed to the solid phase and sorption provides an important buffering role in maintaining soil solution concentrations at low organic acid concentrations, inhibiting microbial degradation. Concentrations of LMW organic compounds in soil solution are typically low (<50 μ M) but the flux through this pool is extremely rapid and microbial mineralization to CO₂ results in mean residence times of 1-10 hours (van Hees et al., 2005). These labile compounds may thus make a substantial contribution to the total efflux of CO₂ from soil. Direct measurements of oxalate exudation from hyphal tips of the ectomycorrhizal fungus *Hebeloma crustuliniforme* (van Hees et al., 2006) have led to calculated exudation rates of 19±3 fmol oxalate per hyphal tip per hour, suggesting that concentrations of 30 mM oxalate could occur within one hour inside feldspar tunnels occupied by fungal hyphae. This would represent a concentration 10 000 times higher than in the surrounding soil solution. Production of the hydroxamate siderophore ferricrocin was also detected and calculated to be able to reach a concentration of 1.5 μ M, around 1000 times higher than in the surrounding soil solution. Interestingly, the steady-state dissolution of goethite by 2'-deoxymugineic acid (DMA) phytosiderophores has been demonstrated to be synergistically enhanced by oxalate (Reichard et al., 2005), and it is possible that synergistic interactions between other combinations of organic acids and siderophores may exist. Organic acid production by intact ectomycorrhizal fungal mycelia colonizing *Pinus sylvestris* seedlings was studied by Ahonen-Jonnarth et al. (2000), using axenic, *in vitro* systems. In this study, production of oxalic acid by seedlings exposed to elevated (0.7 mM) Al and colonized by *Suillus variegatus* or *Rhizopogon roseolus* was up to 39.5 and 26 times, respectively, higher than in non-mycorrhizal control plants. The same type of lab system was used by Johansson et al. (2009) to investigate the effect of different mycorrhizal fungi on production of LMW organic acids, amino acids and DOC. However, in these experiments the identifiable LMW organic acids constituted only a small proportion (3-5%) of the total DOC fraction but DOC production was increased in mycorrhizal treatments relative to the non-mycorrhizal controls.

Studies of mycorrhizal hyphal exudates using NMR spectroscopy (Sun et al., 1999) have revealed exudation of fluid droplets at the hyphal tips of the ectomycorrhizal fungus *Suillus bovinus* and found that sugars and polyols comprised 32%, and peptides 14% of the exudate mass. Oxalic acids and acetic acid were also found, and polyols such as mannitol and arabinol are thought to be important for retaining turgor in fungal hyphae during C translocation along hydrostatic pressure gradients. High internal pressures in hyphae are thought to be an evolutionary adaptation to facilitate penetration of both plant tissues as well as rock surfaces (Jongmans et al., 1997). This exudation of droplets may play an important role in conditioning the immediate environment of hyphal tips, facilitating interactions with substrates and associated microorganisms, even in drier soils. Similar observations have been made

by Querejeta et al. (2003) who demonstrated that water obtained by *Quercus agrifolia* plants, using hydraulic lift, can be transferred to associated arbuscular mycorrhizal and ectomycorrhizal fungi to maintain their integrity and activity during drought, even when the fertile upper soil is dry. Carbon allocation in the form of sugars and polyols (Sun et al., 1999) may be important in generating turgor pressure in hyphae and has consequences for weathering of 5 minerals with lattice structure.

While biologically derived molecules such as organic acids and siderophores are strongly implicated in promoting mineral weathering, it is important to note that biologically derived ligands may also inhibit mineral weathering. Among LMW organic acids, only citric and oxalic acids are commonly observed to stimulate mineral weathering (Neaman et al., 2006; Drever and Stillings, 1997), and humic and fulvic acids, which may dominate 10 dissolved organic matter in soil solutions, have been observed to exert an inhibitory effect on mineral dissolution (Ochs, 1996; Drever and Stillings, 1997).

Different microcosm systems have been used to study interactions between minerals and mycorrhizal fungal mycelia colonizing plant seedlings. Differential allocation of plant-derived C to patches of primary minerals such as 15 quartz and potassium feldspar (Rosling et al., 2004) and to apatite and quartz (Smits et al., 2012) suggest tightly coupled plant-fungal interactions underlying weathering. In the experiment by Smits et al. (2012), when P was limiting, 17 times more ^{14}C was allocated to wells containing apatite than to those containing only quartz, and fungal 20 colonization of the substrate increased the release of P by a factor of almost three. Experiments by van Schöll et al. (2006a) demonstrated that limitation of nutrients (P, Mg, K) affected the composition of organic acids exuded by ectomycorrhizal fungi (more oxalate) but not the total amounts. Other experiments by van Schöll et al. (2006b) have demonstrated significant weathering of muscovite by the ectomycorrhizal fungus *Paxillus involutus* when K was in 25 low supply whereas no effect on hornblende was found under Mg deficiency. Selective allocation of biomass to grains of different minerals by *P. involutus* has also been demonstrated (Leake et al., 2008; Smits et al., 2008) suggesting grain scale “biosensing”, however it is also possible that fungal growth may be influenced by topographic structure (Smits and Wallander, 2017). Schmalenberger et al. (2015) demonstrated mineral-specific exudation of 30 oxalate by *P. involutus* using labelled $^{14}\text{CO}_2$ given to the host plant. Oxalate was exuded in response to minerals in the following sequence: Gabbro > limestone, olivine and basalt > granite and quartz. Experiments using flow-through systems (Calvaruso et al., 2013) have also estimated weathering rates of apatite to be 10 times higher when pine seedlings were present, compared with unplanted systems and attributed this to exudation of organic acids by the roots. The plants had been checked for the absence of fungal ‘contaminants’ but inoculation with the mineral weathering bacterial strain *Burkholderia glathei* PML1(12)Rp appeared to have no significant effect on weathering.

Fungi, bacteria and plants all produce siderophores, low-molecular-mass, metal-complexing compounds. These bind strongly to Fe^{3+} influencing its release and uptake (Kraemer et al., 2014; Ahmed and Holmström, 2014). The hydroxamate siderophores ferrichrome and ferricrocin have been found in soil solution of mor layer podzolic soil overlying granitic rock and intensively colonized by ectomycorrhizal hyphae (Holmström et al., 2004) and should

be kinetically and thermodynamically, even more efficient complexing agents for trivalent cations than oxalic and citric acid. Primary minerals containing substantial amounts of Fe, such as hornblende and biotite, show enhanced dissolution rates in the presence of bacterial or fungal siderophores (Kalinowski et al., 2000; Sokolova et al., 2010) and attachment of microorganisms to the mineral surfaces appears to lead to greater dissolution of elements from 5 biotite (Bonneville et al., 2009; Ahmed and Holmström, 2015)

Release of potassium from K-feldspar and illite in microcosms by the fungus *Aspergillus fumigatus* was demonstrated by Lian et al. (2008) who showed that release of K was enhanced by a factor of 3-4 by physical contact between the fungus and the mineral surface. Simple types of microcosm are usually used for gene expression studies in order to facilitate extraction of RNA from target organisms. Xiao et al. (2012) used differential expression cDNA 10 libraries of *A. fumigatus* using suppression subtractive hybridization technology to investigate the mechanisms by which the fungus weathered K-bearing minerals. K-bearing minerals were found to upregulate the expression of carbonic anhydrase (CA), implying that *A. fumigatus* was capable of converting CO₂ into carbonate to accelerate the weathering of potassium-bearing minerals, which fixed CO₂. During mineral weathering, the fungus changed its metabolism, produced more metal-binding proteins, and reduced membrane metal transporter expression, which can 15 modulate ion absorption and disposal and promote acid production. Wang et al. (2015) used high-throughput RNA-sequencing (RNA-seq) to study the molecular mechanisms of *Aspergillus niger* involved in weathering of potassium feldspar. The fungus was cultured with soluble K⁺ or K-feldspar demonstrating differential expression of genes related to synthesis and transportation of organic acids, polysaccharides and proteins which was closely related to 20 release of K⁺ from the minerals. Regulation of carbonic anhydrase (CA) gene expression in *Bacillus mucilaginosus* and the effects of its expression product in *Escherichia coli* have been examined by Xiao et al. (2014) who found that expression of CA genes was upregulated by the addition of calcite to a Ca²⁺-deficient medium, and that a crude 25 enzyme extract of the expression product in *E. coli* promoted calcite dissolution. Real-time fluorescent, quantitative PCR has been used to explore the correlation between CA gene expression in *B. mucilaginosus* and deficiency/sufficiency of Ca and CO₂ concentration and the results suggest that CA gene expression is negatively correlated with both CO₂ concentration and the ease of obtaining soluble calcium (Xiao et al., 2015). The roles of 30 different CA genes have also been studied in *Aspergillus nidulans* using gene deletion, overexpression and bioinformatics (Sun and Lian, 2019) and the results of this study suggest that the CA gene *canA* is involved in weathering of silicate minerals and carbonate formation, catalysing CO₂ hydration and that *canB* is essential for cellular respiration and biosynthesis in low CO₂ environments. Recent microcosm studies have also used transcriptome analysis to investigate weathering of K-containing feldspar and apatite and demonstrated upregulation of high-affinity ion transporter systems in the ectomycorrhizal fungus *Amanita pantherina* (Sun et al., 2019b).

Summary:

Earlier microcosm demonstrations of selective allocation of carbon to different minerals by ectomycorrhizal mycelium have now been complemented by newer studies demonstrating that selective C allocation to nutrient containing minerals through intact ectomycorrhizal mycelium results in significant increases in nutrient uptake by the host plants (Smits et al. 2012). There is still disagreement about the relative importance of different molecules as weathering agents and better information is required about their chemical identity, concentration and rates of turnover at weathering interfaces. Advances in DNA based techniques have enabled a range of microcosm experiments in which the regulation of weathering interactions between fungi and minerals has been examined in microcosms and further studies based on transcriptomics will provide a more detailed understanding of how weathering of different minerals is regulated in individual species. However, DNA-based community profiling methods should also be used to improve understanding of more complex weathering consortia involving both bacteria and fungi.

5 Systemic consequences of microorganism-mineral interactions in an ecological and evolutionary context

There is strong support for the idea that microorganism-mineral interactions have important consequences at global spatial scales and evolutionary time scales and some of these are illustrated in Fig. 3. Indeed, the concept of “mineral evolution” (Hazen et al., 2008) suggests that *over two thirds of the number of minerals that exist today (>5300) are the result of chemical changes mediated by living organisms* (Fig 3. a). The best known of these is the Great Oxidation Event about 2.3 billion years ago (2.3 Ga) (Kump, 2008; Luo et al., 2016) during which the Earth’s atmosphere changed from one that was almost devoid of oxygen to one that is one-fifth oxygen. Inclusions of potentially biogenic carbon within Hadean zircons as old as 4.1 Ga (Bell et al., 2015) suggest that biological processes could have been operating during the Hadean Eon. Early microbial communities would have developed within sub-surface mineral environments to avoid high levels of ionizing radiation at the interface between the atmosphere and lithosphere. The sub-aerial biofilms at this interface today remain stressful environments (Gorbushina, 2007) but ionizing radiation levels are now much lower due to thickening of the Earth’s atmosphere. Biomarker evidence (Brocks et al., 1999) in rocks formed 200 million years (Ma), before the increase in atmospheric oxygen, suggests that oxygen was already being produced before 2.5 Ga. Oxygenic photosynthesis by cyanobacteria is a likely source of this oxygen but there is evidence that stromatolites were abundant between 3.4 and 2.4 Ga, prior to the advent of cyanobacteria and oxygenic photosynthesis (Allen, 2016) and that Archaean microbial mats of protocyanobacteria switched between photolithoautotrophic and photoorganoheterotrophic metabolism prior to the evolution of cyanobacteria with simultaneous, constitutive expression of genes allowing both types of metabolism. It is also likely that phototrophy based on purple retinal pigments similar to the chromoprotein bacteriorhodopsin, discovered in halophilic Archaea, may have dominated prior to the development of photosynthesis (DasSarma and

Schweiterman, 2018). The activity of these early microorganisms and subsequent accumulation of oxygen in the atmosphere paved the way for the evolution of plants and there is a large and diverse body of evidence that the plastids of algae and higher plants evolved from free-living bacteria by endosymbiosis involving endosymbiotic gene transfer (Zimorski et al., 2014) as well as horizontal gene transfer (Archibald, 2015) (Fig 3 b).

5

Evolution of higher plants and development of vegetation has had a substantial effect on mineral weathering. The first well differentiated forests appeared in the Devonian, and increases in the volume of roots from the Silurian to the Devonian are associated with increases in clay enrichment and chemical weathering in subsurface horizons and drawdown of atmospheric CO₂ (Retallack, 1997). Dissolution of bedrock, accelerated by growth of plants and 10 enhanced weathering of silicates, resulting in HCO₃⁻ carried to the sea and precipitated as carbonates, would have led to removal of CO₂ from the atmosphere and the large drop in CO₂ during the Devonian 400-360 Ma ago is thought to be associated with the rise of land plants and spread and development of forests (Berner, 1997).

The ubiquitous distribution of microorganisms today suggests that plants are not standalone entities, but should be considered from a holistic perspective, as **holobionts**, including the full diversity of the many different

15 microorganisms associated with them (Vandenkoornhuyse et al., 2015). Almost all plant roots are colonized by microbial symbionts, making it difficult to quantify the separate contributions of plants and associated microorganisms to mineral weathering. There is broad agreement that fungi are important biotic agents of geochemical change (see Gadd, 2010, 2013 a, b, 2017) and that coevolution of fungi and plants has enabled them to have increasing influence as biogeochemical engineers (Fig 3 c-g). Fungi exert significant influence on 20 biogeochemical processes, especially in soil, rock and mineral surfaces and the plant root-soil interface where mycorrhizal fungi are responsible for major mineral transformations, redistribution of inorganic nutrients and flow of C. They are important components in rock inhabiting communities with roles in mineral dissolution and secondary mineral formation. The ubiquity and significance of lichens as pioneer organisms in the early stages of mineral soil formation, and as a model for understanding weathering in a wider context, has been discussed by 25 Banfield et al. (1999) and Chizhikova et al. (2016). In lichens, photosynthetically fixed C is transferred from the photobionts (green algae and cyanobacteria) to a fungal thallus in contact with the mineral surfaces. Non-photosynthetic prokaryote assemblages are also present in a zone of microbially-mediated weathering where mineral surfaces are covered in complex mixtures of high molecular weight polymers, clays and oxyhydroxides, and mineral weathering is accelerated via polymer-mediated dissolution/transport/recrystallization. Increasing 30 evidence suggests that these bacteria are integral components of lichen thalli, contributing to the overall fitness of the lichen in functionally diverse ways (Grube et al., 2015) and that the structure of the bacterial microbiome is influenced by the identity of the photoautotrophic symbionts (Hodkinson et al., 2012). Whilst the functional roles of these bacteria are still poorly understood, some have been demonstrated to solubilize phosphate

(Sigurbjörnsdóttir et al., 2015). There are similarities in the carbon compounds produced by fungi forming lichens and other fungi, but in later successional stages other types of symbiosis occur, involving mycorrhizal plants, and throughout evolution successive increases in the size of plants (Quirk et al. 2015) have allowed larger amounts of carbon to be allocated to larger root systems and greater amounts of mycorrhizal mycelium and exudates –

5 increasing their potential for interacting with mineral substrates. Although the genetic potential for hydrolytic decomposition of cellulose and other plant cell wall components has contracted in comparison with their saprotrophic ancestors (Kohler et al., 2015; Martin et al., 2016), saprotrophic fungi also exude the same types of carbon compounds as ectomycorrhizal fungi, including organic acids. *Paxillus involutus*, an ectomycorrhizal species derived from a clade of brown-rot fungi, appears to have retained the non-enzymatic Fenton chemistry
10 used by brown-rot fungi to extract N from organic matter (Nicolás et al., 2019). *P. involutus* produces oxalate and weathers minerals and it is possible that different organic acids have multiple effects beyond weathering but, as far as we are aware, differences in organic acid production have not yet been studied comprehensively from an evolutionary perspective. Fahad et al. (2016) compared mobilization of base cations and P from granite particles by saprotrophic and ectomycorrhizal fungi *in vitro* and found statistically higher levels of accumulation of Mg, K
15 and P by the ectomycorrhizal fungi, but only a few species were examined and further systematic comparisons of larger numbers of species need to be conducted to establish the generality of this result. Symbiotic ectomycorrhizal fungi are thought to have evolved repeatedly and independently from saprotrophic precursors, so there should have been selection for ectomycorrhizal fungi that can efficiently mobilize nutrients and transfer them to the large sinks created by their host trees. However there have also been multiple reversals from the symbiotic habit to the free-
20 living saprotrophic habit (Hibbett et al., 2000) so caution should be exercised in generalizations based on lab experiments. *In-vitro* experiments, in which fungi are cultured without their host plants, also introduce artifacts since the host plants act as important sinks for weathering products, preventing feedback inhibition of weathering processes due to accumulation of reaction products.

25 Many studies of ectomycorrhizal influence on weathering rates have been performed over short periods and do not always provide clear evidence that processes observed at the laboratory-scale play a significant role in “soil-scale” mineral dissolution rates. Smits et al. (2014) used a vegetation gradient from bare soil, via sparse grass to Norway spruce forest in a natural lead contaminated area in Norway to study long-term effects of vegetation on apatite weathering in moraine deposited at the end of the last glaciation. Vegetation had a strong stimulatory effect
30 on apatite weathering and 75% of the variation in apatite weathering could be explained by soil pH, but the effect of plant roots and mycorrhizal symbionts on this process could not be separated. In the top 20 cm of the mineral soil an additional mechanism, not mediated by pH, enhanced dissolution of apatite. The authors suggested this might be caused by organic acids, leading to higher concentrations of the organic-metal complexes on the mineral surfaces but that the origin of these acids was probably not ectomycorrhizal fungi since these fungi were absent in the grass

vegetation at the highest pH area of the vegetation gradient. Under these conditions, the biomechanical and chemical effects of ectomycorrhizal fungi on apatite weathering seemed to be minor, but these effects are probably dependent on the nutrient status of the forest. Enhanced colonization of apatite by ectomycorrhizal hyphae in laboratory systems (Rosling et al., 2004; Smits et al., 2012) is also commonly found under field conditions, but only when P availability 5 is low (Rosenstock et al., 2016; Bahr et al., 2015; Almeida et al., 2018). The potential for weathering by ectomycorrhizal fungi is probably much higher under these conditions and the nutrient status of the forest should be considered when biological weathering rates are quantified, at least for apatite weathering, where P status has a strong effect on fungal colonization of apatite. In contrast, no enhanced colonization of biotite and hornblende by ectomycorrhizal hyphae was found in Norway spruce forests in the Czech Republic under low K or Mg availability 10 (Rosenstock et al., 2016). This suggests that ectomycorrhizal fungi have a smaller potential to enhance weathering of these minerals compared to apatite. However, these results should be treated with caution since no quantitative/chemical estimates of the mineral weathering were made and use of ergosterol-based estimates of fungal biomass as a proxy for ‘weathering’ can be misrepresentative, since some ectomycorrhizal fungi that actively release LMW organic acids may not invest much carbon in their own biomass. Further investigations using RNA-based 15 analysis of active microbial communities, combined with temporal assessment of weathering kinetics, should reveal the true potential of microorganisms in biogeochemical weathering in forest ecosystems. Effects of N-fixing microorganisms on weathering activity have not been studied in detail but the resulting inputs of N might be expected to drive growth and increase demand for rock-derived nutrients. Recent studies by Perakis and Pett-Ridge (2019) based on uptake of strontium (Sr) isotopes, suggest that nitrogen fixing red alder (*Alnus rubra*) trees can take up 20 significantly more rock-derived Sr than five other co-occurring tree species, although the mycorrhizal fungi colonising these trees were not identified.

Fungal weathering of rocks and minerals through biomechanical and biochemical attack has been studied extensively. Proton-promoted dissolution is supplemented by ligand-promoted dissolution of minerals by strong 25 chelators such as oxalic and citric acid that may act synergistically with siderophores. Secondary minerals may be deposited as carbonates, oxalates or other mycogenic minerals and mineraloids and the role of “rock-building fungi” has been discussed in addition to the role of “rock-eating fungi” (Fomina et al., 2010). Fungi are prolific producers of oxalate, and oxalotrophic bacteria are capable of oxidizing calcium oxalate to calcium carbonate. Since the oxalate is organic in origin, and half its C is transformed into mineral C with a much longer residence time, this process 30 represents a potential major sink for sequestration of atmospheric C (Verrecchia et al., 2006). Precipitation of carbonate minerals by microorganisms during silicate weathering has also been discussed by Ferris et al. (1994) in relation to its potential role as a sink for atmospheric CO₂. The oxalate-carbonate pathway may not be important in boreal forest soils, however the African oxalogenic iroko tree *Milicia excelsa*, together with associated saprotrophic fungi and bacteria, enhances carbonate precipitation in tropical oxisols, where such accumulations are not expected

due to the acidic nature of the soil (Cailleau et al., 2011), and the same phenomenon has been demonstrated in acidic soils of a Bolivian tropical forest (Cailleau et al., 2014). Studies of bacterial assemblages in soil associated with ectomycorrhizal roots of *Pinus massoniana* and *Quercus serrata* have revealed enrichment of oxalotrophic bacteria using the oxalate-carbonate pathway, representing a potential long-term sink for photosynthetically fixed carbon 5 derived from the atmosphere (Sun et al., 2019a). The role of microorganisms in dissolution and modification of karst stones such as limestone and dolomite has also been studied (Lian et al., 2010, 2011). Microbially mediated chemical corrosion and precipitation in surface and underground water can play a role in pedogenesis and provide a sink for atmospheric CO₂ and the role of carbonic anhydrase in hydrating atmospheric CO₂ to HCO₃⁻ has been investigated 10 in relation to changes in CO₂ concentration and availability of Ca²⁺ (Xiao et al., 2014, 2015). The results of the latter study suggest that the importance of microbial carbonic anhydrase on silicate weathering and carbonate formation may be higher at current CO₂ levels than under primordial conditions 2 Ma ago when CO₂ levels were much higher.

Rapid decreases in soil respiration following the girdling of forest trees (Högberg et al., 2001), suggest that the flux of current assimilates to mycorrhizal roots is directly connected to the supply and respiration of C in soil. In another study (Högberg and Högberg, 2002), extractable DOC in a 50-year-old boreal forest, was 45% lower in 15 girdled plots than in control plots, suggesting a large contribution by roots and associated fungi to soluble C pools, although the contribution of these two components could not be determined separately. Biogeochemical weathering of silicate rocks is a key process in the carbon cycle (Pagini et al., 2009) and, although consumption of CO₂ by weathering is small compared with transfers associated with photosynthesis and respiration, it is the dominant sink 20 in global carbon balance and controls atmospheric CO₂ and climate patterns at scales of millennia or longer (Goudie and Viles, 2012).

The geoengineering potential of artificially enhanced silicate weathering is now increasingly well established (Köhler et al., 2010) and addition of pulverised silicate rocks to different croplands has been advocated as an effective strategy for global CO₂ removal (CDR) and ameliorating ocean acidification by 2100 (Taylor et al., 2016; Beerling et al., 2018). Large scale field trials are now in progress <http://lc3m.org/> but basic information about the 25 way in which different microorganisms drive the sequestration processes in different soil types is still missing. Recent studies on carbonate weathering by ectomycorrhizal fungi colonizing tree roots (Thorley et al., 2015) suggest that ectomycorrhizal tree species weather calcite containing rock grains more rapidly than arbuscular mycorrhizal (AM) trees because of greater acidification by the ectomycorrhizal trees. Weathering and corresponding alkalinity 30 export to oceans may increase with rising atmospheric CO₂ (Andrews and Schlesinger, 2001) and associated climate change, slowing rates of ocean acidification.

Transfer of increasing amounts of photosynthetically derived carbon to ectomycorrhizal fungi and improved colonization of mineral substrates during evolution of plants (Quirk et al., 2012, 2014) are consistent with the idea that weathering of silicate minerals and sequestration of C into ocean carbonates has led to drawdown of global CO₂ levels during the rise of ectomycorrhizal trees over the past 120 Ma (Taylor et al., 2011; Morris et al., 2015).

However, the relative constancy of atmospheric CO₂ levels and absence of even further reductions over the final 24 Ma of the Cenozoic has been attributed to a negative feedback mechanism caused by CO₂ starvation (Beerling et al., 2012) that is predicted, by numerical simulations, to reduce the capacity of the terrestrial biosphere to weather silicate rocks by a factor of four. Differences in the magnitude of carbon transfer from plants to different types of mycorrhizal fungal symbionts, and the physiological mechanisms regulating this transfer are influenced by the biotic and abiotic environment, as well as the life history and evolutionary origins of the symbiosis. Common-garden experiments (Koele et al., 2012), using sister clades of plants (with different types of mycorrhiza), might provide a suitable way of comparing functional groups but broad generalisations should be made with extreme care since there is a high degree of context dependency (Field et al., 2017). Ericoid mycorrhizal fungi can produce copious amounts of LMW organic acids that solubilize inorganic zinc compounds (Martino et al., 2003) but there are so far no systematic studies of their role in different weathering interactions in comparison to other fungi. Further comparative studies of the role of different types of mycorrhizal symbioses in mineral weathering may shed light on the different physiological mechanisms involved. Soil microorganisms can have strong effects on plant resource partitioning and it has been shown (Ryan et al., 2012) that *Kennedia* species inoculated with arbuscular mycorrhizal fungi allocated lower amounts of carboxylates to the rhizosphere but had higher concentrations of P than non-inoculated plants, presumably using less strongly sorbed forms of P.

Inferences about evolutionary development of weathering have been drawn using vertical scanning interferometry to study “trenching” of silicate mineral surfaces (basalt) buried under different tree species growing in an arboretum (Quirk et al., 2012) and suggest that trenching and hyphal colonization increase with evolutionary progression from AM fungi to ectomycorrhizal fungi, and with progression from gymnosperm to angiosperm host plants. It is suggested that this evolutionary progression resulted in release of calcium from basalt by ectomycorrhizal gymnosperms and angiosperms at twice the rate achieved by AM gymnosperms, and that forested ecosystems have become major engines of continental silicate weathering, regulating global CO₂ concentrations by driving calcium export into ocean carbonates (Quirk et al., 2012) (Fig. 4). Additional laboratory studies of the same tree species using different CO₂ environments suggest that weathering intensified during evolutionary progression from AM fungal symbionts to ectomycorrhizal symbionts and that calcium dissolution rates were related to photosynthate energy fluxes and higher during simulated past CO₂ atmosphere (1500 ppm) under which ectomycorrhizal fungi evolved (Quirk et al., 2014).

30 **Summary:**

Microorganisms have interacted with minerals for billions of years, enriching the atmosphere with oxygen and shaping the evolution of minerals long before the evolution of land plants. There is strong evidence that the plastids of algae and higher plants evolved from free-living bacteria through endosymbiosis and plants have continued to

evolve in conjunction with microorganisms through symbiotic alliances (mycorrhiza, actinorhiza, rhizobia, plant growth-promoting rhizobacteria (PGPR) etc.) such that they are really holobionts – assemblages of organisms. This enabled the holobionts to become successively more efficient biogeochemical engineers. Hypotheses have been advanced concerning the evolutionary development of weathering and differing contributions of different types of mycorrhizal symbiosis. Further advances in understanding will require more studies of different combinations of plant and fungal species, accompanied by rigorous, DNA-based, *in-situ* identification of the different fungal symbionts. However, the magnitude of carbon transfer to different types of mycorrhizal fungal symbionts, and the physiological mechanisms regulating this transfer are highly context dependent and advances in knowledge will require sound ecological understanding, based on integration of a diverse array of biotic and abiotic factors. Better information is still required on the identity of bacteria and fungi colonizing bedrock outcrops and other mineral substrates in forests. The diversity of these communities is high and it is important to identify the particular taxa that are most active in competing for plant derived C and to identify the amounts and chemical forms in which it is delivered to mineral surfaces. Use of ^{13}C -based stable isotope probing is likely to be helpful in identifying the most active taxa delivering plant-derived C to mineral surfaces. Analysis of the chemical composition of compounds involved will necessitate further studies using nanoSIMS, NMR and FTIR spectroscopy. Improved understanding of weathering at an ecological level requires better knowledge about the processes involved in sequestration of atmospheric CO₂ and further investigation of the forms in which C is sequestered during weathering in forests is necessary. Weathering processes are impacted by different environmental conditions and types of forest management and further studies are required to investigate how these are impacted by changes in atmospheric CO₂ concentration and effects of N deposition and fertilization.

6 Methods using stable isotopes

Stable isotopes, especially of Ca and Sr, have been used extensively to source the origin of Ca in drainage water; when applied to plant tissues, they can be used to trace plant nutrients back to their primary source. Isotope tracing has been mostly used to study apatite weathering. P has no stable isotopes, and the mobilisation and uptake dynamics of apatite can therefore only be studied via the Ca ion (or potentially the $^{18}\text{O}/^{16}\text{O}$ in the phosphate group). In most rocks and soils, apatite is the sole primary P source. However, its contribution to the soil solution Ca pool is minor compared with other minerals. If the Ca isotope ratio in the plant is more similar to the signature in apatite than to the signature in the soil solution, then it indicates that the plant directly acquires Ca from apatite. Blum et al. (2002) applied this technique to a temperate mixed forest using Ca:Sr ratios in soil water, minerals in the soil and different mycorrhizal and non-mycorrhizal trees. The authors concluded that direct calcium uptake by ectomycorrhizal fungi weathering apatite in the parental material could compensate for calcium loss in base-poor ecosystems. Data on element ratios should, however, be interpreted with care, because of high variation of Ca:Sr ratios in different plant

tissues and limited understanding of the cycling of these elements in plants (Watmough and Dillon, 2003), as well as contradictory data of Dijkstra and Smits (2002) (see below) that suggest the conclusion of Blum et al. (2002) is overstated. Field studies using mesh bags containing microcline and biotite, buried in Swedish *Picea abies* forests (Wallander et al., 2006) used the ^{87}Sr : ^{86}Sr ratio to calculate the fraction of Sr in the mycorrhizal root tips that had 5 originated from the minerals. Although the total amounts of Sr released from the minerals could not be calculated since the total plant biomass enriched with ^{87}Sr was unknown, the study clearly demonstrates the potential of ectomycorrhizal fungi to mobilize and take up nutrients such as Ca and K from microcline and biotite under field conditions.

In many forest ecosystems, plant-available pools of Mg, Ca, and K are assumed to be stored in the soil as 10 exchangeable cations adsorbed on the cation exchange complex (exchangeable pools). However, other storage forms of Mg, Ca, and K that have not been fully characterized may play an important role in plant nutrition and biogeochemical cycles and be plant-available on very short time scales (<1 day). Isotopic dilution techniques using the stable isotopes ^{26}Mg , ^{44}Ca , and ^{41}K have been developed (van der Heijden et al., 2018) to trace and quantify the 15 pools of Mg, Ca, and K (isotopically exchangeable pools) in the soil of a hardwood forest that contribute directly to equilibrium processes between the soil water and the soil. These show that isotopically exchangeable pools of Mg, Ca, and K are greater than traditionally measured exchangeable pools. Storage forms of Mg, Ca, and K in the 20 isotopically exchangeable pool could include chelation with soil organic matter, retention on soil aluminum and iron oxides and hydroxides through phosphate and/or organic acid bridges and site-specific adsorption. The isotopic dilution method is a relevant tool to quantify the plant-available pools of Mg, Ca, and K on short time scales (source and sink pools) and is a very promising approach to characterize and quantify the processes responsible for the 25 depletion and/or replenishment of these pools over longer time scales.

Field studies of small rock fragments isolated from a Finnish *P. sylvestris* forest with *Tricholoma matsutake* fruiting bodies (Vaario et al., 2015) revealed the presence of *T. matsutake* on 97% of the rock fragments and laboratory assays using X-ray diffraction confirmed the ability of the fungus to absorb some trace elements directly 25 from the rock fragments, but uptake of Mg and K did not appear to be significant. In contrast, laboratory studies of the capacity of different fungi to mobilize P and base cations from granite particles (conducted within QWARTS) (Fahad et al., 2016) suggest that some ectomycorrhizal fungi can mobilize and accumulate significantly higher concentrations of Mg, K and P than non-mycorrhizal fungi. The mycorrhizal fungi can fractionate Mg isotopes, 30 discriminating against heavier isotopes and we found a highly significant inverse relationship between $\delta^{26}\text{Mg}$ tissue signatures and mycelial concentration of Mg (Fig. 5). This provides a theoretical framework for testing hypotheses about fungal weathering of minerals in future experiments. If active mobilization and uptake of lighter ^{24}Mg isotopes results in relative enrichment of heavy Mg isotopes left in soil solution and soil, this should be evident in areas of active weathering. Mesocosm experiments, conducted within the QWARTS project (Mahmood et al., in preparation), employing a gradient of increasing organic matter depletion to simulate progressively more intense

forest biomass harvesting, revealed significant and successive enrichment of ^{26}Mg signatures in the soil solution in the B horizon, associated with increased availability of organic matter and resultant increases in plant and fungal biomass (Fig. 6). No such enrichment was found in other horizons or in systems without plants (and therefore without mycorrhizal fungi). This suggests that significant biological weathering of Mg takes place in the B horizon, driven by higher plant biomass that enables improved carbon allocation to the fungal mycelium and also constitutes a larger sink for uptake of mobilized base cations. Although the experiments provide strong support for the idea of biologically driven mobilization of Mg from B horizon mineral soil, the process was not sufficient to maintain optimal tree growth in systems with a severely reduced organic matter pool. In addition, studies carried out under both field and laboratory conditions show that Mg isotope fractionations are controlled by the same biological factors in the critical zone, defined as the outer layer of earth from vegetation to the soil. Silicate rocks show a relatively small range of variation in Mg isotopic ratios (denoted as $\delta^{26}\text{Mg}$) (Bolou-Bi et al., 2009; Shen et al., 2009; Uhlig, et al., 2017). During the weathering of these rocks at watershed level, it was revealed that isotopic fractionation of Mg isotopes was in favour of light isotopes in soil solution, while the soils were enriched in heavy isotopes (Pogge von Strandmann et al., 2008; Tipper et al., 2010). Studies conducted in forest ecosystems, (Bolou-Bi et al., 2012; Mavromatis et al., 2014; Uhlig et al., 2017) indicate variation in soil solution signatures of surface soil layers, suggesting a role of vegetation through the Mg isotope cycle (uptake and litterfall), soil exchangeable fraction and rainwater, in addition to light Mg isotope return via litterfall. In deeper soil horizons, however, the soil solution signatures may be the result of two additional processes (a) the mineral dissolution leaching the light isotope into solution and subsequently weathered minerals are systematically enriched in heavy Mg isotopes relative to fresh rock, and (b) clay formation and/or Mg adsorption removing the heavy Mg isotope from soil solution (Huang et al., 2012; Opfergelt et al., 2014). Mg isotope fractionation has also been observed under laboratory conditions during the dissolution of primary minerals (Wimpenny et al., 2010).

In studies of Ca isotope cycling in forest ecosystem, it appears that the soil solution and exchangeable fraction generally display enrichment in the heavy isotope compared to soil particles, bedrock and rainwater (Holmden and Bélanger, 2010; Hindshaw et al., 2011). However, the soil solution isotope signatures are not the simple result of weathering processes in soils because the congruent dissolution of rock or mineral observed in lab and field conditions did not cause any measurable Ca isotope fractionation (Hindshaw et al., 2011; Ryu et al., 2011; Cobert et al., 2011). This suggests that another process, such as the preferential uptake of the light Ca isotope (^{40}Ca) by vegetation, decreases the soil solution Ca isotope ratio in the upper horizon in addition to light Ca isotope return via litterfall (Page et al., 2008; Holmden and Bélanger, 2010). In deeper soil horizons, soil solution $\delta^{44/40}\text{Ca}$ may result from the dissolution of minerals such as apatite. Interestingly, experiments by Dijkstra and Smits (2002) indicate that most of the Ca taken up by trees comes from litter recycling. In a comparable mixed forest, also in the north-eastern United States, the annual Ca import from weathering in the rooting zone is less than 0.3% of the annual Ca uptake, which was a four-fold smaller flux than the annual atmospheric deposition (Dijkstra and Smits, 2002). Inputs

of nutrients such as P, from atmospheric deposition, may also be significant in coastal Fynbos systems (Brown et al., 1984) and the Florida everglades (Redfield et al., 2002). However, the data from our QWARTS experiments suggest that mobilization of Mg may function differently in boreal coniferous forests, with higher amounts being mobilized from inorganic substrates in the B horizon.

5 Mycorrhizal fungi play a central role in mobilizing N and P from organic substrates and when these are depleted, N and P limit tree growth, resulting in reduced C supply to the mycorrhizal mycelium and reduced capacity for mobilization of base cations from the mineral horizons. Although mobilization of Mg from the B horizon was sufficient to support increased biomass production in systems supplied with extra organic material (Fig. 6), it was not sufficient to compensate for losses of base cations when organic material was most depleted. The results of these
10 experiments are therefore consistent with the predictions of modelling that, under intensive forestry with removal of organic residues, base cation supply will not be sustainable in the long term. Intensive, sustained harvesting of biomass may lead to N limitation before base cations become limiting. Applications of different fertilizers (Xiao et al., 2017) or inadvertent N deposition (Averill et al., 2018) may have negative effects on both weathering and C sequestration.

15 Smits and Wallander (2017) advocate detailed studies of the liquid chemistry of local weathering sites at the micrometre scale, together with up-scaling to soil-scale dissolution rates, and the authors suggest that future research should focus on whole ecosystem dynamics, including the behaviour of soil organic matter, and that early-stage primary succession ecosystems on low reactive surfaces, such as fresh granites, should be included. Smits and Wallander (2017) also recommend the use of stable isotopes by choosing minerals and soils with distinct isotope
20 ratios.

Summary:

Experiments using stable isotopes have potential to improve understanding of the roles played by different groups of micro-organisms in biological weathering. *In-vitro* studies of base cation mobilization from granite particles so
25 far suggest that symbiotic mycorrhizal fungi may be more efficient at mobilizing Mg, K and P than saprotrophic fungi but it is necessary to test a wider range of species before such broad conclusions can be drawn. Care should also be exercised in interpreting experiments conducted *in vitro* in the absence of host plants, since these provide important sinks for mobilized nutrients that could otherwise retard weathering reactions should they accumulate. Fractionation of stable Mg isotopes by mycorrhizal fungi, with preferential uptake of lighter isotopes, results in
30 enriched levels of ^{26}Mg in soil solution and laboratory experiments with reconstructed podzol profiles have demonstrated that this enrichment occurs primarily in the B horizon. The data suggest that this pathway may be of significance in the field but reductions in (N-containing) organic matter resulted in reduced tree growth and reduced Mg uptake, suggesting that increased biological weathering of Mg is unlikely to compensate for losses of Mg through

organic matter removal if N is also limiting. However, K and P were also deficient in this experiment so conclusions should be drawn with care. Similar experiments with isotopes of other elements may reveal wider information about patterns of nutrient uptake. In addition to their possible weathering effects, mycorrhizal fungi play important roles in N acquisition from organic substrates, illustrating how decomposition and weathering are intercoupled.

5 7 Modelling of biological weathering in forest soils

7.1 Developments and Improvements in modelling biological weathering

Models greatly improve our ability to quantify weathering rates and how they change over time. Akselsson et al. (2019) present an extensive review of methods for estimating weathering rates in forest soils. These range from mass balance budget calculations (e.g. Simonsson et al., 2015) and gravimetric approaches (Turpault et al., 2009), to the depletion method based on the elemental concentration differences between weatherable and unweatherable minerals (such as zirconium bound in zircon or titanium in rutile) (Stendhal et al., 2013), to dynamic models based on the transition state theory (Erlandsson et al., 2016). These methods address, in different ways, the role of biological processes in weathering (Rosling et al., 2009). Here we attempt to describe the major approaches to implementing important biological processes into weathering rate estimates over the last decade.

15 Catchment and ecosystem mass balance approaches have been widely employed to estimate mineral weathering rates (Price et al., 2013, Hartmann and Moosdorf, 2011). Application of machine learning approaches (Povak et al., 2014) can further increase the utility of mass-balance approaches for evaluating the potential importance of different processes to weathering rates. Biomass accumulation emerges, in many simulations, (Wilcke et al., 2017; Zetterberg et al., 2016) as a key variable in mass-balance estimates of mineral weathering and a major source of uncertainty 20 (Simonsson et al., 2015; Zetterberg et al., 2016). Furthermore, the derivative nature of the mass-balance approach reduces its value for assessing the mechanisms that control weathering rates, reducing their suitability to predict future weathering rates under changing conditions.

Taylor et al. (2011) built on a geochemical model developed by Banwart et al. (2009), which attempts to quantify the contribution of biologically derived protons and ligands to mineral weathering rates, and distinguishes between 25 vegetation that forms arbuscular (AM) mycorrhizal associations and vegetation that forms ectomycorrhizal (EM) associations. Their model, assumes that AM fungi do not exude significant amounts of organic acids while EM fungi do, and models the activity of that exudation as that of oxalic acid. They also divide the soil volume into an area of immediate proximity to mycorrhizal hyphae, the mycorrhizosphere, and the bulk soil. When they applied their model 30 over the last 200 Ma they observed that the draw-down of global atmospheric CO₂ levels over the last 120 Ma could largely be attributed to the emergence and diversification of angiosperms and the spread of EM fungi. However, in addition to organic acid exudation, hyphal length density, which defined the volume of the mycorrhizosphere, was parameterized to be 25-fold greater in EM dominated ecosystems than AM dominated systems. Modelled soil

chemistry and the resulting terrestrial carbon sink, were also highly sensitive to hyphal length density. Taylor et al. (2012) further developed this weathering model based on mycorrhizal association type and coupled it to a dynamic global vegetation model and validated it against a global dataset of watershed flux data. The resulting model, when applied over the last 200 Ma indicated that biological weathering was stronger in the distant past than today, and 5 estimated that vegetation and mycorrhizal fungi have increased terrestrial weathering rates by a factor of 2. While their model performed reasonably well in the validation across a global series of catchment data, their findings did not support a distinct dichotomy in weathering behaviour between AM-dominated and EM-dominated ecosystems. Quirk et al. (2014) build on the model developments of Taylor et al. (2011, 2012) to illustrate the potential for a feedback between atmospheric CO₂ levels and biological weathering rates, such that, as CO₂ levels increase, global 10 plant productivity and autotrophic soil inputs of protons and organic acids do so as well, stimulating biological weathering and serving as a negative feedback to increasing CO₂ levels. As CO₂ levels decrease, so does biological weathering. This sequence of models develops hypotheses concerning the role of land-plants in the geology of earth and the global biogeochemical carbon cycle, with a framework to account for differential biological weathering 15 activity by distinct vegetation types. While considerable evidence exists pointing to the potential for ectomycorrhizal fungi to be more potent weathering agents than AM fungi, field studies comparing weathering rates in paired AM- and EM-dominated forests have failed to find significant differences in mineral weathering rates (Koele et al., 2014; Remiszewski et al., 2016). Future applications utilising rhizosphere or mycorrhizosphere vs bulk soil volumes should place more emphasis on the choice of hyphal length densities, and should likely use functions, as opposed to 20 fixed parameters, that depend on plant type as well as plant productivity and nutrient status to describe fine root and mycorrhizal hyphal root lengths.

Roelandt et al. (2010) coupled a reactive transport model to the Lund-Potsdam-Jena global dynamic vegetation model, which they termed Biosphere-Weathering at the Catchment Scale (B-WITCH), and were able to model base cation efflux accurately from the Orinoco watershed. They concluded that vegetation exerts a major role on mineral weathering rates, but that this role is primarily hydrological, via evapotranspiration fluxes. However, while their 25 model did feature organic ligand-promoted dissolution, the source of those ligands was decomposition only, they treat the entire rooting zone as a single interconnected solution, and while they do feature plant functional types, those functional types do not correspond to belowground physiology or mycorrhizal association. The B-WITCH model appears to reflect the most mechanistic approach amongst global dynamic vegetation models to estimating mineral weathering rates, but additional processes may need to be implemented to capture the influence of biology 30 on mineral weathering rates.

Maher et al. (2010) applied the reactive transport geochemical model CrunchFlow, which estimates weathering rates based on experimentally-derived dissolution equations for individual minerals, to examine the effect of fluid residence time, which in turn controls the transport of weathering products away from mineral surfaces, on mineral weathering rates. They observed a strong inverse relationship between fluid residence time and weathering rates and

interpreted this as clear evidence for transport control of weathering rates in natural ecosystems. Lawrence et al. (2014) coupled an organic acid module to the CrunchFlow model to examine the potential role of organic acids, modelled as oxalic acid, on mineral weathering rates, and observed that the primary effect of oxalic acid was to increase soluble Al but decrease free Al³⁺ concentrations in solution; mineral weathering was enhanced near the 5 zone of oxalic acid production (the topsoil) but decreased further down the profile. The description of organic acid levels as the product of production and decomposition processes and the geochemical description of ligand-promoted chelation, dissolution, and transport may be useful process descriptions to model the effects of biological exudates on mineral weathering rates and adaptable across a range of models. Winnick and Maher (2018) developed 10 CrunchFlow to examine the dependence of mineral weathering rates on gaseous and dissolved CO₂ concentrations, and observed a very strong relationship between weathering rates and soil CO₂, and suggested that this may be an 15 important mechanism by which soil respiration of vegetation (and mycorrhizal fungi) may stimulate mineral weathering.

Mineral weathering is dynamically simulated in the PROFILE and ForSAFE models, which have been widely used for unsaturated soils (for recent examples see Akselsson et al., 2016; Erlandsson et al., 2016; Belyazid 15 et al., 2019; Phelan et al., 2014). In ForSAFE, tree cover, soil microbes and related biological processes are also integrally simulated. Trees are assumed to affect weathering through a number of causal pathways: Firstly, trees have a direct negative influence on soil moisture through transpiration. The consequent reduction in soil moisture limits weathering, as the latter is directly dependent on wetted mineral surface area. Water uptake also leads to an 20 increase in element concentrations, drawing the soil solution closer to saturation and acting as a retarding brake on weathering (Erlandsson et al., 2016). Secondly, nutrient uptake reduces the concentration of base cation weathering products, releasing these brakes, thereby promoting weathering rates. Thirdly, plants are responsible for the production of organic matter, which, through below ground allocation and litter fall, feeds soil organic carbon, dissolved organic carbon and CO₂ concentrations. Both organic radicals and higher soil CO₂ pressure have positive 25 influences on weathering rates. At the same time, the mineralization of litter also releases the base cations, thus increasing element concentrations and thereby slowing down weathering rates. Fourthly, plants have a direct effect on soil solution proton concentration which promotes higher mineral weathering. Plants can lower pH through the production of organic matter, but most importantly through the uptake of positively charged cations and release of 30 protons to counterbalance charge. Lower pH promotes higher weathering rates, but also the solubility of aluminium ions whose higher concentrations act as weathering brakes. The net effect on weathering, i.e. the balance between the positive effect from lower pH and the negative from higher aluminium concentrations, may differ depending on soil properties. The contribution of biological weathering may be improved by division of the soil volume into rhizosphere or mycorrhizosphere and bulk soil portions. Process descriptions of root and hyphal influence on the solution and surface chemistry within the rhizosphere/mycorrhizosphere could also be improved. Division of DOC

into discrete chemical functional classes (promoting vs inhibitory, actively exuded vs. incomplete decomposition products) could increase our understanding of the influence of ligand promotion or inhibition of weathering rates.

7.2 Research priorities for modelling biological weathering

5 Based on the preceding sections, we have identified five biological processes that can be incorporated into models quantifying soil mineral weathering rates, to make them more mechanistic and useful as predictive tools:

- Exudation of LMW ligands promoting weathering
- Nutrient uptake rates as a driver of weathering reactions
- The concentration effect of biofilms on weathering-promoting ligands and protons

10 ·The dependence of the above process on particular microbial and plant assemblages, including mycorrhizal type.

- The dependence of the above processes on carbon flux from autotrophs, and the sensitivity of this to water and nutrient availability.

15 The stimulatory effect of particular LMW organic acids and siderophores on soil mineral weathering rates is a function of both exudation rate as well as biological degradation rates of the same compounds. The chemical composition of soil water DOC and exudates exerts considerable control on the degree of stimulation, or, potentially, inhibition of weathering rates. Modelling ligand-promoted dissolution as a function of total DOC without consideration of DOC character may lead to inaccurate interpretations of mineral dissolution rates derived from
20 experiments with specific organic species, but should, with better data, open the door for more complex descriptions of soil solutions and their effects on mineral weathering rates.

Geochemical weathering models require the incorporation of mechanisms (either through equilibrium equations or inhibitory factors) that allow the build-up of weathering products to slow weathering rates. The treatment of soil solution fluxes should allow for accumulation and removal of weathering products in soil microenvironments (such
25 as around mineral surfaces and mycelia), as bulk soil solution data may not capture the concentration gradients found around mineral surfaces. The observation, across a variety of both empirical studies and modelling approaches, that nutrient uptake into vegetation is a major driver of weathering rates should continue to drive research into the effects of soil solution concentrations near mineral surfaces, and their deviation from bulk soil solution, as a factor controlling dissolution rates. Ongoing research into the extent and chemistry of microbial biofilms in soils, aided by
30 technological developments in micropores and spectroscopy is giving an increased understanding of their importance and extent in the soil for controlling the solution chemistry at mineral surfaces, which may lead to incorporation into models.

The dependence of biological weathering on particular microbial and plant assemblages, in particular mycorrhizal type, has not yet been determined and requires further detailed studies of the specificity of ectomycorrhiza-bacteria interactions and the physiological differences between different bacteria and fungi in their ability to promote dissolution of different minerals. A growing consensus on the importance of root length density 5 and hyphal length density as important explanatory factors governing biological process rates, may lead to increased inclusion of them as factors or parameters in future models. Further information is also required on the variation in carbon flux from autotrophs to different fungal and bacterial components of biofilms in contact with different minerals and the sensitivity of this carbon flux to differences in water and nutrient availability. A major area of model development has been in global plant productivity, not least because of its central role in the carbon cycle. 10 Advances in describing belowground allocation (as opposed to aboveground) have lagged far behind, but are now increasing rapidly, and this should provide valuable data to improve model descriptions of biological weathering processes.

8 Conclusions

In this paper we attempt to outline the consequences of interactions between minerals, microorganisms and plants 15 at different spatial scales and to review the influence of biological processes on mineral weathering within an evolutionary context. The interaction of microorganisms with rocks and minerals took place for 3.5 billion years before the appearance of the first land plants and there is documented evidence that early microorganisms had wide-ranging effects on both chemical and biological processes (Fig. 3), including (a) the accumulation of oxygen in the atmosphere, and the evolution of over two thirds of the minerals that exist today and (b) the evolution of plastids 20 through serial endosymbiosis. The subsequent evolution of higher plants made possible by efficient photosynthesis and successive increases in their size, nutrient acquisition and ability to colonize and allocate photosynthetically-derived carbon to mineral (and organic) substrates, has enabled them to have increasing influence as biogeochemical engineers (Fig 3c-g). Microbial symbionts have played an integral part in the evolution of plants and their ability to capture growth limiting nutrients such as N (Moreau et al., 2019). The influence of vegetation on mineral substrates 25 is almost axiomatic but quantification of the contribution of plant-associated microorganisms to mineral weathering is problematical for two reasons. *Firstly*, the ubiquitous distribution of microorganisms, the fact that plants devoid of microorganisms do not exist under natural conditions, means that plants need to be considered from a more holistic perspective, as holobionts, together with the many different microorganisms associated with them. *Secondly*, processes occurring at small spatial scales are difficult to quantify and upscale to the catchment, ecosystem or global 30 scale. Although the combined effects of plants and their microbial symbionts have quantifiable effects on mineral dissolution and capture of nutrients, continued effort must be directed at elucidating the identity, distribution and functional characteristics of these many different microbial taxa. Sverdrup et al. (2009) acknowledged the

importance of “biologically induced systemic effects” on weathering and concluded that “the growth of the trees and forest growth represents the largest single biological process that can affect weathering, followed closely by decomposition of organic matter”. Boreal and temperate forest ecosystems are characterised by ubiquitous symbiotic associations with ectomycorrhizal fungi and the central axiom of the current paradigm of ectomycorrhizal functioning is that these systems have evolved to promote tree growth through efficient uptake of nutrients, in particular through mobilisation of N via decomposition of organic substrates (Lindahl & Tunlid, 2015; Nicolás et al, 2019). Ectomycorrhizal fungi are therefore very likely to influence mineral weathering directly or indirectly and additional information about their direct interactions with mineral substrates and likely responses to different types of environmental stresses, including those induced by forest management practices, is an important research priority.

5 Weathering of minerals is important not just with respect to the sustainability of forestry. It is evident that the global weathering engine has had long-term effects on atmospheric CO₂ levels. Long term stabilization of C, derived from the atmosphere, in organic and mineral substrates, may take place through interactions involving glycoproteins, melanin, extracellular polymeric substances and formation of secondary minerals and mineraloids. Better understanding of these processes may facilitate improved forestry management practices that not only ensure

10 sustainable production of biomass but can also be integrated into new carbon dioxide reduction technologies.

15

Author contributions

R.D. Finlay wrote most parts of the paper but with suggestions and inputs from all co-authors. N. Rosenstock, S. Belyazid and S. Köhler, in particular, wrote most of the section on modelling and E. Bolou-Bi and H. Wallander provided substantial input to the section on stable isotopes. S. Mahmood provided substantial input to Figures 5 and

20 6. The work described in Figures 5 and 6 was carried out by S. Mahmood and Z. Fahad with advice from S. Köhler. E. Bolou-Bi carried out the stable isotope analyses in these experiments.

Competing interests

The authors declare that they have no conflict of interest.

Acknowledgements

25 This study was funded by the Swedish Research Council for Environment, Agricultural Sciences and Spatial Planning FORMAS (grant no. 2011-1691) within the strong research environment “Quantifying weathering rates for sustainable forestry (QWARTS)”, with addition support to RDF from FORMAS (grant nos. 2014-01272 and 2017-00354).

References

Ahmed, E., and Holmström, S. J. M.: Siderophores in environmental research: roles and applications, *Microb. Biotechnol.*, 7, 196–208, 2014.

Ahmed, E., and Holmstrom, S. J. M.: Microbe-mineral interactions: The impact of surface attachment on mineral weathering and element selectivity by microorganisms, *Chem. Geol.*, 403, 13-23, 2015.

Ahonen-Jonnarth, U., Van Hees, P. A. W., Lundstrom, U. S., and Finlay, R. D.: Organic acids produced by mycorrhizal *Pinus sylvestris* exposed to elevated aluminium and heavy metal concentrations, *New Phytol.*, 146, 557-567, 2000.

Akselsson, C., Belyazid, S., Olsson, B., Stendahl, J., Finlay, R. D., Erlandsson Lampa M., and Bishop, K.: Weathering rates in Swedish forest soils, *Biogeosciences*, 2019. <https://doi.org/10.5194/bg-2019-1> (this volume)

Akselsson, C., Westling, O., Sverdrup, H., and Gundersen, P.: Nutrient and carbon budgets in forest soils as decision support in sustainable forest management, *For. Ecol. Manag.*, 238, 167-174, 2007.

Akselsson, C., Olsson, J., Belyazid, S., and Capell, R.: Can increased weathering rates due to future warming compensate for base cation losses following whole-tree harvesting in spruce forests?, *Biogeochemistry*, 128, 89-105, 2016.

Allen, J. F.: A proposal for formation of Archaean stromatolites before the advent of oxygenic photosynthesis, *Front. Microbiol.*, 7, ARTN 1784, 2016.

Almeida, J. P., Rosenstock, N. P., Forsmark, B., Bergh, J. and Wallander, H.: Ectomycorrhizal community composition and function in a spruce forest transitioning between nitrogen and phosphorus limitation, *Fung. Ecol.*, 40, 20-31, 2019.

Andrews, J. A., and Schlesinger, W. H.: Soil CO₂ dynamics, acidification, and chemical weathering in a temperate forest with experimental CO₂ enrichment, *Global Biogeochem. Cycles*, 15, 149– 162, 2001.

Archibald, J. M.: Genomic perspectives on the birth and spread of plastids, *Proc. Natl. Acad. Sci. USA.*, 112, 10147-10153, 2015.

Averill, C., Dietze, M. C. and Bhatnagar, J. M.: Continental-scale nitrogen pollution is shifting forest mycorrhizal associations and soil carbon stocks, *Glob. Change Biol.*, 24, 4544-4553, 2018.

Bahr, A., Ellstrom, M., Bergh, J., and Wallander, H.: Nitrogen leaching and ectomycorrhizal nitrogen retention capacity in a Norway spruce forest fertilized with nitrogen and phosphorus, *Plant Soil*, 390, 323-335, 2015.

Balogh-Brunstad, Z., Kent Keller, C., Thomas Dickinson, J., Stevens, F., Li, C. Y., and Bormann, B. T.: Biotite weathering and nutrient uptake by ectomycorrhizal fungus, *Suillus tomentosus*, in liquid-culture experiments, *Geochim. Cosmochim. Acta*, 72, 2601-2618, 2008.

Banfield, J. F., Barker, W. W., Welch, S. A., and Taunton, A.: Biological impact on mineral dissolution: application of the lichen model to understanding mineral weathering in the rhizosphere, *Proc. Natl. Acad. Sci. USA*, 96, 3404-3411, 1999.

Banwart, S.A., Berg, A., and Beerling, D.J.: Process-based modeling of silicate mineral weathering responses to increasing atmospheric CO₂ and climate change, *Global Biogeochem. Cycles*, 23, GB4013, doi:10.1029/2008GB003243, 2009.

Beerling, D. J., Leake, J. R., Long, S. P., Scholes, J. D., Ton, J., Nelson, P. N., Bird, M., Kantzas, E., Taylor, L. L., Sarkar, B., Kelland, M., DeLucia, E., Kantola, I., Muller, C., Rau, G. H., and Hansen, J.: Farming with crops and rocks to address global climate, food and soil security, *Nat. Plants*, 4, 138-147, 2018.

Beerling, D. J., Taylor, L. L., Bradshaw, C. D. C., Lunt, D. J., Valdes, P. J., Banwart, S. A., Pagani, M., and

Leake, J. R.: Ecosystem CO₂ starvation and terrestrial silicate weathering: mechanisms and global-scale quantification during the late Miocene, *J. Ecol.*, 100, 31-41, 2012.

Bell, E. A., Bohnke, P., Harrison, T. M., and Mao, W. L.: Potentially biogenic carbon preserved in a 4.1 billion-year-old zircon, *Proc. Natl. Acad. Sci. USA*, 112, 14518-14521, 2015.

5 Belyazid, S., Akselsson, C., and Zanchi, G. Water limitation may restrict the positive effect of higher temperatures on weathering rates in forest soils, *Biogeosciences Discuss.*, <https://doi.org/10.5194/bg-2019-44>, in review, 2019.

Berner, R. A.: Paleoclimate – The rise of plants and their effect on weathering and atmospheric CO₂, *Science*, 276, 544-546, 1997.

10 Blum, J. D., Klaue, A., Nezat, C. A., Driscoll, C. T., Johnson, C. E., Siccam, T. G., Eagar, C., Fahey, T. J., and Likens, G. E.: Mycorrhizal weathering of apatite as an important calcium source in base-poor forest ecosystems, *Nature*, 417, 729–731, 2002.

Bolou-Bi, E. B., Vigier, N., Brenot, A., and Poszwa, A.: Magnesium isotope compositions of natural reference materials, *Geostand. Geoanal. Res.*, 33, 95-109, 2009.

15 Bolou-Bi, E. B., Vigier, N., Poszwa, A., Boudot, J. P., and Dambrine, E.: Effects of biogeochemical processes on magnesium isotope variations in a forested catchment in the Vosges Mountains (France), *Geochim. Cosmochim. Acta*, 87, 341-355, 2012.

Bonneville, S., Smits, M. M., Brown, A., Harrington, J., Leake, J. R., Brydson, R., and Benning, L. G.: Plant-driven fungal weathering: Early stages of mineral alteration at the nanometer scale, *Geology*, 37, 615-618, 2009.

20 Bonneville, S., Morgan, D.J., Schmalenberger, A., Bray, A., Brown, A., Banwart, S.A., and Benning, L. G.: Tree-mycorrhiza symbiosis accelerate mineral weathering: Evidences from nanometer-scale elemental fluxes at the hypha–mineral interface, *Geochim. Cosmochim. Acta*, 75, 6988–7005, 2011.

Bonneville, S., Bray, A. W., and Benning, L. G.: Structural Fe(II) oxidation in biotite by an ectomycorrhizal fungi drives mechanical forcing, *Environ. Sci. Technol.*, 50, 5589-5596, 2016.

25 Borgeaud, S., Metzger, L. C., Scignari, T. and Blokesch, M.: The type VI secretion system of *Vibrio cholerae* fosters horizontal gene transfer, *Science*, 347, 63–67, 2015.

Brantley, S. L., Megonigal, J. P., Scatena, F. N., Balogh-Brunstad, Z., Barnes, R. T., Bruns, M. A., Van Cappellen, P., Dontsova, K., Hartnett, H. E., Hartshorn, A. S., Heimsath, A., Herndon, E., Jin, L., Keller, C. K., Leake, J. R., McDowell, W. H., Meinzer, F. C., Mozdzer, T. J., Petsch, S., Pett-Ridge, J., Pregitzer, K. S., Raymond, P. A., Riebe, C. S., Shumaker, K., Sutton-Grier, A., Walter, R., and Yoo, K.: Twelve testable hypotheses on the 30 geobiology of weathering, *Geobiology*, 9, 140-165, 2011.

Brocks, J. J., Logan, G. A., Buick, R., and Summons, R. E.: Archean molecular fossils and the early rise of eukaryotes, *Science*, 285, 1033-1036, 1999.

Brown, G., Mitchell, D. T., Stock, W. D.: Deposition of phosphorus in a coastal Fynbos ecosystem of the south-western Cape, South Africa, *J. Ecol.*, 72, 547-551, 1984.

35 Cailleau, G., Braissant, O., and Verrecchia, E. P.: Turning sunlight into stone: the oxalate-carbonate pathway in a tropical tree ecosystem, *Biogeosciences*, 8, 1755-1767, 2011.

Cailleau, G., Mota, M., Bindschedler, S., Junier, P., and Verrecchia, E. P.: Detection of active oxalate-carbonate pathway ecosystems in the Amazon Basin: Global implications of a natural potential C sink, *Catena*, 116, 132-141, 2014.

40 Callot, G., Maurette, M., Pottier, L., and Dubois, A.: Biogenic Etching of Microfractures in Amorphous and Crystalline Silicates, *Nature*, 328, 147-149, 1987.

Calvaruso, C., Turpault, M.- P., Frey-Klett, P., Uroz, S., Pierret, M.- C., Tosheva, Z., and Antoine, K.: Increase of apatite dissolution rate by Scots pine roots associated or not with *Burkholderia glathei* PML1(12)Rp in open-system flow microcosms, *Geochim. Cosmochim. Acta*, 106, 287–306, 2013.

Chizhikova, N. P., Lessovaia, S. N., and Gorbushina, A. A.: Biogenic Weathering of Mineral Substrates (Review), 5 in: *Biogenic-Abiogenic Interactions in Natural and Anthropogenic Systems*, edited by: FrankKamenetskaya, O. V., Panova, E. G., and Vlasov, D. Y., Springer, Cham, 7-14, doi:10.1007/978-3-319-24987-2_2, 2016.

Clemmensen, K. E., Bahr, A., Ovaskainen, O., Dahlberg, A., Ekblad, A., Wallander, H., Stenlid, J., Finlay, R. D., Wardle, D. A., and Lindahl, B. D.: Roots and associated fungi drive long-term carbon sequestration in boreal forest, *Science*, 339, 1615-1618, 2013.

10 Cobert, F., Schmitt, A. D., Bourgeade, P., Labolle, F., Badot, P. M., Chabaux, F., and Stille, P.: Experimental identification of Ca isotopic fractionations in higher plants, *Geochim. Cosmochim. Acta*, 75, 5467-5482, 2011.

DasSarma, S. and Schwieterman, E.W.: Early evolution of purple retinal pigments on Earth and implications for exoplanet biosignatures, *Int. J. Astrobiol.*, 1-10, <https://doi.org/10.1017/S1473550418000423>, 2018.

15 Deveau, A., Bonito, G., Uehling, J., Paoletti, M., Becker, M., Bindschedler, S., Hacquard, S., Herve, V., Labbe, J., Lastovetsky, O. A., Mieszkin, S., Millet, L. J., Vajna, B., Junier, P., Bonfante, P., Krom, B. P., Olsson, S., van Elsas, J. D., and Wick, L. Y.: Bacterial-fungal interactions: ecology, mechanisms and challenges, *FEMS Microbiol. Rev.*, 42, 335-352, 2018.

Dijkstra, F. A., and Smits, M. M.: Tree species effects on calcium cycling: the role of calcium uptake in deep soils, *Ecosystems*, 5, 385–398, 2002.

20 Doglioni, C., Pignatti, J., and Coleman, M.: Why did life develop on the surface of the Earth in the Cambrian?, *Geosci. Front.*, 7, 865-873, 2016.

Drever, J. I., and Stillings, L. L.: The role of organic acids in mineral weathering, *Coll. Surf. A*, 120, 167-181, doi: 10.1016/S0927-7757(96)03720-X, 1997.

25 Erlandsson, M., Oelkers, E. H., Bishop, K., Sverdrup, H., Belyazid, S., Ledesma, J. L. J., and Kohler, S. J.: Spatial and temporal variations of base cation release from chemical weathering on a hillslope scale. *Chem. Geol.*, 441, 1-13, 2016.

Fahad, Z. A., Bolou-Bi, E. B., Kohler, S. J., Finlay, R. D., and Mahmood, S.: Fractionation and assimilation of Mg isotopes by fungi is species dependent, *Env. Microbiol. Rep.*, 8, 956-965, 2016.

30 Ferris, F. G., Wiese, R. G., and Fyfe, W. S.: Precipitation of carbonate minerals by microorganisms – Implications for silicate weathering and the global carbon-dioxide budget, *Geomicrobiol. J.*, 12, 1-13, 1994.

Field, K. J., Cameron, D. D., Leake, J. R., Tille, S., Bidartondo, M. I., and Beerling, D. J.: Symbiotic options for the conquest of land, *Nat. Commun.*, 3, ARTN 835, 2012.

35 Field, K. J., Davidson, S. J., Alghamadi, S. A. and Cameron, D. D.: Magnitude, dynamics and control of carbon flow to mycorrhizas, in: *Mycorrhizal Mediation of Soil Fertility, Structure, and Carbon Storage*, edited by: Johnson, N. C., Gehring, C., and Jansa, J.: Elsevier, Amsterdam. 375-393. ISBN:978-0-12-8043127, 2017

Finlay, R. D., Wallander, H., Smits, M., Holmstrom, S., Hees, P. V., Lian, B., Rosling, A.: The role of fungi in biogenic weathering in boreal forest soils, *Fung. Biol. Rev.*, 4, 101-106, 2009.

40 Finlay, R. D., and Clemmensen, K. E.: Immobilization of carbon in mycorrhizal mycelial biomass and secretions, in: *Mycorrhizal Mediation of Soil Fertility, Structure, and Carbon Storage*, edited by: Johnson, N. C., Gehring, C., and Jansa, J.: Elsevier, Amsterdam. 413-440. ISBN:978-0-12-8043127, 2017

Flemming, H. C., and Wingender, J.: The biofilm matrix, *Nat. Rev. Microbiol.*, 8, 623-633, 2010.

Flemming, H. C., Wingender, J., Szewzyk, U., Steinberg, P., Rice, S. A., and Kjelleberg, S.: Biofilms: an emergent form of bacterial life, *Nat. Rev. Microbiol.*, 14, 563-575, 2016.

Fomina, M., Burford, E. P., Hillier, S., Kierans, M., and Gadd, G. M.: Rock-building fungi, *Geomicrobiol. J.*, 27, 624-629, 2010.

5 Futter, M. N., Klaminder, J., Lucas, R. W., Laudon, H., and Kohler, S. J.: Uncertainty in silicate mineral weathering rate estimates: source partitioning and policy implications, *Environ. Res. Lett.*, 7, Artn 024025, 2012.

Gadd, G. M.: Metals, minerals and microbes: geomicrobiology and bioremediation, *Microbiology*, 156, 609–643, 2010.

10 Gadd, G. M.: Microbial roles in mineral transformations and metal cycling in the Earth's critical zone, *Mol. Env. Soil Sci.*, 115-165, 2013a.

Gadd, G. M.: Geomycology: Fungi as agents of biogeochemical change. *Biology and Environment, Proc. Roy. Irish Acad.*, 113b(2), 139-153, 2013b

Gadd, G. M.: Fungi, rocks, and minerals, *Elements*, 13, 171-176, 2017.

15 Gazzè, S. A., Saccone, L., Ragnarsdottir, K. V., Smits, M. M., Duran, A. L., Leake, J. R., Banwart, S. A., and McMaster, T. J.: Nanoscale channels on ectomycorrhizal-colonized chlorite: Evidence for plant-driven fungal dissolution, *J. Geophys. Res-Biogeo.*, 117, Artn G00n09, 2012.

Gazzè, S. A., Saccone, L., Smits, M. M., Duran, A. L., Leake, J. R., Banwart, S. A., Ragnarsdottir, K. V., and McMaster, T. J.: Nanoscale observations of extracellular polymeric substances deposition on phyllosilicates by an ectomycorrhizal fungus, *Geomicrobiol. J.*, 30, 721-730, 2013.

20 Gazze, S. A., Stack, A. G., Ragnarsdottir, K. V., and McMaster, T. J.: Chlorite topography and dissolution of the interlayer studied with atomic force microscopy, *Am. Mineral.*, 99, 128-138, 2014.

Gleeson, D. B., Clipson, N., Melville, K., Gadd, G. M., and McDermott, F.P.: Mineralogical control of fungal community structure in a weathered pegmatitic granite, *Microb. Ecol.*, 50, 360–368, 2005.

Gorbushina, A. A.: Life on the rocks, *Env. Microbiol.*, 9, 1613–1631, 2007.

25 Goudie, A. S., and Viles, H. A.: Weathering and the global carbon cycle: Geomorphological perspectives, *Earth-Sci. Rev.*, 113, 59-71, 2012.

Griffiths, R.P., Baham, J.E., and Caldwell, B.A.: Soil solution chemistry of ectomycorrhizal mats in forest soil, *Soil Biol. Biochem.*, 26, 331-337, 1994.

30 Grube, M., Cernava, T., Soh, J., Fuchs, S., Aschenbrenner, I., Lassek, C., Wegner, U., Becher, D., Riedel, K., Sensen, C. W., and Berg, G.: Exploring functional contexts of symbiotic sustain within lichen-associated bacteria by comparative omics, *ISME J*, 9, 412-424, 2015.

Guennoc, C. M., Rose, C., Labbe, J., and Deveau, A.: Bacterial biofilm formation on the hyphae of ectomycorrhizal fungi: a widespread ability under controls?, *FEMS Microbiol. Ecol.*, 94, ARTN fify09310.1093/femsec/fiy093, 2018.

35 Hartmann, J., and Moosdorf, N.: Chemical weathering rates of silicate-dominated lithological classes and associated liberation rates of phosphorus on the Japanese Archipelago - Implications for global scale analysis, *Chem. Geol.*, 287, 125–157, 2011.

Hazen, R. M., Papineau, D., Leeker, W. B., Downs, R. T., Ferry, J. M., McCoy, T. J., Sverjensky, D. A., and Yang, H. X.: Mineral evolution, *Am. Mineral.*, 93, 1693-1720, 2008.

40 Hibbett, D., Gilbert, L., and Donoghue, M.: Evolutionary instability of ectomycorrhizal symbiosis in basidiomycetes. *Nature*, 407, 506–508, 2000.

Hindshaw, R. S., Reynolds, B. C., Wiederhold, J. G., Kretzschmar, R., and Bourdon, B.: Calcium isotopes in a proglacial weathering environment: Damma glacier, Switzerland, *Geochim. Cosmochim. Acta*, 75, 106-118, 2011.

Hodkinson, B. P., Gottel, N. R., Schadt, C. W., and Lutzoni, F.: Photoautotrophic symbiont and geography are major factors affecting highly structured and diverse bacterial communities in the lichen microbiome, *Environ Microbiol*, 14, 147-161, 2012.

Hoffland, E., Giesler, R., Jongmans, T., and van Breemen, N.: Increasing feldspar tunneling by fungi across a north Sweden podzol chronosequence, *Ecosystems*, 5, 11-22, 2002.

Hoffland, E., Giesler, R., Jongmans, A. G., and van Breemen, N.: Feldspar tunneling by fungi along natural productivity gradients, *Ecosystems*, 6, 739-746, 2003.

Hoffland, E., Kuyper, T. W., Wallander, H., Plassard, C., Gorbushina, A. A., Haselwandter, K., Holmstrom, S., Landeweert, R., Lundstrom, U. S., Rosling, A., Sen, R., Smits, M. M., van Hees, P. A., and van Breemen, N.: The role of fungi in weathering, *Front. Ecol. Environ.*, 2, 258-264, 2004.

Högberg, P., Nordgren, A., Buchmann, N., Taylor, A. F. S., Ekblad, A., Högberg, M. N., Nyberg, G., Ottosson-Lofvenius, M., and Read, D. J.: Large-scale forest girdling shows that current photosynthesis drives soil respiration, *Nature*, 411, 789-792, 2001.

Högberg, M. N., and Högberg, P.: Extramatrical ectomycorrhizal mycelium contributes one-third of microbial biomass and produces, together with associated roots, half the dissolved organic carbon in a forest soil, *New Phytol.*, 154, 791-795, 2002.

Holmden, C., and Belanger, N.: Ca isotope cycling in a forested ecosystem, *Geochim. Cosmochim. Acta*, 74, 995-1015, 2010.

Holmstrom, S. J. M., Lundstrom, U. S., Finlay, R. D., and Van Hees, P. A. W.: Siderophores in forest soil solution, *Biogeochemistry*, 71, 247-258, 2004.

Howard, R.J., Ferrari, M.A., Roach, D.H., and Money, N.P.: Penetration of hard substrates by a fungus employing enormous turgor pressures, *Proc Nat. Acad. Sci. USA*, 88, 11281-11284, 1991.

Huang, K. J., Teng, F. Z., Wei, G. J., Ma, J. L., and Bao, Z. Y.: Adsorption- and desorption-controlled magnesium isotope fractionation during extreme weathering of basalt in Hainan Island, China, *Earth Planet. Sc. Lett.*, 359, 73-83, 2012.

Hutchens, E.: Microbial selectivity on mineral surfaces: possible implications for weathering processes, *Fung. Biol. Rev.*, 23, 115-121, 2010.

Jilling, A., Keiluweit, M., Contosta, A. R., Frey, S., Schimel, J., Schnecker, J., Smith, R. G., Tiemann, L., and Grandy, A. S.: Minerals in the rhizosphere: overlooked mediators of soil nitrogen availability to plants and microbes, *Biogeochemistry*, 139, 103-122, 2018.

Johansson, E. M., Fransson, P. M. A., Finlay, R. D., and van Hees, P. A. W.: Quantitative analysis of soluble exudates produced by ectomycorrhizal roots as a response to ambient and elevated CO₂, *Soil Biol. Biochem.*, 41, 1111-1116, 2009.

Jones, D. L., Nguyen, C., and Finlay, R. D.: Carbon flow in the rhizosphere: carbon trading at the soil-root interface, *Plant Soil*, 321, 5-33, 2009.

Jongmans, A. G., van Breemen, N., Lundstrom, U., van Hees, P. A. W., Finlay, R. D., Srinivasan, M., Unestam, T., Giesler, R., Melkerud, P. A., and Olsson, M.: Rock-eating fungi, *Nature*, 389, 682-683, 1997.

Kalinowski, B. E., Liermann, L. J., Brantley, S. L., Barnes, A., and Pantano, C. G.: X-ray photoelectron evidence for bacteria-enhanced dissolution of hornblende, *Geochim. Cosmochim. Acta*, 64, 1331-1343, 2000.

Keiluweit, M., Bougoure, J. J., Nico, P. S., Pett-Ridge, J., Weber, P. K., and Kleber, M.: Mineral protection of soil carbon counteracted by root exudates, *Nat Clim Change*, 5, 588-595, 2015.

Klaminder, J., Lucas, R. W., Futter, M. N., Bishop, K. H., Kohler, S. J., Egnell, G., and Laudon, H.: Silicate mineral weathering rate estimates: Are they precise enough to be useful when predicting the recovery of nutrient pools after harvesting?, *For. Ecol. Manag.*, 261, 1-9, 2011.

Koele, N., Dickie, I. A., Oleksyn, J., Richardson, S. J., and Reich, P. B.: No globally consistent effect of ectomycorrhizal status on foliar traits, *New Phytol*, 196, 845-852, 2012.

Koele, N., Dickie, I. A., Blum, J. D., Gleason, J. D., and de Graaf, L.: Ecological significance of mineral weathering in ectomycorrhizal and arbuscular mycorrhizal ecosystems from a field-based comparison, *Soil Biol. Biochem.*, 69, 63-70, 2014.

Kohler A, Kuo A, Nagy LG, Morin E, Barry KW, Buscot F, et al.: Convergent losses of decay mechanisms and rapid turnover of symbiosis genes in mycorrhizal mutualists, *Nat. Genet.*, 47, 410-415, 2015.

Kohler, P., Hartmann, J., and Wolf-Gladrow, D. A.: Geoengineering potential of artificially enhanced silicate weathering of olivine, *Proc. Natl. Acad. Sci. USA*, 107, 20228-20233, 2010.

Kraemer, S. M., Duckworth, O. W., Harrington, J. M., and Schenkeveld, W. D. C.: Metallophones and trace metal bio-geochemistry, *Aquatic Geochem.*, 21, 159-195, 2014.

Kronnäs, V., Akselsson, C., and Belyazid, S.: Dynamic modelling of weathering rates – the benefit over steady-state modelling, *Soil*, 5, 33-47, 2019.

Kump, L. R.: The rise of atmospheric oxygen, *Nature*, 451, 277-278, 2008.

Lambers, H., Raven, J.A., Shaver, G.R., and Smith, S.E.: Plant nutrient-acquisition strategies change with soil age, *Trends Ecol. Evol.*, 23, 95-103, 2008.

Lambers, H., Mougel, C., Jaillard, B., and Hinsinger, P.: Plant-microbe-soil interactions in the rhizosphere: an evolutionary perspective, *Plant Soil*, 321, 83-115, 2009.

Landeweert, R., Hofflund, E., Finlay, R. D., and van Breemen, N.: Linking plants to rocks: Ectomycorrhizal fungi mobilize nutrients from minerals, *Trends Ecol. Evol.*, 16, 248-254, 2001.

Lawrence, C., Harden, J., and Maher, K.: Modeling the influence of organic acids on soil weathering, *Geochim. Cosmochim. Acta*, 139, 487-507, 2014.

Leake, J. R., Duran, A. L., Hardy, K. E., Johnson, I., Beerling, D. J., Banwart, S. A., and Smits, M. M.: Biological weathering in soil: the role of symbiotic root-associated fungi biosensing minerals and directing photosynthate-energy into grain-scale mineral weathering, *Min. Mag.*, 72, 85-89, 2008.

Leake, J. R. and Read, D. J.: in. Mycorrhizal symbioses and pedogenesis throughout Earth's history. in: *Mycorrhizal Mediation of Soil Fertility, Structure, and Carbon Storage*, edited by: Johnson, N. C., Gehring, C., and Jansa, J.: Elsevier, Amsterdam. 9-33. ISBN:978-0-12-8043127, 2017.

Lehmann, J., and Kleber, M.: The contentious nature of soil organic matter, *Nature*, 528, 60-68, 10.1038/nature16069, 2015.

Li, Z.B., Liu, L.W., Chen, J., and Teng, H.H.: Cellular dissolution at hypha- and spore- mineral interfaces revealing unrecognized mechanisms and scales of fungal weathering. *Geology* 44, 319-322, 2016.

Lian, B., Wang, B., Pan, M., Liu, C. Q., and Teng, H. H.: Microbial release of potassium from K-bearing minerals by thermophilic fungus *Aspergillus fumigatus*, *Geochim. Cosmochim. Acta*, 72, 87-98, 2008.

Lian, B., Chen, Y., and Tang, Y. A.: Microbes on Carbonate Rocks and Pedogenesis in Karst Regions, *J. Earth Sci.-China*, 21, 293-296, 2010.

Lian, B., Yuan, D. X., and Liu, Z. H.: Effect of microbes on karstification in karst ecosystems, *Chinese Sci. Bull.*, 56, 3743-3747, 2011.

5 Lindahl, B. D., Ihrmark, K., Boberg, J., Trumbore, S. E., Hogberg, P., Stenlid, J., and Finlay, R. D.: Spatial separation of litter decomposition and mycorrhizal nitrogen uptake in a boreal forest, *New Phytol.*, 173, 611-620, 2007.

Lindahl, B. D., and Tunlid, A.: Ectomycorrhizal fungi – potential organic matter decomposers, yet not saprotrophs, *New Phytol.*, 205, 1443-1447, 2015.

10 Liu, H. L., and Lian, B.: Quantitative evaluation of different fractions of extracellular polymeric substances derived from *Paenibacillus mucilaginosus* against the toxicity of gold ions, *Coll. Surf. B: Biointerfaces*, 175:195-201, 2019.

Liu, Y. P., Sun, Q. B., Li, J., and Lian, B.: Bacterial diversity among the fruit bodies of ectomycorrhizal and saprophytic fungi and their corresponding hyphosphere soils, *Sci. Rep.*, 8, ARTN 11672, 2018.

15 Luo, G. M., Ono, S. H., Beukes, N. J., Wang, D. T., Xie, S. C., and Summons, R. E.: Rapid oxygenation of Earth's atmosphere 2.33 billion years ago, *Sci. Adv.*, 2, UNSP e160013410.1126/sciadv.1600134, 2016.

Ma, J. F., Ryan, P. R., and Delhaize, E.: Aluminium tolerance in plants and the complexing role of organic acids, *Trends Plant Sci.*, 6, 273-278, 2001.

20 Maher, K.: The dependence of chemical weathering rates on fluid residence time, *Earth Planet. Sci. Lett.*, 294, 101–110, 2010.

Martin, F., Kohler, A., Murat, C., Veneault-Fourrey, C., and Hibbett, D. S.: Unearthing the roots of ectomycorrhizal symbioses. *Nat. Rev. Microbiol.*, 14, 760–773, 2016.

25 Martino, E., Perotto, S., Parsons, R., and Gadd, G. M.: Solubilization of insoluble inorganic zinc compounds by ericoid mycorrhizal fungi derived from heavy metal polluted sites, *Soil Biol. Biochem.*, 35, 133-141, 2003.

Marupakula, S., Mahmood, S., and Finlay, R. D.: Analysis of single root tip microbiomes suggests that distinctive bacterial communities are selected by *Pinus sylvestris* roots colonized by different ectomycorrhizal fungi, *Env. Microbiol.*, 18, 1470-1483, 2016.

Marupakula, S., Mahmood, S., Jernberg, J., Nallanchakravarthula, S., Fahad, Z. A., and Finlay, R. D.: Bacterial microbiomes of individual ectomycorrhizal *Pinus sylvestris* roots are shaped by soil horizon and differentially sensitive to nitrogen addition, *Env. Microbiol.*, 19, 4736-4753, 2017.

30 Mavromatis, V., Prokushkin, A. S., Pokrovsky, O. S., Viers, J., and Korets, M. A.: Magnesium isotopes in permafrost-dominated Central Siberian larch forest watersheds, *Geochim. Cosmochim. Acta*, 147, 76-89, 2014.

McLoughlin, N., Staudigel, H., Furnes, H., Eickmann, B., and Ivarsson, M.: Mechanisms of microtunneling in rock substrates: distinguishing endolithic biosignatures from abiotic microtunnels, *Geobiology*, 8, 245-255, 2010.

McMaster, T. J.: Atomic Force Microscopy of the fungi-mineral interface: applications in mineral dissolution, weathering and biogeochemistry, *Curr. Opin. Biotech.*, 23, 562-569, 2012.

35 Mitchell, A. C., Lafreniere, M. J., Skidmore, M. L., and Boyd, E. S.: Influence of bedrock mineral composition on microbial diversity in a subglacial environment, *Geology*, 41, 855-858, 2013.

Moldan, F., Stadmark, J., Fölster, J., Jutterström, S., Futter, M. N., Cosby, B. J., and Wright, R. F.: Consequences of intensive forest harvesting on the recovery of Swedish lakes from acidification and on critical load exceedances, *Sci. Tot. Environ.*, 603, 562-569, 2017.

40 Montross, S.N., Skidmore, M., Tranter, M., Kivimaki, A.L., and Parkes, R.J.: A microbial driver of chemical weathering in glaciated systems, *Geology*, 41, 215-218, 2013.

Moreau, D., Bardgett, R. D., Finlay, R. D., Jones, D. L., and Philippot, L.: A plant perspective on nitrogen cycling in the rhizosphere, *Funct. Ecol.*, 33, 540–552, 2019.

5 Morris, J.L., Leake, J.R., Stein, W.E., Berry, C.M., Marshall, J.E.A., Wellman, C.H., Milton, A., Hillier, S., Mannolini, F., Quirk, J., and Beerling, D.J.: Investigating Devonian trees as geoengineers of past climates: linking palaeosols to palaeobotany and experimental geobiology, *Palaeontology* 58, 787–801, 2015.

Neaman, A., Chorover, J., and Brantley, S.L.: Effects of organic ligands on granite dissolution in batch experiments at pH 6. *Amer. J. Sci.*, 306, 451–473, 2006.

10 Nicolás, C., Martin-Bertelsen, T., Floudas, D., Bentzer, J., Smits, M., Johansson, T., Troein, C., Persson, P., and Tunlid, A.: The soil organic matter decomposition mechanisms in ectomycorrhizal fungi are tuned for liberating soil organic nitrogen, *ISME J.*, 13, 977–988, 2019.

Ochs, M.: Influence of humified and non-humified natural organic compounds on mineral dissolution, *Chem. Geol.*, 132, 119–124, 1996.

15 Opfergelt, S., Burton, K. W., Georg, R. B., West, A. J., Guicharnaud, R. A., Sigfusson, B., Siebert, C., Gislason, S. R., and Halliday, A. N.: Magnesium retention on the soil exchange complex controlling Mg isotope variations in soils, soil solutions and vegetation in volcanic soils, Iceland, *Geochim. Cosmochim. Acta*, 125, 110–130, 2014.

Pagani, M., Caldeira, K., Berner, R., and Beerling, D. J.: The role of terrestrial plants in limiting atmospheric CO₂ decline over the past 24 million years, *Nature*, 460, 85–94, 2009.

20 Page, B. D., Bullen, T. D., and Mitchell, M. J.: Influences of calcium availability and tree species on Ca isotope fractionation in soil and vegetation, *Biogeochemistry*, 88, 1–13, 2008.

Paris, F., Bonnaud, P., Ranger, J., and Lapeyrie F.: In vitro weathering of phlogopite by ectomycorrhizal fungi. I. Effect of K⁺ and Mg²⁺ deficiency on phyllosilicate evolution, *Plant Soil*, 177, 191–201, 1995.

25 Paris, F., Botton, B., and Lapeyrie, F.: In vitro weathering of phlogopite by ectomycorrhizal fungi. 2. Effect of K⁺ and Mg²⁺ deficiency and N sources on accumulation of oxalate and H⁺, *Plant Soil*, 179, 141–50, 1996.

Perakis, S. S., and Pett-Ridge, J. C.: Nitrogen-fixing red alder trees tap rock-derived nutrients, *Proc. Natl. Acad. Sci. USA*, 116, 5009–5014, 2019.

25 Phelan, J., Belyazid, S., Kurz, D., Guthrie, S., Cajka, J., Sverdrup, H., and Waite R.: Estimation of soil base cation weathering rates with the PROFILE model to determine critical loads of acidity for forested ecosystems in Pennsylvania, USA: Pilot application of a potential national methodology. *Water Air Soil Poll.*, 225, 2014.

30 Philippot, L., Raaijmakers, J. M., Lemanceau, P., and van der Putten, W. H.: Going back to the roots: the microbial ecology of the rhizosphere, *Nat. Rev. Microbiol.*, 11, 789–799, 2013.

Pogge von Strandmann, P. A. E., Burton, K. W., James, R. H., van Calsteren, P., Gislason, S. R., and Sigfusson, B.: The influence of weathering processes on riverine magnesium isotopes in a basaltic terrain, *Earth Planet. Sc. Lett.*, 276, 187–197, 2008.

35 Povak, N.A., Hessburg, P.F., McDonnell, T.C., Reynolds, K.M., Sullivan, T.J., Salter, R.B., and Cosby, B.J.: Machine learning and linear regression models to predict catchment-level base cation weathering rates across the southern Appalachian Mountain region, USA, *Water Resour. Res.*, 50, 2798–2814, 2014.

Price, J.R., Peresolak, K., Brice, R.L., and Tefend, K.S.: Temporal variability in the chemical weathering of Ca²⁺-bearing phases in the Loch Vale watershed, Colorado, USA: A mass-balance approach, *Chem. Geol.*, 342, 151–166, 2013.

40 Querejeta, J. I., Egerton-Warburton, L. M., and Allen, M. F.: Direct nocturnal water transfer from oaks to their mycorrhizal symbionts during severe soil drying, *Oecologia*, 134, 55–64, 2003.

Quirk, J., Beerling, D. J., Banwart, S. A., Kakonyi, G., Romero-Gonzalez, M. E., and Leake, J. R.: Evolution of trees and mycorrhizal fungi intensifies silicate mineral weathering, *Biol. Lett.*, 8, 1006-1011, 2012.

Quirk, J., Andrews, M. Y., Leake, J. R., Banwart, S. A., and Beerling, D. J.: Ectomycorrhizal fungi and past high CO₂ atmospheres enhance mineral weathering through increased below-ground carbon-energy fluxes, *Biol. Lett.*, 10, ARTN 20140375, 2014.

Quirk, J., Leake, J. R., Banwart, S. A., Taylor, L. L., and Beerling, D. J.: Weathering by tree-root-associating fungi diminishes under simulated Cenozoic atmospheric CO₂ decline, *Biogeosciences*, 11, 321-331, 2014.

Quirk, J., Leake, J. R., Johnson, D. A., Taylor, L. L., Saccone, L., and Beerling, D. J.: Constraining the role of early land plants in Palaeozoic weathering and global cooling, *Proc. Roy. Soc. B-Biol. Sci.*, 282, ARTN 20151115, 2015.

Redfield, G. W.: Atmospheric deposition of phosphorus to the everglades: concepts, constraints and published deposition rates for ecosystem management, *Sci. World J.*, 2, 1843-1873, 2002.

Reichard, P. U., Kraemer, S. M., Frazier, S. W., and Kretzschmar, R.: Goethite dissolution in the presence of phytosiderophores: Rates, mechanisms, and the synergistic effect of oxalate, *Plant Soil*, 276, 115-132, 2005.

Remiszewski, K.A., Bryce, J.G., Fahnstock ,M.F., Pettitt, E.A., Blichert-Toft, J., Vadeboncoeur, M.A., and Bailey, S.W.: Elemental and isotopic perspectives on the impact of arbuscular mycorrhizal and ectomycorrhizal fungi on mineral weathering across imposed geologic gradients, *Chem. Geol.*, 445, 164-171, 2016.

Retallack, G. J.: Early forest soils and their role in Devonian global change, *Science*, 276, 583-585, 1997.

Roelandt, C., Goddérus, Y., and Bonnet, M.: Coupled modeling of biospheric and chemical weathering processes at the continental scale, *Glob. Biogeochem. Cycles*, 24, GB2004, (doi:10.1029/2008GB003420), 2010.

Rosenstock, N. P., Berner, C., Smits, M. M., Kram, P., and Wallander, H.: The role of phosphorus, magnesium and potassium availability in soil fungal exploration of mineral nutrient sources in Norway spruce forests, *New Phytol.*, 211, 542-553, 2016.

Rosling, A., Lindahl, B. D., and Finlay, R. D.: Carbon allocation to ectomycorrhizal roots and mycelium colonising different mineral substrates, *New Phytol.*, 162, 795-802, 2004.

Rosling, A., Roose, T., Herrmann, A. M., Davidson, F. A., Finlay, R. D., and Gadd, G. M.: Approaches to modelling mineral weathering by fungi, *Fung. Biol. Rev.*, 23, 138-144, 2009.

Ryan, M. H., Tibbett, M., Edmonds-Tibbett, T., Suriyagoda, L. D. B., Lambers, H., Cawthray, G. R., and Pang, J.: Carbon trading for phosphorus gain: the balance between rhizosphere carboxylates and arbuscular mycorrhizal symbiosis in plant phosphorus acquisition, *Plant Cell Environ.*, 35, 2170-2180, 2012.

Ryu, J. S., Jacobson, A. D., Holmden, C., Lundstrom, C., and Zhang, Z. F.: The major ion, delta Ca-44/40, delta Ca-44/42, and delta Mg-26/24 geochemistry of granite weathering at pH=1 and T=25 degrees C: power-law processes and the relative reactivity of minerals, *Geochim. Cosmochim. Acta*, 75, 6004-6026, 2011.

Saccone, L., Gazze, S. A., Duran, A. L., Leake, J. R., Banwart, S. A., Ragnarsdottir, K. V., Smits, M. M., and McMaster, T. J.: High resolution characterization of ectomycorrhizal fungal-mineral interactions in axenic microcosm experiments, *Biogeochemistry*, 111, 411-425, 2012.

Savage, V. J., Chopra, I. and O'Neill, A. J.: *Staphylococcus aureus* biofilms promote horizontal transfer of antibiotic resistance, *Antimicrob. Agents Chemother.*, 57, 1968-1970, 2013.

Schmalenberger, A., Duran, A. L., Bray, A. W., Bridge, J., Bonneville, S., Benning, L. G., Romero-Gonzalez, M. E., Leake, J. R., and Banwart, S. A.: Oxalate secretion by ectomycorrhizal *Paxillus involutus* is mineral-specific and controls calcium weathering from minerals, *Sci. Rep.*, 5, ARTN 12187, 2015.

Seiffert, F., Bandow, N., Bouehez, J., von Blanckenburg, F., and Gorbushina, A. A.: Microbial colonization of bare rocks: laboratory biofilm enhances mineral weathering, *Procedia Earth Planet. Sci.*, 10, 123-129, 2014.

Shen, B., Jacobsen, B., Lee, C. T. A., Yin, Q. Z., and Morton, D. M.: The Mg isotopic systematics of granitoids in continental arcs and implications for the role of chemical weathering in crust formation, *Proc. Natl. Acad. Sci. USA*, 106, 20652-20657, 2009.

Sigurbjornsdottir, M. A., Andresson, O. S., and Vilhelmsen, O.: Analysis of the *Peltigera membranacea* metagenome indicates that lichen-associated bacteria are involved in phosphate solubilization, *Microbiol-SGM*, 161, 989-996, 2015.

Simonsson, M., Bergholm, J., Olsson, B., von Brömssen, C., and Öborn, I.: Estimating weathering rates using base cation budgets in a Norway spruce stand on podzolised soil: Analysis of fluxes and uncertainties, *For. Ecol. Manag.*, 340, 135-152, 2015.

Smith, S. E. and Read, D. J.: *Mycorrhizal Symbiosis*, 3rd ed., Academic Press, Amsterdam, London, 2008.

Smits, M. M., Bonneville, S., Haward, S., and Leake, J. R.: Ectomycorrhizal weathering, a matter of scale?, *Mineral. Mag.*, 72, 131-134, 2008.

Smits, M. M., Bonneville, S., Benning, L. G., Banwart, S. A., and Leake, J. R.: Plant-driven weathering of apatite – the role of an ectomycorrhizal fungus, *Geobiology*, 10, 445-456, 2012.

Smits, M. M.: Scale matters? Exploring the effect of scale on fungal-mineral interactions, *Fung. Biol. Rev.*, 23, 132-137, 2009.

Smits, M. M., Hoffland, E., Jongmans, A. G., and van Breemen, N.: Contribution of mineral tunneling to total feldspar weathering, *Geoderma*, 125, 59-69, 2005.

Smits, M. M., Johansson, L., and Wallander, H.: Soil fungi appear to have a retarding rather than a stimulating role on soil apatite weathering, *Plant Soil.*, 385, 217-228, 2014.

Smits, M. M. and Wallander, H.: Role of mycorrhizal symbiosis in mineral weathering and nutrient mining from soil parent material, in: *Mycorrhizal Mediation of Soil Fertility, Structure, and Carbon Storage*, edited by Johnson, N. C., Gehring, C., and Jansa, J.: Elsevier, Amsterdam. 35-46. ISBN:978-0-12-8043127, 2017.

Sokolova, T. A., Tolpeshta, I. I., and Topunova, I. V.: Biotite weathering in podzolic soil under conditions of a model field experiment. *Euras. Soil Sci.*, 43, 1150-1158, 2010.

Söderström, B.E.: Seasonal fluctuations of active fungal biomass in horizons of a podzolized pine-forest soil in central Sweden, *Soil Biol. Biochem.*, 11, 149-154, 1979.

Stendahl, J., Akselsson, C., Melkerud, P. A., and Belyazid, S.: Pedon-scale silicate weathering: comparison of the PROFILE model and the depletion method at 16 forest sites in Sweden. *Geoderma*, 211, 65-74, 2013.

Sterkenburg, E., Clemmensen, K. E., Ekblad, A., Finlay, R. D., and Lindahl, B. D.: Contrasting effects of ectomycorrhizal fungi on early and late stage decomposition in a boreal forest, *ISME J.*, 12, 2187-2197, 2018.

Sun, Q. B., and Lian, B.: The different roles of *Aspergillus nidulans* carbonic anhydrases in wollastonite weathering accompanied by carbonation, *Geochim. Cosmochim. Acta*, 244, 437-450, 2019.

Sun, Q., Li, J., Finlay, R. D., and Lian, B.: Oxalotrophic bacteria assemblages in the ectomycorrhizosphere and their effects on oxalate degradation and carbon fixation potential, *Chem. Geol.*, 514, 54-65, 2019a.

Sun, Q., Ziyu, F., Finlay, R. D., and Lian, B.: Transcriptome analysis provides novel insights into the response of the ectomycorrhizal fungus *Amanita pantherina* to weather K-containing feldspar and apatite, *Appl. Environ. Microbiol.*, 85, e00719-19, 2019b.

Sun, Y. P., Unestam, T., Lucas, S. D., Johanson, K. J., Kenne, L., and Finlay, R.: Exudation-reabsorption in a

mycorrhizal fungus, the dynamic interface for interaction with soil and soil microorganisms, *Mycorrhiza*, 9, 137-144, 1999.

Sverdrup, H.: Chemical weathering of soil minerals and the role of biological processes, *Fung. Biol. Rev.*, 23, 94-100, 2009.

5 Taylor, L., Banwart, S., Leake, J., and Beerling, D. J.: Modeling the evolutionary rise of ectomycorrhiza on sub-surface weathering environments and the geochemical carbon cycle, *Am. J. Sci.*, 311, 369-403, 2011.

Taylor, L. L., Banwart, S. A., Valdes, P. J., Leake, J. R., and Beerling, D. J.: Evaluating the effects of terrestrial ecosystems, climate and carbon dioxide on weathering over geological time: a global-scale process-based approach, *Phil. Trans. R. Soc. London Ser. B*, 367, 565-582, 2012.

10 Taylor, L. L., Quirk, J., Thorley, R. M. S., Kharecha, P. A., Hansen, J., Ridgwell, A., Lomas, M. R., Banwart, S. A., and Beerling, D. J.: Enhanced weathering strategies for stabilizing climate and averting ocean acidification, *Nat. Clim. Change*, 6, 402-406, 2016.

15 Thorley, R. M. S., Taylor, L. L., Banwart, S. A., Leake, J. R., and Beerling, D. J.: The role of forest trees and their mycorrhizal fungi in carbonate rock weathering and its significance for global carbon cycling, *Plant Cell Environ.*, 38, 1947-1961, 2015.

Tipper, E. T., Gaillardet, J., Louvat, P., Capmas, F., and White, A. F.: Mg isotope constraints on soil pore-fluid chemistry: Evidence from Santa Cruz, California, *Geochim. Cosmochim. Acta*, 74, 3883-3896, 2010.

Toljander, J., Lindahl, B., Paul, L., Elfstrand, M., and Finlay, R. D.: Influence of arbuscular mycorrhizal mycelial exudates on soil bacterial growth and community structure, *FEMS Microbiol. Ecol.*, 61, 295-304, 2007.

20 Tuason, M. M. S. and Arocena, J. M.: Calcium oxalate biomineralization by *Piloderma fallax* in response to various levels of calcium and phosphorus, *Appl. Environ. Microbiol.*, 75, 7079- 7085, 2009.

Turpault, M.-P., Nys, C., and Calvaruso, C.: Rhizosphere impact on the dissolution of test minerals in a forest ecosystem. *Geoderma* 153, 147-154, 2009.

25 Uhlig, D., Schuessler, J. A., Bouchez, J., Dixon, J. L., and von Blanckenburg, F.: Quantifying nutrient uptake as driver of rock weathering in forest ecosystems by magnesium stable isotopes, *Biogeosciences*, 14, 3111-3128, 2017.

Uroz, S., Oger, P., Lepleux, C., Collignon, C., Frey-Klett, P., and Turpault, M. P.: Bacterial weathering and its contribution to nutrient cycling in temperate forest ecosystems, *Res. Microbiol.*, 162, 820-831, 2011.

30 Uroz, S., Turpault, M. P., Delaruelle, C., Mareschal, L., Pierrat, J. C., and Frey-Klett, P.: Minerals affect the specific diversity of forest soil bacterial communities, *Geomicrobiol. J.*, 29, 88-98, 2012.

Uroz, S., Kelly, L. C., Turpault, M. P., Lepleux, C., and Frey-Klett, P.: The mineralosphere concept: Mineralogical control of the distribution and function of mineral-associated bacterial communities, *Trends Microbiol.*, 23, 751-762, 2015.

35 van Breemen, N., Finlay, R., Lundstrom, U., Jongmans, A. G., Giesler, R., and Olsson, M.: Mycorrhizal weathering: A true case of mineral plant nutrition ?, *Biogeochemistry*, 49, 53-67, 2000.

van der Heijden, G., Bel, J., Craig, C. A., Midwood, A. J., Mareschal, L., Ranger, J., Dambrine, E., and Legout, A.: Measuring plant-available Mg, Ca, and K pools in the soil-an isotopic dilution assay, *ACS Earth Space Chem.*, 2, 292-313, 2018.

40 van Hees, P. A. W., Vinogradoff, S. I., Edwards, A. C., Godbold, D. L., and Jones, D. L.: Low molecular weight organic acid adsorption in forest soils: effects on soil solution concentrations and biodegradation rates, *Soil Biol. Biochem.*, 35, 1015-1026, 2003.

van Hees, P. A. W., Jones, D. L., Finlay, R., Godbold, D. L., and Lundström, U. S.: The carbon we do not see – the impact of low molecular weight compounds on carbon dynamics and respiration in forest soils: a review, *Soil Biol. Biochem.*, 37, 1-13, 2005.

5 van Hees, P. A. W., Rosling, A., Essen, S., Godbold, D. L., Jones, D. L., and Finlay, R. D.: Oxalate and ferricrocins exudation by the extramatrical mycelium of an ectomycorrhizal fungus in symbiosis with *Pinus sylvestris*, *New Phytol.*, 169, 367-377, 2006.

van Schöll, L., Hoffland, E., and van Breemen, N.: Organic anion exudation by ectomycorrhizal fungi and *Pinus sylvestris* in response to nutrient deficiencies, *New Phytol.*, 170, 153-163, 2006a.

10 van Schöll, L., Smits, M.M., and Hoffland, E.: Ectomycorrhizal weathering of the soil minerals muscovite and hornblende, *New Phytol.*, 171, 805–814, 2006b.

Vaario, L. M., Pennanen, T., Lu, J. R., Palmen, J., Stenman, J., Leveinen, J., Kilpelainen, P., and Kitunen, V.: *Tricholoma matsutake* can absorb and accumulate trace elements directly from rock fragments in the shiro, *Mycorrhiza*, 25, 325-334, 2015.

15 Vandenkoornhuyse, P., Quaiser, A., Duhamel, M., Le Van, A., and Dufresne, A.: The importance of the microbiome of the plant holobiont, *New Phytol.*, 206, 1196-1206, 2015.

Verrecchia, E. P., Braissant, O., and Cailleau, G.: The oxalate-carbonate pathway in soil carbon storage: the role of fungi and oxalotrophic bacteria. In *Fungi in Biogeochemical Cycles*, edited by Gadd, G. M., Cambridge University Press, Cambridge. 289-310. 2006.

20 Wallander, H., Johansson, L., and Pallon, J.: PIXE analysis to estimate the elemental composition of ectomycorrhizal rhizomorphs grown in contact with different minerals in forest soil, *FEMS Microbiol. Ecol.*, 39, 147-156, 2002.

Wallander, H., Hagerberg, D., and Aberg, G.: Uptake of Sr-87 from microcline and biotite by ectomycorrhizal fungi in a Norway spruce forest, *Soil Biol. Biochem.*, 38, 2487-2490, 2006.

25 Wang, W. Y., Lian, B., and Pan, L.: An RNA-sequencing study of the genes and metabolic pathways involved in *Aspergillus niger* weathering of potassium feldspar, *Geomicrobiol. J.*, 32, 689-700, 2015.

Watmough, S. A., and Dillon, P. J.: Mycorrhizal weathering in base-poor forests, *Nature*, 423, 823-824, 2003.

Wilcke, W., Velescu, A., Leimer, S., Bigalke, M., Boy, J., and Valarezo, C.: Biological versus geochemical control and environmental change drivers of the base metal budgets of a tropical montane forest in Ecuador during 15 years, *Biogeochemistry*, 136, 167-189, 2017.

30 Wild, B., Daval, D., Beaulieu, E., Pierret, M.-C., Viville, D., and Imfeld, G.: In-situ dissolution rates of silicate minerals and associated bacterial communities in the critical zone (Strengbach catchment, France), *Geochim. Cosmochim. Acta*, 249, 95-120, 2019.

Wild, B., Imfeld, G., Guyot, F., and Daval, D.: Early stages of bacterial community adaptation to silicate aging, *Geology* 46, 555-558, 2018.

35 Wimpenny, J., Gislason, S. R., James, R. H., Gannoun, A., Pogge Von Strandmann, P. A. E., and Burton, K. W.: The behaviour of Li and Mg isotopes during primary phase dissolution and secondary mineral formation in basalt, *Geochim. Cosmochim. Acta*, 74, 5259-5279, 2010.

Winnick, M.J., and Maher, K.: Relationships between CO₂, thermodynamic limits on silicate weathering, and the strength of the silicate weathering feedback, *Earth Planet. Sci. Lett.*, 485, 111–120, 2018.

40 Xiao, B., Lian, B., Sun, L.L., and Shao, W. L.: Gene transcription response to weathering of K-bearing minerals by *Aspergillus fumigatus*, *Chem. Geol.*, 306-307, 1-9, 2012.

Xiao, L. L., Sun, Q. B., Yuan, H. T., and Lian, B.: A practical soil management to improve soil quality by applying mineral organic fertilizer, *Acta Geochim.*, 36, 198-204, 2017.

5 Xiao, L. L., Hao, J. C., Wang, W. Y., Lian, B., Shang, G. D., Yang, Y. W., Liu, C.Q., and Wang, S.J.: The up-regulation of carbonic anhydrase genes of *Bacillus mucilaginosus* under soluble Ca^{2+} deficiency and the heterologously expressed enzyme promotes calcite dissolution. *Geomicrobiol. J.*, 31, 632-641, 2014.

Xiao, L. L., Lian, B., Hao, J. C., Liu, C. Q., and Wang, S. J.: Effect of carbonic anhydrase on silicate weathering and carbonate formation at present day CO_2 concentrations compared to primordial values. *Sci. Rep.*, 5, 7733, 2015.

10 Zetterberg, T., Olsson, B.A., Löfgren, S., Hyvönen, R., and Brandtberg, P. O.: Long-term soil calcium depletion after conventional and whole-tree harvest, *For. Ecol. Manag.*, 369, 102–115, 2016.

Zhang, L., Fan, J., Ding, X., He, X., Zhang, F., and Feng, G.: Hyphosphere interactions between an arbuscular mycorrhizal fungus and a phosphate solubilizing bacterium promote phytate mineralization in soil, *Soil Biol. Biochem.*, 74, 177-183, 2014.

15 Zhang, L., Xu, M., Liu, Y., Zhang, F., Hodge, A., and Feng, G.: Carbon and phosphorus exchange may enable cooperation between an arbuscular mycorrhizal fungus and a phosphate-solubilizing bacterium, *New Phytol.*, 210, 1022–1032, 2016.

Zimorski, V., Ku, C., Martin, W. F., and Gould, S.B.: Endosymbiotic theory for organelle origins, *Curr. Opin. Microbiol.*, 22, 38–48, 2014.



a**b**

Fig. 1. (a) Schematic diagram showing biofilm structure and function, and the biological and chemical processes that biofilms influence. **(b)** Extracellular polymeric substance (EPS) halos and their possible influence on interactions between hypha and mineral surfaces (based on observations by Gazzè et al., 2013). (**Fig. 1a** reproduced with permission; Flemming et al.: Nat. Rev. Microbiol., 14, 563-575, 2016.)




Fig. 2. The flow of plant-derived carbon through fungal hyphae to organic and inorganic substrates drives biogeochemical processes such as decomposition and weathering and influences patterns of C release and sequestration into stable organic and inorganic forms. Carbon is assimilated by plants (a) and transferred directly to symbiotic mycorrhizal hyphae that transfer nutrients mobilised by the hyphae back to their hosts (b). Products of mycelial respiration are released to the atmosphere (c). The fungal secretome (d) consists of different labile compounds that can be translocated to different organic or inorganic substrates. These compounds may be released into an extracellular polysaccharide matrix (e) or as droplets that condition the hyphosphere, facilitating interactions with bacteria (f). Hydrolytic and oxidative enzymes (g) mobilize N and P from plant-derived organic substrates (h) or microbial necromass (i). Peptides and antibiotics play important roles in signalling and influencing microbiome structure (j), sugars and polyols maintain osmotic gradients and hyphal turgor (k) and low molecular weight organic acids and siderophores influence the mobilization of P and base cations from minerals (l). Long term sequestration and stabilization of carbon can take place in recalcitrant organic substrates (m) and secondary minerals and mineraloids (n). (Reproduced with permission; Finlay, R. D. and Clemmensen, K.: Immobilization of carbon in mycorrhizal mycelial biomass and secretions, in: Mycorrhizal Mediation of Soil: Fertility, Structure and Carbon Storage, edited by: Johnson, N. C., Gehring, K., and Jansa, J.: Elsevier, Amsterdam. pp 413-440, 2017. ISBN:978-0-12-8043127)




Fig. 3. Schematic diagram summarizing an evolutionary perspective of interactions involving mineral weathering and decomposition. Current rates of mineral weathering have been influenced by different ‘events’ and processes, including the effects of biological processes on mineral evolution (**a**), serial endosymbiosis (**b**), enabling the evolution of higher plants, mycorrhizal symbiosis (**c**) enabling increasing colonization of substrates by roots and mycorrhizal mycelium (**d**), leading to more efficient nutrient uptake and larger amounts of photosynthetic tissue (**e**). The evolution of ectomycorrhizal fungi (ECM) has enabled efficient extraction of N and P from recalcitrant organic material (**f**) powered by higher C allocation and better colonization of organic and mineral substrates (**f & g**). Note the time-scale of the most recent 500 M years is expanded by a factor of approximately eight.




Fig. 4. The effects of evolutionary advancement in plants and mycorrhizas in the geochemical carbon cycle, increasing the weathering of calcium (Ca)-, phosphorus (P)-, and silicon (Si)-bearing minerals and generating clays. Plants and their mycorrhizal fungi have increased the rates of dissolution of continental silicates especially calcium silicate (CaSiO_3), and apatite (Ca phosphate- CaPO_4), but a portion of the Ca, P, and Si released from rocks is washed into the oceans where these elements increase productivity. Some of the Ca and P end up in limestone and chalk deposits produced by marine organisms such as corals and foraminifera, thereby sequestering carbon dioxide (CO_2) that was dissolved in the oceans into calcium carbonate (CaCO_3) rock for millions of years. Dissolved Si is used in sponges, radiolarians, and diatoms that can accumulate on the sea floor. The ocean sediments are recycled by subduction or uplift by tectonic forces, with volcanic degassing and eruptions of base-rich igneous rocks such as basalt returning Ca, P, Si, and other elements back to the continents, thereby reinvigorating ecosystems with new nutrient supplies through weathering. Note for simplicity that magnesium is not shown in the figure, but follows parallel pathways to Ca and is co-involved in sequestering CO_2 into dolomitic limestones. **aq**, liquid state; **g**, gaseous state. (Reproduced with permission: Leake, J. R. and Read, D. J.: Mycorrhizal Symbioses and Pedogenesis Throughout Earth's History. in: Mycorrhizal Mediation of Soil: Fertility, Structure and Carbon Storage. edited by: Johnson, N. C., Gehring, K., and Jansa, J.: Elsevier, Amsterdam. pp 9-33, 2017. ISBN:978-0-12-8043127)




Fig. 5. Bivariate plots of $\delta^{26}\text{Mg}$ (‰) versus Mg concentration (mg g^{-1}) in mycelia of ectomycorrhizal and nonmycorrhizal fungi grown on mineral free Modified Melin-Norkrans (MMN) medium amended with granite particles. The fungi were grown on cellophane membranes covering the growth substrates in Petri dish microcosms. Open blue symbols represent nonmycorrhizal fungi and closed brown symbols represent ectomycorrhizal fungi. (Reproduced with permission; Fahad et al.: Env. Microbiol. Rep., 8, 956-965, 2016.)




Fig. 6. Mesocosms containing reconstructed podzol soil profiles with different amounts of organic (O) horizon material to simulate different intensities of forest harvesting. **(a)** no O horizon, **(b)** 50% thickness O horizon, **(c)** Normal (100%) thickness O horizon, **(d)** 150% thickness O horizon. The histograms show levels of enrichment of ^{26}Mg in soil solution extracted from the O (organic), E (eluvial) and B (illuvial) horizons. The upper part of each diagram represents systems incubated without plants, the lower part of each diagram represents systems containing *Pinus sylvestris* seedlings (as illustrated). Note that the seedling growth is proportional to the amount of organic soil, from which ectomycorrhizal fungi mobilize N. The enrichment of ^{26}Mg in the soil solution becomes greater and greater with increasing plant growth (and therefore increasing Mg uptake) – but only in the B horizon, because there is discrimination against uptake of the heavy isotope. This suggests that the B horizon is the primary site of active mineral weathering and Mg uptake. Extensive colonization of roots, organic and mineral substrates by ectomycorrhizal mycelia is visible. Horizontal scale bar in **(a)** = 5 cm.